



NOV-20¢

# POPULAR SCIENCE

MONTHLY

**HOW FLYERS BREATHE AT  
EXTREME HIGH ALTITUDES**  
PAGE 77

*When Russia Fights Japan* PAGE 65





# Straight steer

*by Fisher*

*The Army-Navy "E" flies above three Fisher plants for excellence in aircraft production and from two others for tank production, while the Navy "E," with three stars, is flown by still another Fisher plant for its naval ordnance work.*

**T**WO amazing instruments — the gyro horizon and the directional gyro — help to give the American bombardier his big moment. Both are designed by Sperry Gyroscope, and built by Sperry and Fisher Body.

In precision flying, these delicate indicating instruments help a pilot to keep on his designated target. In blind flying or night flying they help him keep the true course to his objective.

Precision beyond anything ever attempted by Fisher is a "must" in their manufacture. Rare and special skills are necessary every step of the way.

**Craftsmanship gave us the answer, just as it gave us the answer to bomber, tank and anti-aircraft gun problems.**

**Craftsmanship has never yet let us down.**

And today you may be certain that as long as there's a micrometer and a microscope left in the world, our men will do their best to give their brothers in the air a straight steer — by Fisher.



**ARMAMENT  
BODY BY**

*Fisher*



# "Sure I helped make that 80,000,000 mile road test of synthetic passenger car tires"

*says Aetna Welfare Nurse*



HERE'S HOW HUNDREDS OF LEADING COMPANIES AND CAR OWNERS JOINED IN MAKING THE GREATEST AUTOMOBILE TIRE ROAD TEST OF ALL TIME—MONTHS BEFORE PEARL HARBOR.

One morning three years ago this Aetna Life Insurance Company nurse noticed a new kind of tire on her car. "It's a test," the maintenance man said. "Those tires are more than half synthetic Ameripol." So she drove them and made her report. And hundreds of other passenger car owners did the same thing—testing these B. F. Goodrich tires for a total of 80,000,000 miles.



Today we're making tires in which 99% of the natural rubber has been replaced by "GR-S" synthetic from government plants. And the experience gained in that first test has helped us to make them dependable, high-quality tires.

Some of these tires are now available for car owners who qualify, but most of our synthetic rubber production is still needed to supply our armed forces. The "rubber crisis" is very real—and very present. So it's still patriotic to save your present tires—and not to drive a single needless mile.

A few of the many companies that helped make this test

American Can Co.  
Baltimore & Ohio Railroad  
The Borden Co.  
General Outdoor Advertising Co.  
General Baking Co.  
Gulf Oil Corporation

Geo. A. Hormel & Co.  
Kellogg Company  
New York Telephone Co.  
Pet Milk Sales Corp.  
Railway Express Agency  
Secony-Vacuum Oil Co.  
Standard Brands, Inc.



Awards to 7 plants

*In war or peace*  
**B.F. Goodrich**  
**FIRST IN RUBBER**



NOVEMBER, 1943

Buy War Savings Bonds and Stamps regularly.



# Completely at Sea

## ABOUT WHAT BATTERY TO BUY?



### BUY THE BATTERY THAT IS THE CHOICE OF EXPERTS

Why not let the experts help chart your course when you buy your next battery?

A million-mile, trans-ocean flying record has just been established by a Pan American Clipper equipped with Auto-Lite batteries. Auto-Lite batteries, too, are specified for service with our fighting

forces in tanks, half-tracks, jeeps . . . wherever dependable power counts most.

Make sure you get the longer life . . . the extra power you need today. Make your next battery an Auto-Lite—specified as original equipment by leading automotive engineers.

**TOLEDO, 1 AUTO-LITE BATTERY CORPORATION OHIO**

Manufacturing Plants at: Niagara Falls, Indianapolis, Atlanta, Oakland, Oklahoma City, Toronto

**BACK THE ATTACK WITH WAR BONDS**



The "Million-Mile" Pan-American Clipper uses AUTO-LITE Batteries for its ocean-spanning record-breaking flights.

AUTO-LITE Batteries have been proved under fire on every fighting front.



**AUTO-LITE**  
means  
**AUTO-LITE**

# AUTO-LITE BATTERIES

Popular Science Monthly for November, 1943, Volume 143, Number 5. Published monthly at 350 Fourth Avenue, New York 10, N. Y., by Popular Science Publishing Co., Inc. Entered as second-class matter Dec. 2, 1918, at the Post Office at New York under the act of March 3, 1879; additional entry as second-class matter at Dayton, Ohio. Yearly subscriptions in the United States, \$2.00.



# INCREASE YOUR

# "FIRE POWER"

## ON THE PRODUCTION FRONT!



**You** can increase your "fire power" on the production front—and increase your chances for prosperity in tomorrow's victory-world—by enrolling right now for a low-cost, short-term War Course with the International Correspondence Schools.

I. C. S. War Courses are not just textbooks—they are a combination of profusely illustrated texts written by recognized practical authorities and edited specially for home study. Lessons are examined by members of the I. C. S. staff of trained teachers, whose methods are approved by leading educators.

Find out now how simple it is to get sound, practical I. C. S. training in a short time, at surprisingly low cost. The coupon will bring you complete information, without obligation. Mail it today!

**LEARN MORE—  
TO PRODUCE MORE—  
TO INSURE YOUR FUTURE!**

## INTERNATIONAL CORRESPONDENCE SCHOOLS

HELPING TO TRAIN AMERICANS FOR VICTORY

BOX 7443-K, SCRANTON 9, PENNA.

Gentlemen: Please send me (without cost or obligation) full information regarding the Special War Course which I have marked X:

- ☐ Accounting
- ☐ Air Pilot
- ☐ Airplane Drafting
- ☐ Architecture
- ☐ Aviation Engines
- ☐ Aviation Mechanics
- ☐ Bookkeeping
- ☐ Carpentry
- ☐ Chemistry
- ☐ Civil Engineering
- ☐ Cost Accounting
- ☐ Diesel Engines
- ☐ Electrical Engineering
- ☐ Foremanship

- ☐ Gas and Electric Welding
- ☐ High School
- ☐ Industrial Electrical Engineering
- ☐ Internal Combustion Engines
- ☐ Machinist's Apprenticeship
- ☐ Machine Shop
- ☐ Managing Men at Work
- ☐ Mechanical Drawing
- ☐ Mechanical Engineering
- ☐ Mold Loft Work
- ☐ Motor Boat Navigation
- ☐ Plastics
- ☐ Plumbing and Heating

- ☐ Practical Electricity
- ☐ Radio
- ☐ Reading Blueprints
- ☐ Secretarial
- ☐ Sheet Metal
- ☐ Ship Drafting
- ☐ Ship Fitting
- ☐ Shop Practice
- ☐ Structural Engineering
- ☐ Surveying and Mapping
- ☐ Textiles
- ☐ Tool Designing
- ☐ Toolmaking
- ☐ Traffic Management

My name..... My age.....

My present job..... Length of time with present employer.....

The "job ahead" for which training would fit me.....

My address..... City..... State.....

SPECIAL  
TUITION RATES  
FOR MEMBERS  
OF THE  
ARMED FORCES





# POPULAR SCIENCE

FOUNDED 1872

MONTHLY

VOL. 143 NO. 5

Mechanics & Handicraft

A TECHNICAL JOURNAL OF SCIENCE AND INDUSTRY

## CONTENTS for NOVEMBER, 1943

Cover: Kodachrome by Lieut. C. D. Pierce,  
Courtesy U. S. Army Air Forces

### News

Our New Theory of Air Power.....	49
Knocking Out the U-Boats.....	54
How to Navigate a Raft.....	57
When Russia Fights Japan.....	65
The Iron Horse Saves the Day.....	73
Demand Oxygen System for Flyers....	77
New Jobs for Fused Quartz.....	82
Ditching a Flying Fortress.....	84
Brain-Teasers in Uniform.....	89
You Can "See" the Weather.....	90
"Ghost Light" Goes to War.....	98
Facts About Your Ears.....	102
Secret of Our Air Gunnery.....	112
Putting the Heat on the Axis.....	118
Propellers for Our Warplanes.....	122

### Automobiles

Checking Generator Regulators.....	128
Useful Auto Hints.....	131
Gus Wilson Deals in Opposites.....	132

### — Home and Workshop

Dutch Colonial Settle Table.....	HW 513
Servicing Fire Extinguishers.....	HW 524
Filmless Photography Is Fun.....	HW 530
Attachments for Your Bandsaw.....	HW 536
Old Sewing Machine Modernized....	HW 540
How a Spur Gear Is Milled.....	HW 548
Electric Furnace for Shop Use.....	HW 554
How a Vacuum-Tube Grid Works.....	HW 556
Magical Tricks with Chemistry.....	HW 565

## PUTTING THE PRECISION IN PRECISION BOMBING

OUR bombardiers' boast that they can "hit a pickle barrel at 10,000 feet" is backed up by a mathematical and mechanical miracle. When a bomb is dropped from a plane traveling 200 miles an hour, miles above the earth, it is a job for an Einstein to figure just where it is going to land. Good as they are, our bombardiers are not expected to be mathematical wizards. Their amazing skill in picking off enemy factories, rail yards, and military installations is due to the wonderful tool with which they have been provided—the precision bombsight. You may have wondered how this Axis-beating instrument works. An article in our December issue will explain the complicated mathematical problems involved and the ingenious mechanism that solves them.

EDITOR . . . . . Charles McLendon  
ASSISTANT EDITOR . . . . . Arthur Wakeling  
HOME & WORKSHOP EDITOR . . . . . Harry Walton  
ART EDITOR . . . . . Carsten Grande

EDITORIAL ASSOCIATES: Fred O. Newman, news editor; Alden P. Armagnac, B. T. Richards, Harry Samuels, Michele de Santis, Don Romero, Jack O'Brien, Jean Ackermann, Frank Rowsome, Jr.

ART ASSOCIATES: Stewart Rouse, William Patrick, Samuel Dukler, Evelyn Cooper.

PHOTOGRAPHY: W. W. Morris, Robert F. Smith.

Published monthly at 353 Fourth Avenue, New York 10, N. Y., by Popular Science Publishing Co., Inc. Godfrey Hammond, President and Treasurer; R. C. Wilson, Raymond J. Brown, Charles McLendon, Stephen P. Glennon, Vice-Presidents; F. W. Briggs, Secretary. Entered as second-class matter Dec. 18, 1918, at the Post Office at New York under the act of March 3, 1879; additional entry as second-class matter at Dayton, Ohio. Entered as second-class matter at the Post Office Department, Canada. Printed in U.S.A. Copyright, 1943, by Popular Science Publishing Co., Inc. All rights reserved in the United States, Great Britain, and in all countries participating in the International Copyright Convention and the Pan American Copyright Convention. Yearly subscriptions to United States and its possessions, \$2.00; Canada, \$2.50; foreign countries, excepting Canada, \$3.00. Subscribers must notify us of change of address four weeks in advance of the next publication date. Be sure to give both old and new address.





## **She Still Has "The Voice With A Smile"**

War traffic keeps her busier than ever but she manages to keep calm and pleasant.

She still has "The Voice With A Smile" even when the lights are thick on the Long Distance switchboard and the circuits are crowded. Even when she has to ask you to —

*"Please limit your call to 5 minutes. Others are waiting."*

That's to help everybody get better service and you couldn't ask for a better reason than that.

**BELL TELEPHONE SYSTEM**





# WILL YOU BE READY...



## When the Air Age Comes?

**Y**ou can be ready to enjoy the coming air age and fly your own Piper Cub . . . if you prepare yourself now!

Take aviation subjects at night school, study aeronautics at home. Then, when peacetime comes, see your Piper Dealer and learn to fly. He can solo you with as little as eight hours of dual instruction in a Piper Cub.

### Send Today for Your "HOW TO FLY" Booklet!



Prepared by a certificated flight instructor. Clearly explains basic flight principles. Send 10c for booklet and Piper catalog to cover postage-handling. Piper Aircraft Corporation, Dept. P8113, Lock Haven, Pennsylvania.

### 16mm. SOUND FILM

—"The Construction of a Light Airplane." For distribution points write: Supervisor, Audio-Visual Aids, Extension Services, Penna. State College, State College, Penna.



**PIPER** *Cub*  
POINTS THE WAY TO WINGS FOR ALL AMERICANS

## Coming Next Month

**GUN POWER** will make history when the Allied grand fleets force a showdown with the elusive Japanese Navy. The big rifles that speak from the turrets of our men-of-war are the most powerful instruments of destruction ever used at sea. Arthur Grahame tells how they evolved from the simple brass tubes that were the first naval artillery, 500 years ago.

**MOSQUITOES** have been bad in Berlin lately—not the kind that can be shoed away with a spray gun, either. They're nasty little British fighter-bombers made almost entirely of plywood and capable of hauling a troublesome amount of explosive at fighter-plane speeds. William S. Friedman tells you what you want to know about this scourge of the Nazis.

**THAT POSTWAR CAR** of yours—what will it look like, and how will it perform? When the automobile manufacturers get into production on new models, we can expect many radical changes. An article gives you a preview of the automobile of the near future—its design, its power plant, and the comforts and conveniences it will give the motorist. Don't miss this glimpse of the highways of tomorrow.

**INVENTORS ARE EXCITED** over proposed changes in our patent laws. Legislation before Congress would substitute "compulsory licensing" for the absolute control now enjoyed by inventors over their discoveries. You'll want to know the facts about this controversy. Would the proposed law remove the incentive that has made Yankee ingenuity proverbial throughout the world?

**STEEL IS THE STUFF** that will win the war. We hear a lot about guns, tanks, and ships, but they all go back to this raw material. To show you what steel is and where we get it, Alden P. Armagnac takes you on a tour of the flaming furnaces of "Victory Valley" on the Monongahela, one of the great steel-making centers that feed the "Arsenal of Democracy."

**WHEN YOU USE A LADDER**, be sure it is the right kind. Personal safety and good work both require it. If a ladder is just a ladder to you, it will pay you to read up on the subject. A practical article describes the different types, from the lowly stepladder to the long extension job, and tells which is best for each purpose.



# NOW! A NEW CARTOON CHARACTER FOR HOME PROJECTOR OWNERS!

**"kiko"**  
**THE KANGAROO**

8 mm 16 mm



Never before seen in 8mm. and 16mm. movies! Now! KIKO—funniest cartoon character yet—comes to your screen in fast-action movies. Wait until you see the children's glee at watching him! Here's new pleasure for every projector owner! Give the joy of "Kiko" films to your own family...to other projector-owning families! They're new! They're fun! They're something to own!

## 8 RIOTOUS SUBJECTS YOU CAN OWN

1. "The Big Fight"
2. "Cleaned Out"
3. "The Foxy Fox"
4. "Hail The King"
5. "Ostrich Troubles"
6. "On The Scent"
7. "Danger On Ice"
8. "Red Hot Rhythm"

©Terrytoons, Inc.



### "TRACK MEET THRILLS"

A thrill a second! Champion track men performing at their best! Pole vault! Broad jump! High jump! Discus! Hurdles! Other events! Own this movie now!

**ON SALE AT YOUR PHOTO DEALER NOW!**

<b>LOW COST</b>	8mm. 50 ft. . . . .	\$1.75
	8mm. Complete . . .	5.50
	16mm. 100 ft. . . . .	2.75
	16mm. Complete . . .	8.75
	16mm. Sound-On-Film	17.50



### CASTLE FILMS

RCA BLDG. FIELD BLDG. RUSS BLDG.  
NEW YORK, 20 CHICAGO, 3 SAN FRANCISCO, 4

Address  
Nearest Office

Please send FREE "KIKO" Catalog. Also Castle's new FREE De Luxe Film Catalog.

Name \_\_\_\_\_

Address \_\_\_\_\_

City \_\_\_\_\_ State \_\_\_\_\_

PR-11





**MIDWEST'S best and ONLY  
customer...TODAY!**



**T**HE French have a proverb—"The more things change, the more they are the same." How true that is of Midwest Radio! Once we counted satisfied Midwest Radio owners in hundreds of thousands . . . in every part of the globe. Today, we have only one customer—America's fighting man. But you'll find him, too, in every corner of the world—and, by his side, radio or electronic equipment, built by Midwest, giving him the same dependable performance that for 22 years has made Midwest Radios an international favorite.

When Victory is won, a new era in radio and electronics will open for you who have been forced to stand by while a greater need was being served. What this new era will bring, it would be foolish to conjecture. But, of this you can be certain—Midwest will be back again with highest quality radio receivers, and with Factory-To-You savings of up to 50%—as always!



**★ AT LEAST 10% IN WAR BONDS**  
**MIDWEST RADIO CORPORATION**  
Department 59-E CINCINNATI, OHIO

**★ SEND  
FOR  
FREE  
BOOKLET!**



A 24-page booklet "Radio—The Eyes and Ears of Our Armed Forces" will be sent **FREE** on your request if accompanied by 10c in stamps or coin for which we will send you a War Savings Stamp.





**E**VERY drafting board is a battlefield across which move tanks, guns, planes and ships. Every new weapon must pass through this design stage before it reaches production and moves on to the literal fighting fronts.

Learn now to fight as a *trained* draftsman and help your country while you help yourself.

Freedom to pick your own battlefield in fighting for success in life is one of your great heritages

as an American. And in choosing the drafting board, you know that big, well-paid jobs are to be won there. Thousands of successful men made their start in just that way.

Many of today's draftsmen will be among tomorrow's leaders. You can learn drafting—at low cost—by studying an I. C. S. Course in your spare time! Mail this coupon today and you're getting into communication with a real future.

## INTERNATIONAL CORRESPONDENCE SCHOOLS

HELPING TO TRAIN AMERICANS FOR VICTORY

BOX 7444-K, SCRANTON, PENNA.

Without cost or obligation, please send me booklet and full particulars about the course *before* which I have marked X:

**SPECIAL  
TUITION RATES  
FOR MEMBERS  
OF THE  
ARMED FORCES**



- ☐ Airplane Drafting
- ☐ Architectural Drafting
- ☐ Electrical Drafting
- ☐ Mechanical Drafting
- ☐ Ship Drafting
- ☐ Structural Drafting
- ☐ Blueprint Reading
- ☐ Air Brake
- ☐ Air Conditioning
- ☐ Architecture
- ☐ Automobile Tune-up
- ☐ Automobile Repair
- ☐ Aviation
- ☐ Aviation Mechanics
- ☐ Boiler Making

- ☐ Bridge Engineering
- ☐ Chemistry
- ☐ Civil Engineering
- ☐ Concrete Engineering
- ☐ Contracting and Building
- ☐ Cotton Manufacturing
- ☐ Diesel Engine
- ☐ Electrical Engineering
- ☐ Electrician
- ☐ Electrical Maintenance
- ☐ Equipment
- ☐ Heating
- ☐ Heat Treatment of Metals
- ☐ Highway Engineering
- ☐ House Planning

- ☐ Industrial Metallurgy
- ☐ Instrumental Engineering
- ☐ Machinist
- ☐ Inspector
- ☐ Management of Inventions
- ☐ Marine Engines
- ☐ Mechanical Engineering
- ☐ Mine Foreman
- ☐ Navigation
- ☐ Patternmaking
- ☐ Plastics
- ☐ Plumbing
- ☐ Public Works Engineering
- ☐ Pulp and Paper Making
- ☐ Radio, General
- ☐ Radio Operating
- ☐ Radio Servicing

- ☐ R. R. Section Foreman
- ☐ R. R. Signalman
- ☐ Refrigeration
- ☐ Sanitary Engineering
- ☐ Sheet Metal Work
- ☐ Shifting
- ☐ Ship Fitting
- ☐ Steam Engines
- ☐ Steam Fitting
- ☐ Surgeons Engineering
- ☐ Surveying and Mapping
- ☐ Telegraphy
- ☐ Telephony
- ☐ Textile Drafting
- ☐ Toolmaking
- ☐ Tread Design
- ☐ Welding Gas and Electric
- ☐ Woolen Manufacturing

- ☐ Accounting
- ☐ Advertising
- ☐ Bookkeeping
- ☐ Business Correspondence
- ☐ Business Management
- ☐ Cartooning
- ☐ Civil Service

- ☐ College Preparatory
- ☐ Commercial
- ☐ Commercial Illustrating
- ☐ Cost Accounting
- ☐ C. P. Accounting

- ☐ Business Courses
- ☐ First Year College
- ☐ Foremanship
- ☐ French
- ☐ German
- ☐ High School
- ☐ Managing Men at Work

- ☐ Railway Postal Clerk
- ☐ Salesmanship
- ☐ Secretarial
- ☐ Spanish
- ☐ Stenography and High Lettering
- ☐ Traffic Management

- ☐ Advanced Dressmaking
- ☐ Foods and Cookery

- ☐ Home Economics Courses
- ☐ Home Dressmaking
- ☐ Professional Dressmaking and Designing

- ☐ Tea Room and Cafeteria Management, Catering

Name..... Address.....

City..... State..... Postal Position.....

Canadian residents send coupon to International Correspondence Schools Canadian, Limited, Montreal, Canada.  
British residents send coupon to I. C. S., 1 Kingway, London, W. C. 2, England.







# LESSON FREE

## at Home in Spare Time to

# TECHNICIAN



### There is a Shortage of Radio Technicians. Many Good Jobs are Open!

There's a big shortage today of capable Radio Technicians and Operators. Fixing Radios pays better now than ever before. With new Radios out of production, fixing old sets which were formerly traded in, adds greatly to the normal number of service jobs.

Broadcasting Stations, Aviation and Police Radios and other Radio branches are scrambling for Operators and Technicians. Radio Manufacturers now working on Government orders for Radio equipment, employ trained men. The Government, too, needs hundreds of competent civilian and enlisted Radio men and women. You may never see a time again when it will be so easy to get started in this fascinating field.

### Be Ready to Cash in on Jobs Coming in Television, Electronics

Think of the NEW jobs that Television, Frequency Modulation, Electronics, and other Radio developments will open after the war! You have a real opportunity. I will train you to be ready to cash in when Victory releases the amazing wartime Radio developments for peacetime use!

### Many Beginners Soon Make \$5, \$10 a Week EXTRA in Spare Time

Right now, probably in your neighborhood, there's room for more spare and full time Radio Technicians. Many N.R.I. Students make \$5, \$10 a week EXTRA money fixing Radios in spare time while learning. I send EXTRA MONEY JOB SHEETS that tell how to do it! My "50-50 Method" - half building and testing real Radio Sets in half learning from easy-to-grasp, illustrated lessons. It's a tested, proved way to learn Radio at home in spare time. Think how much practical experience you'll get by building the Superber and Measuring Instrument illustrated at right - by conducting 50 sets of experiments on these and other Circuits you build with parts I supply! Within a few months you can be ready to run your own Spare Time Shop, fix the Radios of your friends and neighbors—get paid while learning!



### START NOW Toward Radio's Rich Rewards!

MAIL THE COUPON. I'll send you the FREE Lesson and my valuable, 64 page, illustrated book. They're packed with facts about Radio. You'll see snapshots and letters from men I trained, so you can know what N.R.I. did for others. You'll read a description of my Course—50-50 Method! A Experienced K to Extra Money Job Sheets. You'll have my free Lesson to keep. And you'll see many fascinating jobs Radio offers and how YOU can train at home. No obligation—no salesman will call! If you want to JUMP YOUR PAY—Mail Coupon in an envelope or pasted on penny post #1 J. E. SMITH, President, Dept. 3MP3, National Radio Institute, Washington-2, D. C.

TRAINING MEN FOR  
VITAL RADIO JOBS

**GOOD PAY**

### You Build These and Other Radio Circuits with 6 Big Kits I Send



A.M. SIGNAL-GENERATOR (above) Build it yourself! Provide amplitude-modulated signals for test and experimental purposes. Gives valuable practice!



### Good For Both 64 PAGE BOOK SAMPLE LESSON FREE

Mr. J. E. Smith, President, Dept. 3MP3  
NATIONAL RADIO INSTITUTE, Washington-2, D. C.


Mail me FREE, without obligation, your Sample Lesson and 64 page book "Win Rich Rewards in Radio." (No salesman will call. Please write plainly.)

Name \_\_\_\_\_ Age \_\_\_\_\_

Address \_\_\_\_\_

City \_\_\_\_\_ State \_\_\_\_\_ ZIP \_\_\_\_\_





# By These Signs -----

## Strange Keys to the Powers of the Universe

"GOD GEOMETRIZES," said an ancient sage. Within the straight line, curve, and angle—and their combinations—exist the forces of creation. These *secret symbols* contain the mysterious laws of the universe. Upon their right use—or the neglect of them—the success or failure of every human enterprise depends.

Have you a desire, something you wish to accomplish in life? Put your finger on a dot. In whatever direction you move your finger from the dot, you have made a beginning. Thus a dot is the symbol of *one*—or a beginning. Your desire then is also symbolized by *one*. If you follow the proper method or way to accomplish what you want, you have arrived at point *two*. Whenever these two symbols are brought together—the idea and the right way—you produce point *three*—the success of your plan. Success, therefore, is symbolized by the three equal sides of a *triangle*.

In planning your personal affairs—business, domestic, or the welfare of your family—do you use a *Cosmic formula*? Do you determine whether your acts are in accord with Divine truths eternally expressed in symbols? Why does the circle represent completion? Why is it said that a man is on the square? These

symbols are used by astronomers and scientists to prove the physical laws of the universe—why don't you apply them to the problems of your everyday world? Learn what symbols, as powers and forces of nature, you can simply and intelligently use in directing the course of your life.

Let the Rosicrucians (not a religious organization), a world-wide brotherhood of learning, reveal to you the symbolism of successful living.

### Let this GIFT BOOK Explain

If you want to prepare yourself through understanding for the greater rewards of life, write for the fascinating *free Sealed Book*. It explains how you may receive this age-old wisdom. Use the coupon below.

Scribe Y. A. K.  
THE ROSICRUCIANS, AMORC  
San Jose, California, U. S. A.

Please send me the Free, Sealed Book. I am interested in knowing how I may obtain the masterful Rosicrucian teachings.

Name.....

Address.....

.....



THE ROSICRUCIANS, AMORC - SAN JOSE, CALIFORNIA, U. S. A.



# 15 Minutes a Day!

*Give me just this  
and I'll prove I can make you*  
**A NEW MAN!**

I'M "trading-in" old bodies for new! I'm taking men who know that the condition of their arms, shoulders, chests and legs—their strength, "wind," and endurance—is not 100%. And I'm making NEW MEN of them. Right now I'm even training hundreds of soldiers and sailors who KNOW they've got to get into shape FAST!

## Only 15 Minutes a Day!

Are you ALL MAN—tough-muscled, on your toes every minute, with all the up-and-at-'em that can lick your weight in wildcats? Or do you need the help I can give you—the help that has already worked such wonders for other fellows, everywhere?

All the world knows I was ONCE a skinny, scrawny 97-lb. weakling. And NOW it knows that I am the holder of the title, "The World's Most Perfectly Developed Man." How did I do it? How do I work miracles with the bodies of other men in only 15 minutes a day? The answer is "Dynamic Tension," the amazing method I discovered and which changed me from a 97-pound weakling into the champion you see here!

In just 15 minutes a day right in the privacy of your own home, I'm ready to prove that "Dynamic Tension" can lay a new outfit of solid muscle over every inch of your body. Let me put new, smashing power into your arms and shoulders—give you an armor-shield of stomach muscle—strengthen your legs into real columns of surging stamina. If lack of exercise or wrong living has weakened you inside, I'll get after that condition, too, and show you how it feels to LIVE!

## FREE This Famous Book that Tells You How to Get a Body that Men Respect and Women Admire

My book, "Everlasting Health and Strength," tells you exactly what "Dynamic Tension" can do. And it's packed with pictures that SHOW you what it does. RESULTS it has produced for other men. RESULTS I want to prove it can get for YOU! If you want to learn how you can actually become a NEW MAN, right in the privacy of your own home and in only 15 minutes a day, then man!—get this coupon into the mail to me as fast as your legs can get to the letterbox! CHARLES ATLAS, Dept. 111, 115 East 23rd St., New York 10, N. Y.

NOVEMBER, 1943

Buy War Savings Bonds and Stamps regularly.

*Charles  
Atlas*

—actual photo  
of the man  
who holds the  
title, "The  
World's Most  
Perfectly De-  
veloped Man."

Charles Atlas—America's  
Greatest "Builder of Men"

Among all the physical in-  
structors and "conditioners of  
men" ONLY ONE NAME  
STANDS OUT. That name is  
Charles Atlas!

In every part of the country  
Charles Atlas is recognized as  
"America's Greatest Builder of  
Men." Thousands upon thou-  
sands have put their physical  
development into his capable  
hands!

And now that the call is for  
men capable of helping Ameri-  
ca meet and conquer any na-  
tional emergency, many thou-  
sands of others (even those al-  
ready in their country's Army  
and Navy) are calling upon  
Charles Atlas to  
build the kind of  
men America vi-  
tally needs!

**MAIL THIS COUPON NOW!**

CHARLES ATLAS, Dept. 111  
115 East 23rd St., New York 10, N. Y.

I want the proof that your system of "Dynamic Tension" will help make a New Man of me—give me a healthy husky body and big muscular development. Send me your free book, "Everlasting Health and Strength."

Name . . . . .  
(Please print or write plainly)

Address . . . . .

City . . . . . State . . . . .

☐ Check here if under 16 for Booklet A.



# More GOOD JOBS in DRAFTING

In AIRCRAFT and other War Industries!



**Calls for Draftsmen Are Increasing! . . . Read the want-ads for proof of this urgent demand.**

This complete drawing outfit,—everything to work with,—including drafting table, drawing board, supplies, etc.,—**ALL SENT TO YOU AT NO EXTRA COST** if you are a Chicago Tech Student.

**Mail Coupon Below**

The War Production program has increased the demand for Aircraft Draftsmen, Machine Draftsmen, Architectural Draftsmen, Electrical Draftsmen, and Structural Draftsmen. The Draftsman always comes first on any new project in manufacturing and industry—peace or wartime.

## The Draftsman—"The Key Man" in War or Peacetime Industry

No new machines can be built, no airplanes constructed, no bridges or buildings erected, no ships or submarines launched until the draftsman has completed his work. Real immediate opportunities exist in Drafting—the profession upon which all construction is vitally dependent. Drafting is clean, interesting, well paid work. Steady employment. Investigate today what Drafting offers you! Help your country in a vital War production job on the important Home Front—and help yourself to a well paid job in Drafting.

## Learn in Spare Time,—at Home!

(or at the College in Chicago)

With our easy step-by-step lessons, (and the tools we furnish), you can learn in your spare time at home. Convenient terms. To prove to you how easy it is to learn Drafting by the Chicago Tech Method we'll send you a **Trial Lesson FREE**. No charge for this lesson either now or later. Send a post card or the coupon now for



**free**  
**TRIAL LESSON**  
**Send Coupon**

## CHICAGO TECHNICAL COLLEGE

P-219 Tech. Bldg., 2000 S. Michigan Ave., Chicago 16, Ill.

Yes,—please send me **FREE Trial Lesson in DRAFTING**

- |   |  |
|---|--|
| <input type="checkbox"/> Aircraft Drafting      | <input type="checkbox"/> Machine Drafting      |
| <input type="checkbox"/> Electrical Drafting    | <input type="checkbox"/> Structural Drafting   |
| <input type="checkbox"/> Architectural Drafting | <input type="checkbox"/> Building Construction |

Name

Address

City  State

Occupation  Age

# AVIATION

## FOR YOUR CAREER PLUS WAR SERVICE



*Both*

## AT THE SAME TIME

Before you are 18 **MAKE YOURSELF THE KIND OF MAN THE AVIATION INDUSTRY OR THE AIR SERVICES WANT . . . THE KIND THEY CANNOT DO WITHOUT . . .** so you can **ADVANCE RAPIDLY**. Since 1929, Curtiss Wright Tech has been specializing in modern and progressive training for Aeronautical Engineers and Master Aviation Mechanics. No lying involved! Write for full information. Include name, address and date of birth. Dept. PS-11

**CURTIS WRIGHT TECHNICAL INSTITUTE**

GRAND CENTRAL AIR TERMINAL  
Glendale (Los Angeles Co.) California

THE MOST ADVANCED AIRCRAFT MAINTENANCE SCHOOL OF AMERICA

## WAR OPPORTUNITIES for YOU in ACCOUNTING

War needs call for many new bookkeepers and accountants at good pay. Taxes and government regulations demand many extra in government offices and in industry. Enlarged plants need more. Also, many present accountants are being called to the armed services. This opens unusual opportunity to women and to men not subject to military call. And this opportunity will continue after the war is over.

You can prepare for these opportunities in spare time at home. Cost is moderate and easy terms can be arranged. For 34 years Laballe has been training accountants—over 2,000 C.P.A.'s among our alumni. Our training is condensed, practical, interesting. Instruction staff of full-time C.P.A.'s. You can take short course or full accountancy course. Free placement service.

Write today for free 48-page booklet, "Accountancy, the Profession That Pays." It describes the opportunities and requirements of this field and tells of our training.

Please send me your free booklet, "Accountancy, the Profession That Pays," and information about your training.



Name  Age

Address

City and State

**LASALLE EXTENSION UNIVERSITY**  
**A Correspondence Institution**

Dept. 1183-M CHICAGO, ILL.



# INVENTORS

## NOW Is the Time to PATENT and SELL Your Invention

Now, more than ever before, is the right time to patent your invention. Why? Because manufacturers everywhere presently engaged in war production are looking ahead to the future by buying up patent rights now, so they will have new and attractive items to make and sell for civilian consumption as soon as the war is over. This is what happened during and after the last war. Hence, the smart thing for you to do is to look ahead to the future too. Protect your invention by applying for a patent now, so you will be in position to cash in on an outright sale, or on the royalties your invention will bring.

### Patent Guide Shows What To Do

Our "Patent Guide for the Inventor" answers many important questions concerning Patents that inventors constantly ask. It tells what facts, details, drawings, sketches, etc. are necessary to apply for a Patent; how to protect your invention through dated and witnessed disclosure; how to do this AT ONCE to safeguard your rights; how Patent Office Records can be checked to determine whether the invention is probably patentable before filing fees need be paid; discusses costs involved and a practical way these can be paid as the application progresses. It tells how some inventors secured financial backing, how many simple inventions have proved large commercial successes, how Patents covering improvements also can be profitably utilized and marketed; tells countless other facts of interest.

### Why You Need Expert Assistance

The Patent Laws were enacted for your benefit—to give you protection for the features of your invention which are Patentable. But these features must be legally and concisely set forth in the form of "claims." This phase of the procedure is so complex that the Patent Office advises the inventor to engage a competent Registered Patent Attorney. We maintain a large staff—carefully trained registered patent attorneys—expert draftsmen—experienced searchers—to serve you. We have been serving inventors for more than 20 years.

### Take First Step Now

With the Patent Guide you will receive also Free a "Record of Invention" form which will enable you at once to establish the date of your invention, before you file your Patent application. This step costs you nothing yet may be vital to your success. Remember—in Patent Matters, ACTION IS IMPORTANT. Delay can be costly. Mail the coupon in an envelope, or paste it on a penny postcard NOW.

**CLARENCE A. O'BRIEN & HARVEY B. JACOBSON**

*"Worthy of your Trust"*


Registered Patent Attorneys

32-L Adams Building  
Washington, D. C.

*Get This*  
**FREE BOOK**

**IMMEDIATELY MAIL COUPON TODAY!**

*Get*  
**FREE  
COPY**



**CLARENCE A. O'BRIEN  
& HARVEY B. JACOBSON**

CLARENCE A. O'BRIEN & HARVEY B. JACOBSON

Registered Patent Attorneys before the United States Patent Office

32-L Adams Building, Washington, D. C.

Please send me your 48-Page "Patent Guide for the Inventor" and your specially prepared "Record of Invention" form FREE. This request does not obligate me.

Name

Address

City  State

(Please write or print plainly.)



# Readers Say:

## Sailors Had an Easier Way of Doing It in 1897

ON PAGE 72 of your August issue, you give a vision-range formula that has been worked out by the Clipper captains of Pan American Airways. The formula is to multiply the square root of the plane's altitude by 1.225,

the result being the distance that a pilot can see. Some time around 1897 I read an engineering handbook that said something to this effect: "Any intelligent officer of a ship knows that the square root of 1.5 multiplied by the height of the eye in feet is the distance of the visible horizon." I have experi-

I GUESS THAT WILL HOLD YOU, YOU SKY LUBBER!



mented with both formulas, and I find that they give approximately the same results—only I think that the older one is easier to work with and to remember. I've remembered it for over 40 years.—W. H., Cranbrook, B. C., Canada.

## Perhaps Recent Jap Reverses Are Responsible

THE LETTER of M. L. H., of Levering, Mich. in the September issue, may have been intended as a humorous contribution to your Readers Say columns, but it does not alter the fact that water that is allowed to drain undisturbed from a bathtub or similar container, will always swirl counterclockwise. Naturally, if a person puts his hand in the swirl and swings it around clockwise, he can reverse the direction of the swirl. Incidentally, here is a question I would like to put to M. L. H. If he should ever travel south of the Equator—in the South Pacific area, for example—he will find that draining water al-

ways swirls clockwise. Perhaps he can tell me why?—G. E. B., Niagara Falls, N. Y.

## Hearty Approval of P.S.M.'s Two-Purpose Back Cover

HAS ANYONE ever complimented you on your back cover, which makes such a handy marker for reading? If no one has, allow me to. I find it a special convenience, and sincerely hope that you have no intention of discontinuing this feature. I have been taking POPULAR SCIENCE for more years than I care to remember. I start at the front cover and plow straight through it. I invariably enjoy every issue.—G. M., Dover, Fla.

## A Good Steer—Straight from the Manufacturer

THE ARTICLE on page 129 of your September issue covering the adjustment of our automobile steering gear was naturally of great interest to us. We should like to point out, however, that to eliminate end play in the roller shaft of the Gemmer gear, the adjustment should be made with the steering wheel in mid position, as when driving straight ahead. The design of the Gemmer gear is such as to permit adjustment for wear in the center of the worm without causing binding either side of the center. If adjustment is made either side of center, however, the gear may bind in the mid position. Any backlash at either end will cause no trouble because the gears are under thrust when in the turning position.—G. B., Gemmer Manufacturing Co., Detroit, Mich.

## A Torpedoed Midshipman Gets Us Right Side Up

WHILE reading through the July issue, I noticed in your article, "These Are the Badges of Courage," that your photograph of the three-striped Torpedoed Seaman Bar is upside down. The light blue stripe, representing the sky, should be at the top, and the dark blue stripe, representing the water, should be at the bottom. The red stripe in the middle stands for the action encountered. I've checked this carefully so that I am pretty sure that I've got it right. At any rate, that is the way I wear the one that was issued to me.—Cadet Midshipman W. A. P., U. S. Merchant Marine Academy, Kings Point, L. I., N. Y.

You're perfectly right, W. A. P.—and thanks. All we can say is that we're glad we at least got the red stripe in the right place.—Ed.





You can't  
see it . . .  
but it's there



**T**HE MOST ACCURATELY machined rotating part ever built—although apparently in balance to the naked eye—may be *out of balance*.

*You can't see the unbalance . . . even if it's there.*

With the rapid development of high-speed machines, the need for *locating and correcting* unbalance in rotating parts has become vitally important—if you want smooth, vibration-free operation and long life.

In 1933, scientists in the Westinghouse Research Laboratories tackled this problem of quickly and accurately measuring the *static and dynamic unbalance* in rapidly whirling masses—both symmetric and asymmetric.

Through painstaking study and experiment, these Westinghouse research en-

gineers discovered a totally new principle for balancing rotating parts of every shape and form . . . the "Dynetric Balancer."

Today, the Gisholt Dynetric Balancer . . . using Westinghouse *electronic equipment* . . . is solving the most difficult balancing problems in many war plants.

With this machine, vibrations as small as *twenty five millionths* of an inch in crankshafts, armatures, turbine rotors, propellers, and countless other whirling parts are located and measured in a matter of minutes, or even seconds!

Westinghouse Electric & Manufacturing Co., Pittsburgh, Pennsylvania.

**Westinghouse**  
PLANTS IN 25 CITIES . . . OFFICES EVERYWHERE



# Readers Say:

## A Lost Poem Finds Its Author

I HAVE just noticed in your "Readers Say" for July a letter from Captain A. R., of the Royal Canadian Air Force, Lachine, Quebec, concerning the poem, "A Gunner's Vow," which appeared on page 118 of your April issue. The captain is quite right about the author's initials being G. H. H. The author's full name is George Henry Harding—and I'm very proud to be able to tell you that he is my son. He wrote the poem in August, 1940, at the time he was training to be an air gunner. He was later made a pilot and then grounded because of airsickness. He is now a radio operator in the R.C.A.F. The poem, as it appears in your April issue, is incomplete. It has a first stanza which goes as follows:

If I must be a gunner,  
Then please Lord grant me grace,  
That I may leave this station  
With a smile upon my face.

I am quoting this first stanza for you with the thought that those of your readers who enjoyed the poem as it appeared in your magazine, and who possibly have made copies of it, might like to have the poem in its entirety.—Mrs. G. H., London, Ont., Canada.

## Five Sons Keep Ma Hep to Jeeps

WHEN the war is over we shall see the jeep doing more work in civilian life than it did in the service. It is bound to be a vital machine on farms, in logging camps, in oil fields, and in mining districts. In metropolitan areas it will be every busy business man's first aid to success. P.S. I have seven sons—five in the armed forces, and two about to enter. That's why I know so much about jeeps.—Mrs. W. M. F., Cleburne, Tex.

ME AND KIPLING!



## We Fielded This One Without an Error

IN THE article, "Big Leagues Get a War Baseball," which appeared in your July issue, you state that A. G. Spalding & Bros., make all the baseballs used in the major leagues. Yet in the photograph in the lower right-hand corner of page 47 you show a National League ball with Spalding's trademark and an American League ball with Reach's trademark. How about that?—B. B., Greensboro, N. C.

Very simple, B. B.—Spalding uses two trademarks: one for the National League, one for the American. The balls are identical—with, of course, the exception of the trademark.—Ed.

## We Didn't Mean to Be So Tough on Boules

IN LOOKING over the January issue of your magazine, I noticed in your article entitled "Synthetic Jewels," that you have given the Mohs hardness of aluminum oxide boules as 9.8. As director of research for a company engaged in the manufacture of abrasives and refractory materials, I have reason to believe that this figure is incorrect. I know that the boules are hard, but I don't think they are quite that hard.—R. C. B., Niagara Falls, N. Y.

You're right, R. C. B. The figure should be 9.03. Thank you for calling the error to our attention.—Ed.

## For Old X-Ray Negatives —Alcohol in Moderation

WHO CARES ABOUT THE NEGATIVES?



IF J. A. K., of Nashville, Tenn., whose letter appeared in your August issue, will wipe his old X-ray negatives with a cloth that has been dampened with ordinary "rubbing" alcohol, he will find that this thoroughly cleans the film. He must be careful, however, not to

douse the cloth too heavily with alcohol, else the gelatine base is likely to become mushy.—T. J. L., Minneapolis, Minn.





## Heroes' Alma Mater

Our airmen have proved themselves masters of anything that flies.

When you hear of their exploits you wonder how such skill, such devastating dexterity could be acquired in a few brief months. Surely, these men must have been "born to the blue."

Yet the plain fact is that scarcely one in a thousand ever flew a plane before the war. Each and every one had to be *trained*—thoroughly and quickly.

In their training, the Fairchild PT 19 Primary Trainer with "fighter" characteristics is their flying school.

This staunch little ship is ideal for the rigorous acrobatic program prescribed in primary training. In the words of a veteran pilot-teacher now at an Army flying school: "It is unnecessary to caution a student or to warn him about excessive speeds in pull-outs or dangerous positions while he is flying a

PT-19. We simply go ahead and teach him to do every maneuver in the book: slow rolls, snap rolls, Immelmans, loops, half rolls, inverted coordination exercises and turns, vertical reversements, spins, and combinations of these. The PT-19 can certainly 'take it.' That is the best confidence builder ever invented."

From behind soda fountain and plow, office desk and ivied walls, after a short intensive training in the PT-19, the most daring and expert flyers the world has known have emerged. After six hours training in a PT-19 it is not unusual to solo Army students who have never flown before.

As a constant check on the performance of PT-19's, on the American mainland and abroad, the reports of a corps of specialists written in the field, enable our engineers and designers back home to keep that "touch of tomorrow in the planes of today."

 **FAIRCHILD**

BACK THE ATTACK WITH WAR BONDS

ENGINE AND AIRPLANE CORPORATION  
30 ROCKEFELLER PLAZA, NEW YORK

Ranger Aircraft Engines Division, Farmingdale, L.

• Fairchild Aircraft Division Hagerstown Md. • Burlington, N. C. • Laramie Division, New York, N.Y.



# Free 7-Day Offer!

## AUTO MECHANICS!

### REPAIR ANY MAKE CAR—TODAY!



Explains Every Repair Job on Every Model of All These Cars—1935 through 1942!

American Bantam; Auburn Austin Buick; Cadillac Chevrolet; Chrysler; Cord; DeSoto Dodge; Ford; Graham Hudson; Hupmobile Lafayette; LaSalle Lincoln; Lincoln Zephyr; Mercury; Nash Oldsmobile; Overland; Packard; Pierce Arrow; Plymouth; Pontiac; Rex; Studebaker; Terraplane; Willys.  
200,000 Facts, 450 Charts, 900 Photos, Drawings, Diagrams. Size 8 1/2 x 11 in. Published by MoTor's, The Leading Automotive Business Magazine.

Same FREE 7-Day Offer MoTor's Truck Repair Manual! 1400 pictures, 905 pages, 300,000 facts. Used by U. S. Armed Forces. Strong Fabrioid binding, size 8 1/2 x 11 in. Covers 10,000 models 1936-1942. All Gasoline Engines, ALL DIESELS. Hessel, Diesel Fuel Injection Systems, etc., etc.

Helps EVERY Mechanic—even experts—do repair jobs easier, quicker

Explains every auto repair operation STEP-BY-STEP, easy-to-use! Hundreds of photographs, diagrams, drawings, show exact "how to do it" of repairs, adjustments, replacements. All jobs on every model since 1935! Engine; Electric, Fuel, Cooling, Lubrication Systems, Clutch, Transmission, Universals, Rear End; Wheels, Brakes; Knee Action, Shock Absorbers, Springs; Body; Free Wheel, Overdrive, Fluid Coupling!

**150 FACTORY BOOKS IN ONE!** Imagine a COMPLETE COLLECTION of ALL official shop procedure manuals, prepared by each car manufacturer's own engineers! That's what you GET in this book! Open the manual to the car you want—you'll find everything to show the right way to do the job. This is the factory shop manual used by the U. S. Army, trade, technical and vocational schools.

**SEND NO MONEY** Simply fill out coupon below. Mail it today and a copy of MoTor's up-to-the-minute New Auto Repair Manual will be sent to you at once for 7 days Free Examination.

MoTor Book Dept., Dept. 1211, 572 Madison Ave., New York 22, N. Y. Rush to me at once: (check box opposite book you want).

☐ MoTor's AUTO REPAIR MANUAL (formerly "MoTor's Factory Shop Manual"). If O.K., I will remit \$1 in 7 days, \$1 monthly for 4 months, plus 35c postage with final payment (\$5.35 in all). Or I'll return book in 7 days. (Foreign, remit \$7 with order.)

☐ MoTor's TRUCK REPAIR MANUAL. If O.K., I will remit \$2 in 7 days, \$2 monthly for 3 months, plus 35c postage with final payment (\$8.35 in all). Or I'll return book in 7 days. (Foreign, remit \$11 with order.)

Name \_\_\_\_\_ Age \_\_\_\_\_  
Address \_\_\_\_\_  
City \_\_\_\_\_ State \_\_\_\_\_

☐ Check here if enclosing full payment. WE pay 35c postage. Same 7-Day Return Privilege.

## HOW I STEPPED into a Big Pay HOTEL JOB!

Know Nothing About Hotel Work, R. F. Hedges Becomes Hotel Manager With Substantial Increase in Salary



"Dissatisfied with my job in an oil company, I enrolled for the Lewis Course. Soon after completing my training I was appointed Catering Manager of an Omaha hotel. Then the Lewis Employment Bureau placed me as Kitchen Steward of another hotel. I made constant progress, finally stepping from an Assistant Managership to my present position as Manager of this new 250 room hotel at a substantial salary increase. I owe my success to Lewis Spare-Time, Home Study Training."

### HOTELS NEED TRAINED MEN AND WOMEN

Thousands of Lewis-trained men and women winning success in the colorful, essential hotel, club and institutional field. They are making good as Managers, Assistant Managers, Stewards, Hostesses, Executive Housekeepers and 55 other types of well-paid positions. Today our Government's last wartime housing, food and recreational program swells the demand for trained men and women. Opportunities for Lewis graduates greater than ever; their success has proved previous experience unnecessary in this business where you are not dropped because you're over 40. Good grade school education plus Lewis Training qualifies you at home.



"I'm A Success At 32"

For 2 years I had been with a big electric company. Not satisfied with the salary and opportunity, I enrolled for Lewis Training. They placed me in my first position at Housekeeper of a famous resort hotel. Now Mistress Housekeeper at this beautiful apartment hotel. — Alice Barton

Good grade school education plus Lewis Training qualifies you at home. Write your name and address in the margin and mail this ad TODAY for Free Book which tells how you are registered free of extra cost in Lewis National Placement Service.

**LEWIS HOTEL TRAINING SCHOOL**  
Room 8X-2705 Washington 7, D. C.  
(20th Year)

## EVERY Musician SHOULD GET THIS BOOK!

ADD FLAIR TO THE LIFE OF YOUR BAND INSTRUMENT



40 PAGES  
44 ILLUSTRATIONS  
MAKES OF

Your band instrument must last for the duration. That's why you need this new and helpful book, *How To Care For Your Instrument*. In no other book can you find such valuable and helpful information. Covers all makes and types of wind and percussion instruments—40 pages of instructions, 44 illustrations to help make your instrument last longer. Worth many times its 10c cost. Get yours at your Corn dealer's or send 10c today.

ONLY 10c WORTH FAR MORE


C. E. CONN, Ltd., 1152 CONN AVE., ELKHART, IND.

Send me a copy of *How To Care For Your Instrument*. Enclosed find 10c in stamps for postage.

NAME \_\_\_\_\_  
ADDRESS \_\_\_\_\_  
CITY \_\_\_\_\_ STATE \_\_\_\_\_



**MEN!** *Learn* **ELECTRICITY** *whether you are* **16** *OR UP TO* **50**  
**GET THE TRAINING YOU NEED IN 12 WEEKS AT COYNE**



**DON'T BE HELD BACK BY:**

- **AGE!**  
It's the only one in this picture that you can't have a good excuse for. If you have young or old you are in a bad way. You know that your
- **LACK OF EXPERIENCE!**  
You can't do anything on your own. You can't do anything on your own. You can't do anything on your own.
- **LACK OF CASH!**  
You pay tuition after graduation. You pay tuition after graduation. You pay tuition after graduation.
- **LACK OF SCHOOLING!**  
It is the only one in this picture that you can't have a good excuse for. If you have young or old you are in a bad way. You know that your

**Do VITAL WAR WORK...with a VICTORY FUTURE!**



**I'LL FINANCE YOUR TRAINING!**

Don't want to be assigned to some dull, low-pay no-future job. Get your training at Coyne NOW — and be ready soon to take your pick of many well-paid electrical positions.

Learn to do more vital work for America's war program. In 12 short, busy weeks in the Coyne Shops you can get the "know-how" you need for a real opportunity now — and at the same time you'll be in a field with a peace-time future.

## Learn-by-Doing on Real Equipment

Layne has a vast amount of floor space in shops where you learn on motors, switchboards, electronic devices, air conditioning and refrigeration apparatus and on aircraft engines. You also learn house wiring, motor wiring, armature winding etc. etc.

You don't need previous experience or advanced education. You train by actual work. In 90 days at Coyne you can master this training and be ready for a good job—a COYNE-TRAINED ELECTRICIAN!

**START NOW—PAY LATER!**

Lots of fellows who come to Coyne have very little cash. So don't delay for that reason. I'll finance your training. I'll help you get part-time work to help pay living expenses while in school. You can pay tuition in easy monthly payments AFTER YOU GRADUATE.

## JOB SERVICE FOR LIFE

As soon as you're trained, my Graduate Employment Service will assist you in getting local. This service is FREE to graduates. We have placed men in fine jobs all over America. You'll find this service a big help now and throughout your lifetime.

**GET MY BIG FREE BOOK!**

See what Coyne offers. My big book of pictures, facts and PROOF is yours on request. Clip and mail coupon at once. Learn how quickly and easily you can become a COYNE TRAINED ELECTRICIAN. Your opportunity is waiting. Send for my big book TODAY.

**H. C. LEWIS**  
President  
**COYNE ELECTRICAL SCHOOL**  
500 So. Paulina St. Dept. 83-73 Chicago, Ill.

### New Opportunity Offer!

**EXTRA COURSE IN  
RADIO  
AND  
ELECTRONICS  
INCLUDED!**



Electricity is the foundation of all Radio, Television and Electronics. When you combine your Coyne electrical training with my new special Radio and Electronics course, you have the basis for a great future in this sensational, fast-growing field.



**44 YEARS OF SUCCESS — AMERICA'S  
PIONEER "LEARN-BY-DOING" SCHOOL**

H. C. LEWIS, President  
COYNE ELECTRICAL SCHOOL  
500 S. Paulina Street Dept. 401 Chicago, Ill.  
Send me your Free Book. Telephone me when you send.  
Radio Electrician's Textbook and 1000 Questions and Answers  
Telephone and Grammar Books

NAME	+	+
ADDRESS		
CITY		



# INVENTORS

## This BOOK

## and INVENTION RECORD (Cost You Nothing) FREE BOOK



### HOW TO PROTECT, FINANCE and SELL YOUR INVENTION

Our FREE BOOK and other literature available to our clients gives you complete data on how to ready your invention for money making. It tells you how others did it—who they went to for finances—how they arranged partnerships—how they made contacts with manufacturers—how they dictated royalty arrangements—how much money they made—how you can find a market. Our new FREE BOOK discloses sources of quick revenue if your invention is patentable and saleable with profit possibilities.

#### THE FIRST STEP

The first step in getting your invention ready for market is to make a dated record of it on our "Invention Record" form. This form properly filled out and witnessed will be invaluable to you later in establishing the date of your invention should need for such evidence arise. We will be glad to send you our "Invention Record" and have it witnessed in this office when you return it with disclosure of your device. This service costs you nothing—and it immediately puts you on record as the originator of your device.

#### Protect Your Invention NOW!

We have many letters in our files from manufacturers requesting inventions. Today's demand for new devices is tremendous—added to by emergency needs. Protect your invention now with a U.S. Patent. By acting promptly you may prevent another inventor getting in ahead of you at the Patent Office here in Washington. The first step is to make a sketch and description of your invention on our "Invention Record" have it witnessed and mail it to us. We will then make a Search of the U.S. Patent Office files to ascertain whether we can get patent protection for you. This is a step you should make NOW—before another steps in ahead of you and walks away with a patent.

COUPON FORM

## McMORROW & BERMAN

PATENT ATTORNEYS

142-L Albee Building, Washington E. D. C.

Send me your NEW FREE Book "How to Protect, Finance and Sell Your Invention" and specially prepared "Invention Record" form at once. I understand that this request does not obligate me.

NAME \_\_\_\_\_

ADDRESS \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_

Write or Print Name Clearly

## IT'S FREE!

Don't Miss This up-to-the-minute

## NEW BOOK

THE AGE OF CHEMISTRY

THE AGE OF CHEMISTRY

THE PORTER CHEMICAL CO., 44 PROSPECT AVE., HAGERSTOWN, MD.

## SUPER JU JITSU

### NOW GET TOUGH DOUBLE-QUICK!



Learn how YOU can be dangerous. Lick brutes twice your size with only your bare hands, even when they are armed. This powerful fighting system is unbelievably efficient. You don't need ox-like muscles—it's brains that count! New, easy self-study course at amazing low price. Free trial offer and money-back guarantee. Hurry! Write today for FREE DETAILS. Nelson Co., 421 S. Wabash, Dept. L-303, Chicago.

## Try Anti-Gray Hair Vitamins

### Plus Wheat Germ Oil (E) Vitamins ON THIS MONEY BACK OFFER

#### RESTORING COLOR TO GRAY HAIR WITHOUT DYES IS SCIENCE'S LATEST MIRACLE

If your hair is gray, grayed, streaked, faded or off color, modern science offers you a new hope without dyeing. A week or so to a month on your daily diet can cause hair to turn gray. Improve your diet, get extra vitamins from the "Anti-Gray" Panates Vitamins by simply taking the original 2-way Panates Vitamin treatment. You may be amazed and delighted to see the gray spots disappear, restore on of normal growth of color to the hair, and a new complexion parting a great improvement in your hair. Hurry! Write today for FREE DETAILS. You'll get an iron clad guarantee that leaves no room for doubt.

PANATES is different—it not only contains a powerful supply of "Anti-Gray Hair" Vitamins but "Staff-of-Life" Vitamin (E) Wheat Germ Oil as well. Panates is not a hair dye. You have nothing to fear. No mess, no fuss. You can test safe, healthy Panates whether you have dye in your hair or not, because Panates Vitamins work from within to check gray spread and literally feed natural color back into the hair roots.

When the blood does not provide the proper elements, the tiny laboratory that manufactures color shuts down and the hair grows gray. Perhaps you may need the vitamins in Panates. Make this test today.

#### SEND FOR THIS INTRODUCTORY TRIAL OFFER TODAY



The 30 day trial of the regular \$4.75 (40 day) Panates double action Vitamins is only \$1.75 if you act at once! SEND NO MONEY pay postage plus C.O.D. postage on arrival on guarantee of full satisfaction or money back. Send \$1.75 and we pay all postage. Or if you want more of the amazing Panates Anti-Gray Hair Vitamin story, write for FREE Valuable Booklet, "Vitamins and Gray Hair." No cost, no obligation. Whatever you send for our letter or postcard in the mail today while Special Offer to you lasts. Who knows perhaps the 2 vitamins in Panates may be the wonderful easy way answer to your hair color worries!

PANATES CO.

Not in stores Write Dept. A-262, 310 S. MICHIGAN AVENUE, CHICAGO 4, ILLINOIS



## AUDELS AIRCRAFT WORKER... \$1

Answers Your Questions on 1—Aircraft Materials, Terms, Parts, 2—Blueprints, Working Drawings, 3—Mathematics, How to Estimate, 4—Layout & Jigging, 5—Tools & Machinery, 6—Holding Spot Welding & Rivets, 7—Fabrication, Assembly, etc., 8—Assembly, Fuse age, Wing & Fin—How to Use Tools, 9—Tables & Data, Symbols, Army & Navy Specifications, etc. 216 Pages illus.

## AUDELS SHEETMETAL PATTERN LAYOUTS... \$4

Developed by Experts for Sheet Metal Workers, Layout Men & Mechanics, A Practical Library, includes 10 Sections, size 7 1/2 x 10 x 2—1125 Pages—24 Layouts—1000 illus. covers 1001 types Parts, Fully indexed for ready reference to answer any question about pattern. Covers all phases of sheet metal work including Pattern cutting, Pattern Design, Sheet & Shop Procedure.

## AUDELS SHEETMETAL WORKERS HANDY BOOK... \$1

Practical Inside Information, Fundamentals of Sheet Metal Work 216 pages, Illustrated, 11 sections, clearly written, Essential & Important facts, figures, pointers in every language, Ref. Index.

## AUDELS WELDERS GUIDE... \$1

A concise, practical text on operation & maintenance of all welding machines for all mechanics. Over 400 pages, illustrated. Covers all methods of electric and acetylene welding including airplane work.

## AUDELS ANSWERS ON BLUE PRINT READING... \$2

For Mechanics & Builders, Covers all types of blue print reading including ship & airplane, 316 pages, fully illustrated.

## AUDELS NEW MACHINIST & TOOLMAKERS HANDY BOOK... \$4

Covers modern machine shop practice in all its branches. A practical book in 1 New from cover to cover. Tells how to set up & operate lathe, screw and mill, 2 machines, shapers, 11 presses and all other machine tools. 1600 pages, fully illustrated, 7 1/2 x 10 x 2. Indexed, 5 sections, 1—Machine Shop Practice, 2—Blue Print Reading & How to Draw, 3—Calculations & Mathematics for Machinists, 4—Shop Physics, 5—How to Use the Machine Shop chapters. Easy to read and understand. A shop companion that answers your questions.

## AUDELS MATHEMATICS & CALCULATIONS FOR MECHANICS \$2

Mathematics for home study or reference. 240 pages, 316 illus. Practical mathematics from beginning, how to figure correct. Easy, correct methods covering a complete review. 11 & 12 inch.

## AUDELS AUTOMOBILE GUIDE... \$4

A practical quick ready reference book for auto mechanics, service men, operators & owners. Explains theory, construction & setting of modern motor cars, trucks, buses & auto type diesel engines. 116 pages, fully illustrated, 5 1/2 x 7 1/2, indexed. A standard book for mechanics, New for 1943 covered.

## AUDELS DIESEL ENGINE MANUAL \$2

A practical, concise treatise with questions and answers on the theory, operation and maintenance of modern diesel engines including General Motors, Cummins, etc. 154 pages, fully illustrated, flexible binding, pocket size. All latest points brought out. This book is of extreme value to engineers, operators & students.

## AUDELS RADIOMANS GUIDE... \$4

A key to the practical understanding of radio in the Frequency Modulation, Television, etc. A result of Marine Radio & Radio engineering, servicing, amateurs. 212 pages, 100 illustrations & diagrams, Photos, 116 Questions & Answers, Reference Index. Author's clear, concise.

## AUDELS HANDY BOOK OF PRACTICAL ELECTRICITY... \$4

For maintenance engineers, electric and all electrical workers. 110 Pages, 2000 illus. Covers important electrical information in handy form—covering Marine Wiring, Radio, Television, Welding, Indexed. A key to a practical understanding of electricity.

## AUDELS CARPENTERS & BUILDERS GUIDES—4 Vols. \$6

A practical illustrated trade assistant on modern construction for carpenters, joiners, builders, mechanics and all woodworkers. 4 vols., 1000 pages, 3700 illustrations, flexible covers. Each volume pocket size. Sold separately \$1.50 a vol.

## AUDELS PLUMBERS & STEAMFITTERS GUIDES—4 Vols. \$6

A Practical Trade Assistant & Handy Reference. Explains in plain language & by clear illustrations, diagrams, charts & graphic pictures principles of modern plumbing practice including Marine Pipe Fitting and Air Conditioning. 4 Vols.—1670 Pages—162 Diagrams. Each Vol. Pocket Size. Sold Separately \$1.50 a Vol.

## AUDELS WIRING DIAGRAMS... \$1

216 Pages, Illustrated. Gives practical facts on wiring of electrical apparatus. It explains clearly in simple language how to wire apparatus for practically all fields of electricity. Each diagram is complete & self-explanatory. Highly Modern! Pocket Companion.

## AUDELS ELECTRONIC DEVICES... \$2

Tells What You Want to Know About Electric Etc. Easily Understood. Covers photo-electric cells & their applications, Amplifiers, Illumination, frequencies, voltage, photocell, tubes, Ohm's Law, wiring diagrams, etc.

AUDEL, Publishers, 49 W. 23 St., N. Y. 10



## AN AUDEL GUIDE IS A GOOD FRIEND!

Use the brains and experience of others in these Guides of the Trades. Save time and money with right methods, short cuts, labor saving ideas. CHECK NOW! You can look over any Audel Guide in your home. Start the Easy Payments if satisfied.

## -----CUT HERE----- MAIL ORDER

THEO. AUDEL & CO., 49 W. 23rd St., New York 10

Please mail me for 7 days' free examination the books marked (X) below. I agree to mail \$1 in 7 days on each book or set ordered, and to further mail \$1 a month on each book or set ordered until I have paid purchase price.

If I am not satisfied with Guides I will return them.

<input type="checkbox"/> Audels PUMPS, HYDRAULICS & AIR COMPRESSORS \$4.	
<input type="checkbox"/> Audels WELDERS GUIDE	1.
<input type="checkbox"/> Audels BLUE PRINT READING	2.
<input type="checkbox"/> Audels SHEET METAL WORKERS Handy Book	1.
<input type="checkbox"/> Audels SHEET METAL PATTERN LAYOUTS	4.
<input type="checkbox"/> Audels AIRCRAFT WORKER	1.
<input type="checkbox"/> Audels MATHEMATICS and CALCULATIONS	2.
<input type="checkbox"/> Audels MACHINISTS & TOOLMAKERS Handy Book	4.
<input type="checkbox"/> Audels DIESEL ENGINE MANUAL	2.
<input type="checkbox"/> Audels MECHANICAL Dictionary	4.
<input type="checkbox"/> Audels AUTO GUIDE	4.
<input type="checkbox"/> Audels MARINE ENGINEERS HANDY BOOK	4.
<input type="checkbox"/> Audels SHIPFITTERS Handy Book	1.
<input type="checkbox"/> Audels MARINE Engineers Guide	2.
<input type="checkbox"/> Goethe MECHANICAL DRAWING COURSE	1.
<input type="checkbox"/> Rogers Mechanical DRAWING and Design	2.
<input type="checkbox"/> Audels MILLWRIGHTS and Mechanics Guide	4.
<input type="checkbox"/> Audels CARPENTERS and Builders Guides (4 vols.)	6.
<input type="checkbox"/> Audels PLUMBERS and Steamfitters Guides (4 vols.)	6.
<input type="checkbox"/> Audels MASONS and Builders Guides (4 vols.)	6.
<input type="checkbox"/> Master PAINTER and DECORATOR	2.
<input type="checkbox"/> Audels GARDENERS & GROWERS GUIDES (4 vols.)	6.
<input type="checkbox"/> Audels ENGINEERS and Mechanics Guides Nos. 1, 2, 3, 4, 5, 6, 7 and 8 complete	12.
<input type="checkbox"/> Audels Answers on Practical ENGINEERING	1.
<input type="checkbox"/> Audels Answers on REFRIGERATION	2.
<input type="checkbox"/> Hawkins Aids to ENGINEERS EXAMINATION	2.
<input type="checkbox"/> Rogers MACHINIST GUIDE	2.
<input type="checkbox"/> Audels WIRING DIAGRAM	1.
<input type="checkbox"/> Audels Handy Book of PRACTICAL ELECTRICITY	4.
<input type="checkbox"/> Audels ELECTRICAL POWER CALCULATIONS	2.
<input type="checkbox"/> Hawkins ELECTRICAL Guides at \$1. each	10.
<input type="checkbox"/> Audels ELECTRONIC DEVICES	2.
<input type="checkbox"/> Audels ELECTRIC Dictionary	2.
<input type="checkbox"/> Audels RADIOMANS GUIDE	4.
<input type="checkbox"/> Audels NEW ELECTRIC LIBRARY at \$1.50 a Volume Vols. I, II, III, IV, V, VI, VII, VIII, IX, X, XI, XII.	

Name.....  
Address.....  
Occupation.....  
Employed by..... P.M.



**WEN 16 OR UP TO 50**

**Come to COYNE for a great future in**



# RADIO COMMUNICATIONS AND ELECTRONICS



## "Learn-by-Doing" on Real Radio Apparatus!

Airports, radio stations, film studios, police short-wave, television, industrial electronics—all need **TRAINED RADIO SPECIALISTS**. Learn the quick practical way, on actual equipment in the great Coyne Shops. Not by correspondence, but personal training based on 44 years of "know-how"!



## I'LL FINANCE YOUR TRAINING!

Don't let lack of money hold you back. My plan lets you start now, pay tuition in easy monthly payments when you're trained and on the job. I help you get part time work to help pay living expenses while training, give you Lifetime Employment Service as a Coyne grad.

## Prepares for Govt. License

Many of the better Radio jobs require government license. Coyne has enabled hundreds to pass this test successfully. You learn operating laws to send Code rapidly, do trouble-shooting—handle real transmitting equipment, etc., etc.

## Dozens of Branches to Choose From

Why be satisfied with a narrow, no-future line when by putting in a short time in my Shops, you can qualify for unlimited opportunities in **RADIO AND ELECTRONICS**, today's fast-growing fields! These pictures show only a few of countless well-paid jobs for trained Radio Operators.

## SEND FOR FREE BOOK

Fully illustrated with big pictures of my Shops—facts about your future. Mail coupon now. No obligation. No salesman will call. Act today!

**H. C. LEWIS, Pres., RADIO DIV. COYNE ELECTRICAL SCHOOL**  
500 S. Paulina St. Dept. 43-4H  
Chicago, Illinois

H. C. LEWIS, Pres.,  
RADIO DIV. COYNE ELECTRICAL SCHOOL  
500 S. Paulina St. Dept. 43-4H Chicago, Illinois  
Send For Free Book, "Learn-by-Doing" in Radio, and details of easy "Pay-After-Graduation" plan.

NAME .....  
ADDRESS .....  
CITY ..... STATE .....

Buy War Savings Bonds and Stamps regularly.

# "YOU ARE UNDER ARREST!"



**There's a Thrill in Bringing a Crook to Justice Through Scientific CRIME DETECTION!**

I have taught thousands this exciting, profitable, pleasant profession. Let me teach you, too, in your own home. Learn Finger Printing, Firearms Identification, Police Photography and Secret Service Methods thoroughly quickly and at small cost.

**53% of All American Bureaus of Identification** employ students or graduates of I. A. S. You too can fit yourself to fit a responsible and profitable job with good pay and a ready employment. But don't delay get the details now. Let me show you how easily and completely I can teach you for in a few days you will be doing your own work in your own home. You may pay as you learn. Write today. Now. Be sure to state age.

**Be A FINGER PRINT Expert**

**FREE!!!**  
Send for This Free BLUE BOOK OF CRIME

**INSTITUTE OF APPLIED SCIENCE**  
1920 Sunnyside Ave., Dept. 1362, Chicago, Ill.



## Why It Pays To LEARN PHOTOGRAPHY NOW

Never before so many job and career opportunities! Photographers needed in business, industry, science, N.Y.I. graduates winning promotion, higher pay in Armed Forces. Qualify at America's largest, oldest school. Resident or home study. **FREE** catalog describes commercial, portrait, motion picture and color courses. Write today!



**N. Y. INSTITUTE OF PHOTOGRAPHY**, Dept. 5, 10 W. 33 St., New York 1, N. Y.

## 1953: A New World

The Commencement of Divine Order

A New World is emerging from the present conflict. A New Society is being born. Do you agree to know its standards of citizenship, its laws and its history and achievements? 1953 marks the beginning of a new era in the world. What will it be like? How will it further human progress? Will it be a cultural center for the world? Read **THE INCORPORABLE**, 80 pages of answers with unusual illustrations. Free. No obligation. Write Dept. 4.

**LEMURIAN FELLOWSHIP**

110 North Larchmont Boulevard Los Angeles, California

## Correspondence Courses in RADIO and ELECTRICAL ENGINEERING LOW AS \$25

**ELECTRICAL ENGINEERING**. Get good grasp of wide electrical field. Modern, very complete syllabus. Theory made easy. **RADIO ENGINEERING**. Learn the course in radio public address, photo-electric, etc. Training in the latest radio and electronic techniques. Tuition **ONLY \$25** either cash or deferred payment plan. Service men needed badly. Write for free copies of school catalogs, student magazines, etc. **LINCOLN ENGINEERING SCHOOL**, Franklin St., Dept. 559 (Formerly at Lincoln, Neb.) WASHINGTON, D. C.

## ARTISTS MAKE MONEY

Find out your ability. Send name, age, occupation and address for Free Vocational Art Test.

**ART INSTRUCTION, INC.**, 11142 Art Instruction Bldg., Minneapolis, Minn. (Formerly Federal Schools, Inc.)

## BIGGER PAY THAN EVER!

Local "Store Route" Plan pays men like you big money—steady. In wholesale business of your own home. Sell Vitamins, a market of a billion. New low cost route. For the open territory field. Earn as the salesmen plus 10% of quick profit. Must be a local resident. No experience needed. Amazing free **FREE**. Write TODAY.



**WORLD'S PRODUCTS CO**

Dept. 43-L Spencer, Indiana



## EARN MONEY PAINTING PORTRAITS

No previous training or talent necessary. Unique Stuart System teaches you, by mail, in 10 simple, easy-to-follow lessons, to make excellent charcoal and oil likenesses. Detailed guidance for your every step. Send for free book today.

**STUART STUDIOS**

121 Monument Circle, Room 2811, Indianapolis, Ind.

Please send me free book and outline of lessons.

Name .....  
Street .....  
City ..... State .....



**THIS MIRACULOUS  
TIME SAVING**

*is Yours*

# SLIDE RULE FREE!

If You Seize  
This Sensational  
Offer

**Become a MATH Wizard! Get the Right Answers  
In a Flash Without Paper or Pencil!**

**MULTIPLY, DIVIDE, SQUARE, CUBE, EXTRACT  
SQUARE AND CUBE ROOTS AS EASY AS PIE!**

An absolute gift worth a fortune to anyone in business, in a war job, or in the armed forces. A genuine, full-size Slide Rule, complete with an attractive, handy-carrying case. Solves the toughest math problems in a flash! All the features of a very expensive Slide Rule—six scales instead of four, plus a results indicator. Free with the latest, low-cost printed book of its kind, "MATHEMATICS MADE SIMPLE."

**EARN MORE MONEY  
IN YOUR JOB!**

**EARN A RATING—  
COMMISSION  
in the armed forces.**

**10 in. Long**

With Handy Carrying Case.  
A. B. C. C. D. E. Scales  
Ladies Slide

## "MATHEMATICS MADE SIMPLE"

**NEW, AMAZING "FIGUR-EASE" METHOD!**

The Latest Complete, Time Saving Home Study Book For Your Spare Time

A math education helps you get ahead. This book makes learning math simple, interesting and exciting fun. The latest book of its kind. Written as if you had a college professor sitting at your elbow explaining all the main rules, the short cuts, the professional tricks—with diagrams of each step. It takes the headache out of math!

### COMPLETE ANSWERS TO ALL PROBLEMS

Answers to every problem worked out in detail. Practice exercises follow each lesson so that you can develop speed and accuracy. Problems in your every day work, explained step by step. A test at the start points out your weaknesses and a test at the end shows your improvement. Plus many more valuable features!

### FOR BEGINNERS AND EXPERTS!

"Figur-Ease" method makes math a "pinch" for everyone ever using a pencil—BEGINNERS, ALL WAR WORKERS INCLUDING ENGINEERS, THOSE IN BUSINESS, ARMED FORCES, STUDENTS, ETC. Also ideal for a "brush-up" and reference for quick answers. A "must" for everyone!

### SIX COMPLETE BOOKS CONDENSED INTO ONE!

"MATHEMATICS MADE SIMPLE" is streamlined for simple, enjoyable study. Written by an expert teaching in one of the largest universities, and a civil engineer with years of applying math on the job. Contains six main sections—equal to years of school training—now condensed into one book for time saving instruction at the lowest price for so great a value—only \$1.49 including the remarkable Free Slide Rule!

### What the "Figur-Ease" Method Teaches You!

- ARITHMETIC • ALGEBRA • PLANE AND SOLID GEOMETRY
- LOGARITHMS • SCALES • GRAPHS • SHOP MATH
- TRIGONOMETRY (TANGENTS) • HOW TO USE THE SLIDE RULE, ETC.

• All problems explained step by step. • Answers to all problems completely worked out. • A test at the start to show weaknesses. • A test at the end to show improvements. • How to save actual on the job problems. • Available up to the minute also for passing tests in Armed Forces, War Work, Civil Service, etc.

**PLUS MANY MORE PRACTICAL FEATURES**

### PRaised TO THE SKIES BY NEWSPAPER REVIEWERS:

"A life raft for those whose jobs have plunged them head-on into mathematical calculation without special training to the higher brackets." —OAKLAND TRIBUNE

"Designed for those who want knowledge and want it QUICKLY, NEW and EASIER SHORTCUTS in mathematics." —GALVESTON TRIBUNE

"It can't be done? These authors show that it can." —TAMPA TRIBUNE

### SEND NO MONEY—EXAMINE FREE

Simply mail the coupon. Don't send a cent. Rush your order—there are limited copies due to paper rationing. See for yourself how much this book can do for you—NOW AND IN PEACETIME!

### FREE GIFT COUPON

KENMORE PUBLISHING COMPANY,  
Dept. B-17, 224 Fifth Ave., N. Y. C. 1  
Rush to me "Mathematics Made Simple" with my FREE SLIDE RULE GIFT and carrying case. I will deliver with postman on delivery \$1.49 plus postage. If not satisfied within 5 days I will return book for refund.

NAME \_\_\_\_\_  
ADDRESS \_\_\_\_\_  
CITY \_\_\_\_\_, STATE \_\_\_\_\_

☐ Check here if you wish to save postage by enclosing only \$1.49 with coupon. Canada Order—No C. O. D.—Send \$2.00

## MATHEMATICS Made Simple

H. STUART  
A. B. C. C. D. E. Scales

**New! Easy! Short-Cut Methods  
make Mathematics Profitable**

IN WAR JOBS!



IN ARMED FORCES!



IN BUSINESS!



**THIS B**


ARITHMETIC • ALGEBRA  
Use of Slide Rule Explained

All problems explained step by step  
—all problems explained

**ONLY  
\$1.49**  
LOWEST PRICE  
FOR A BOOK  
OF THIS SIZE  
SIZE 8 1/2 x 11



## Sent FREE for 7-Day Trial MACHINE SHOP TRAINING COURSE



Machine Tools fully described, demonstrated. Lessons in all kinds of bench work. Instructions to tool up, operate machines. Hundreds of short cuts enable you to get Expert's Pay.

### FOR BEGINNERS & EXPERTS Easiest, Quickest Way to Get MACHINIST TRAINING

Compiled by practical machine shop experts. Now in Machine Shop Training—shipped just as it is FREE for 7-day examination. After 1 Lesson Assignment shop test. With same training principles and instruction as given students in our huge Los Angeles shops. Hundreds of illustrations, diagrams, charts, tables. Beginners and experts need this proved course. Mail Coupon at once and also receive FREE 7 Drafting Lessons, Machinist's Dictionary and 2 Shop Math Tests.

**NATIONAL SCHOOLS**  
Los Angeles, Calif.



### 3 BIG VOLUMES—SEND NO MONEY

NATIONAL SCHOOLS, Dept. L-11  
4000 E. Figueroa St. Los Angeles 37, Calif. **Postcard**  
Ship your 3 VOLUME MODERN MACHINE SHOP TRAINING COURSE, postpaid. Within 7 days after receiving Course (and Bonus G. E. I. will either return shipment and owe you nothing, or if satisfied I'll send \$3.00 and \$1.00 a month until total of \$12.50 is paid. Final payment \$1.50. You may deduct \$1.25 if you enclose cash \$11.25 with this Coupon. Same return privilege.

NAME \_\_\_\_\_  
ADDRESS \_\_\_\_\_  
CITY \_\_\_\_\_ STATE \_\_\_\_\_  
OCCUPATION \_\_\_\_\_ AGE \_\_\_\_\_

## Make BIG MONEY AT HOME! NEW Invention Electroplates by BRUSH



### Now Plates CHROMIUM! ALSO GOLD, SILVER, NICKEL, COPPER ETC.

**War Increases Demand—You Profit!**  
New, patented invention makes possible big earnings AT HOME. Replate auto-parts—worn articles in homes, stores, hotels, restaurants, etc., with durable, sparkling, new coat of metal—with stroke of brush. Easy, simple, quick. Genuine Gold, Silver, Nickel, Cadmium, etc. Everything furnished. Outfit complete, ready for use. No shop required. Clear from \$2 to \$5 an hour in lifetime business. Small investment starts you in business. Steady repeat. Machine can pay for itself in work. Send TODAY for FREE SAMPLE and illustrated BOOKLET how you can have a life income from a business of YOUR OWN built upon satisfied customers. Act at once!

**WARNER ELECTRIC COMPANY**  
663 N. Wells St., Chicago, Ill., Dept. 467

### FREE BOOK & SAMPLE

WARNER ELECTRIC CO., 663 N. Wells St., Chicago, Ill., Dept. 467  
Gentlemen: Send me Free Sample and Illustrated Booklet.

Name \_\_\_\_\_  
Address \_\_\_\_\_  
City \_\_\_\_\_ State \_\_\_\_\_

Buy War Savings Bonds and Stamps regularly.

## FIX ANY RADIO

Amazing New Invention



Learn quickly to repair all radio sets. New, revolutionary different Comparison method permits you to do expert work almost immediately. No previous radio knowledge required. Introductory training included. Find any fault quickly. Use a screw driver, pliers and a piece of wire—no testers needed. Simple point-to-point picture suggestions tell you where to look for faults and how to make the repair. Plan U-8 Copyrighted. Covers every radio set, new and old. You may try the plan for 10 days without risk.

**Easy to Apply**

Price only \$1.50, postpaid. In large Manual form, 8 1/2 x 11 in., 112 pages. Data on 346 radio tubes, 16 trouble-shooting blueprints. Over 1,000 time-saving service hints. Developed by M. R. Beitman, noted engineer and author. Order without risk for 10 days use. Write today.

**SATISFACTION GUARANTEED**

Read the introductory job sheets, follow the step-by-step picture hints, and fix any radio in minutes instead of hours. The complete simplified training is yours for only \$1.50, postpaid. In days trial. Money back guarantee. **SUPREME PUBLICATIONS**, 229 E. Jefferson St. Chicago 2, Ill.

### THIS VALUABLE BOOK

# FREE

### LEARN CARTOONING AT HOME IN SPARE TIME

Send for this FREE book containing money-making tips, cartooning charts, idea creating methods, list of cartoon buyers, and other valuable information. Read about the money-making opportunities in one of the most fascinating of all professions—CARTOONING! With this booklet we will include a complete portfolio describing our easy Course in Cartooning and explaining our new Markette Method of instruction. We will also tell you how to get the Cartoonists' Exchange Laugh Finder FREE of extra cost. This amazing device actually helps create and originate humorous ideas. Send name at once and mention your age.



**CARTOONISTS' EXCHANGE**

Dept. 14411, Pleasant Hill, Ohio

### MASCOT SLIDE RULE

Fits the pocket. Quickly solves any problem in multiplication, division, proportion. Gives the square, the square root, logarithm and reciprocals of all numbers. Trig scales give sines and tangents of numbers. Fine black graduations on white celluloid. Price in fabricoid case \$1.00 in leather case \$1.25. Money back if not satisfied. Special offer to agents and dealers.

**TAVELLA SALES CO., 21 West Broadway, New York, N. Y.**



### Locksmithing NOW MADE EASY!

New course for practical new mechanical locksmiths. Fix it shops etc. Learn to fit keys, pick locks, de-code make masterkeys. 11 pages. Send name for FREE details. No obligation—write today! **Nelson Co., 221 S. Wabash, Dept. L-702, Chicago.**



**GENUINE U. S. BARGAINS**  
O. D. Wool Blankets (used) \$2.95  
U. S. Army Mat on Bags (New) .49  
U. S. Army Pup Tents (used) 3.50  
Slightly Used Army Caisson Wheels with Axles, 36" high Wt. 322 lbs. \$37.50  
Thousands of other bargains in military, outdoor & sport goods for hunter, farmer, wood. Send 10c for 32 page catalog to be earned with first order.  
**A and N SUPPLY CO.**  
6784 LESTER ST. RICHMOND, VA.



## Large Manufacturer Will Pay Cash or Royalty for New Items

Here is your chance to cash in on your inventions for new products made of metal. These can include machine parts, new equipment, or production parts. Write fully giving descriptions, send sketches if needed—tell us your price. We will arrange meeting if interested—or return your material. Write **M.M.C., 11th Floor, 283 Fourth Ave., New York 10, New York.**



# PLASTICS

**THE GREAT *New* FIELD OF OPPORTUNITY**  
**PLASTICS ENGINEERS AND TECHNICIANS NEEDED**  
**IN NOT ONE BUT MANY CLASSES OF INDUSTRY**

● Leaders in science and industry have long been saying, "Keep your eye on Plastics." But now the time for action has arrived. The future of huge possibilities has already begun. Developments in Plastics for hundreds of wartime uses have set the pace for revolutionary changes in peacetime production of thousands of products.

## THIS IS YOUR BIG CHANCE

Today there's a big need in vital war production for those who are trained in Plastics. From one to a hundred articles made of Plastics must be supplied for every man in our fighting forces. Start training now in Plastics Engineering, in spare time in your own home. Fit yourself for a responsible, well-paid position. Help to win Victory. And at the same time you will be preparing for even greater opportunities when the war is over.

There is scarcely an industry in which these so-called "miracle materials" will not play an important part. After the war many old materials, methods and skills will be replaced. Acquire the all-important "know how." Be in a position to step into one of the key jobs.

## YOU CAN LEARN WHILE YOU EARN

Turn at least part of your leisure time into money. Qualify at home for a larger income in an interesting career. Build greater security for your future in a vocation that looms large on the horizon of the new industrial era. Hours you might otherwise waste can put you well on your way toward lasting success.

It's easy to find out about Plastics training. To get details and outline of study prepared by specialists, and about the school that has helped thousands to success during the past 46 years, write us or check and mail the coupon. Send today. The sooner you take this easy step, the sooner you will reach your goal and reap the rich rewards.

## AMERICAN SCHOOL OFFERS COMPLETE TRAINING SERVICE IN MANY SUBJECTS

You who have not completed high school or have missed vocational training in college, and who cannot spare time to go away to school, can complete your education in your choice of many subjects. Several of these are listed in the coupon at right. Check the subject in which you are interested, fill in your name and address, clip and mail the coupon today.

## AMERICAN SCHOOL

Dept. E-246, Drexel at 13th Street, Chicago 27

PRACTICAL, EFFECTIVE HOME - STUDY TRAINING SINCE 1897

## Take This First Easy Step

## CHECK, CLIP AND MAIL COUPON NOW

AMERICAN SCHOOL, Dept. E-246, Drexel at 13th, Chicago 27, Ill.

If *usual obligation*, Please send FREE and postpaid, bulletin and details of the Subjects checked.

- |   |   |  |
|---|---|--|
| <input type="checkbox"/> PLASTICS ENGR      | <input type="checkbox"/> Accounting and         | <input type="checkbox"/> Drafting and Design |
| <input type="checkbox"/> Refrigeration      | <input type="checkbox"/> C. P. A.               | <input type="checkbox"/> for Men and Women   |
| <input type="checkbox"/> Architecture       | <input type="checkbox"/> Cost Accounting        | <input type="checkbox"/> Radio               |
| <input type="checkbox"/> and Building       | <input type="checkbox"/> for Manufacturing      | <input type="checkbox"/> High School         |
| <input type="checkbox"/> Practical Plumbing | <input type="checkbox"/> Bookkeeping            | <input type="checkbox"/> Air Conditioning    |
| <input type="checkbox"/> Automotive         | <input type="checkbox"/> Private Secretary      | <input type="checkbox"/> Shipbuilding        |
| <input type="checkbox"/> Engineering        | <input type="checkbox"/> Diesel Engineering     | <input type="checkbox"/> Mechanical Eng.     |
| <input type="checkbox"/> Aviation Drafting  | <input type="checkbox"/> Surveying & Topo-      | <input type="checkbox"/> Shop Management     |
| <input type="checkbox"/> Aviation           | <input type="checkbox"/> graphical Drafting     | <input type="checkbox"/> Tool Making         |
| <input type="checkbox"/> Business           | <input type="checkbox"/> Sheet Metal            | <input type="checkbox"/> Better Foremanship  |
| <input type="checkbox"/> Management         | <input type="checkbox"/> Pattern Drafting       | <input type="checkbox"/> Machine Shop        |
|   | <input type="checkbox"/> Electrical Engineering | <input type="checkbox"/> Operations          |

Name . . . . . Occupation . . . . .  
 Address . . . . . Age . . . . .  
 City . . . . . State . . . . .



HERE IS YOUR SUCCESS CHANCE

BE A

# RADIO-ELECTRONIC TECHNICIAN



**SPRAYBERRY TRAINS YOU QUICKLY  
FOR WAR AND PEACETIME WORK**

**You Learn in Easy Step-By-Step Stages  
No Previous Experience Needed**

The offer I make you here is the opportunity of a lifetime. It's your big chance to get ready for a wonderful future in the swiftly expanding field of Radio-Electronics INCLUDING Radio, Television, Frequency Modulation, and Industrial Electronics. Be wise NOW is the time to act. Aside from future considerations, just think of the IMMEDIATE possibilities in Radio during war time. They're tremendous! Best of all, it's easy for the beginner to get started through my quick, practical training.

**Prepares You For A Business  
of Your Own**

**... or Good Radio Jobs, Civilian or Military**

The Sprayberry course is short, intensive and interesting. It starts right at the beginning of Radio. You can't get lost. It gets the various subjects across in such a clear, simple way that you understand and remember. I make it easy for you to learn Radio Set Repair and Installation Work... by practical, proved, time tested methods. I teach you how to install and repair Electronic Equipment and give you the broad fundamental principles so necessary as a background no matter what branch of Radio you wish to specialize in. Soon you'll be qualified for a job. This was work OR, if you enter the Armed Forces or Marines, my training will help you with higher rating and better pay. Let me show you what Sprayberry training can do for you.

**JUST OFF THE PRESSES**

**"How to Test and Repair  
Radio Sets Without  
Meters"**

**YOURS FREE THESE  
TWO VALUABLE  
BOOKS!**



Developed in the Sprayberry Laboratory, this instructive volume tells about an amazingly simple, yet efficient method for Radio trouble-shooting and repair without use of regular equipment made scarce due to war. Send for this FREE book now while the supply lasts and along with it, I will send you another big FREE book describing my Radio Electronic training. Use coupon below.

**MAIL COUPON**

**SPRAYBERRY ACADEMY OF RADIO**  
F. L. Sprayberry, President  
622-L University Place, N. W., Washington, (9) D. C.  
Please rush my FREE copies of "HOW TO TEST and REPAIR RADIO SETS WITHOUT METERS" and "HOW TO MAKE MONEY IN RADIO"

Name ..... Age .....  
Address .....  
City ..... State .....  
(Mail in plain envelope or make no penny postcard)

Buy War Savings Bonds and Stamps regularly.

**DRAW for MONEY**

**Be An ARTIST!**

**Trained Artists Are Capable of Earning  
\$30-\$50-\$75 A WEEK**

**Use Your Spare Time to Prepare  
For a Profitable Art Career**

It's interesting and pleasant to study Art the W. E. A. way. **COMMERCIAL ART, DESIGNING, CARTOONING**—all in ONE complete course. No previous Art experience necessary—hundreds have profited by our practical home study method since 1913. Write today for information in FREE BOOK "Art for Pleasure & Profit". It's all about our course, service—and commercial opportunities for you in Art. State age.

**WASHINGTON SCHOOL OF ART**  
Studio 1311-F, 1115-15th St., N. W.,  
Washington 5, D. C.

**ENGINEERING DEGREE IN  
27 MONTHS**

**INDIANA  
TECHNICAL  
COLLEGE**

Courses in Aeronautical, Chemical, Civil, Electrical, Mechanical, and Radio Engineering. One year courses in Industrial and Drafting. Approved by C. A. A. Prep courses without added cost. Low tuition. Large industrial center. Opportunity to earn part living expenses. Enter December, March, June, September. Catalog \$115 E Washington Blvd., Ft. Wayne, Ind.

**LAW**

**STUDY AT HOME for PERSONAL SUCCESS and  
LARGER EARNING** 31 years expert instruction over 100,000 students enrolled. LL.B. Degree awarded. All texts furnished. Easy payments. Send for FREE BOOK—"Law and Executive Guidance".

**AMERICAN EXTENSION SCHOOL OF LAW**  
Dept. 35-B, 5 East Huron St., Chicago, Ill.



**MONEY IN RABBITS-CAVIES**

**WE BUY** and put you in touch with other markets. Catalog and copy of magazine free. Or send for Free Book "How to Buy and Sell" and know a Rabbit is in to the AMERICAN SMALL STOCK FARMER. OUTDOOR ENTERPRISE CO., 6755, PEARL RIVER, N. Y.

# A FROLIC READER FOR THE GENTLEMAN



Here indeed is Reading for Pleasure. **THE PLAYBOY'S HANDBOOK** is a clever, cheerful, sly collection of American Humor at its best. It's a man's book, just like hunting is a man's sport. Ranging from the sublime to the ridiculous, it features such exhilarating curiosities as

Just A Freudy-Cat, by Jack Hanley; Mythology from "The Bachelor Life", by George Jean Nathan; Advice To A Young Man On The Choice Of a Maiden by Benjamin Franklin; Mr. Preble Gets Rid Of His Wife, by James Thurber; The Greeks Had A Yea For It by Gilbert Seldes; The 99-44 100% Puritans by Duncan Linderhill; For Women Only by Marjorie Daw; Slag Lines by Wm. Allen Brooks; A Trip To Hollywood, by Frank Sullivan; The Art Of Persuasion, by Stephen Moore, plus other articles, cartoons, stories, gags and nonsense!

Do not deny yourself the enjoyment of these frivolities. The price is only \$1.00, the pleasure a thousandfold. Mail the coupon now.

**KNICKERBOCKER PUB. CO.**  
120 Greenwich St., Dept. D-224, New York 6, N. Y.

Send me a copy of "THE PLAYBOY'S HANDBOOK." It's guaranteed to be a riot of fun—or my money back.  
( ) I am enclosing \$1.00 ( ) Send C.O.D. plus postage

Name ..... City .....  
Address ..... State .....



# RICH REWARDS FOR THOSE WHO KNOW PLASTICS



## BE A PLASTICS TECHNICIAN



Do you want action now—in a vital, growing war-time industry . . . helping to turn out fighting planes and jeeps and bombs and tanks? There's a big demand for men and women plastics technicians to fill important war industry positions . . . and if you start your training now—at home—you may qualify for a place in this vital part of the war program

### LOOK TO THE FUTURE

Even more important is the question—what will you do when the war is over? Will you be among those fighting for jobs that may no longer exist? Or will you be well on your way to a permanently profitable career, or established in your own business, with plastics?

Build your personal post-war plans on a sound knowledge of plastics. This country is already in the Plastics Era. The future of the plastics industry is so rich that some predictions seem exaggerated and fantastic . . . but the fact remains that plastics have proven themselves and are vital in the production of airplanes, autos, furniture, radios, trains, clothing, electrical appliances and equipment, machinery, tools, and hundreds of other products.

### CHOOSE YOUR FIELD . . . Enter it thru PLASTICS

You should be able to see for yourself what plastics will mean in virtually every field—the possibilities that will be available to those trained in plastics. Now is the time to prepare for your chosen field, as a plastics technician.

### LEARN AT HOME

Make your increased hours at home pay you dividends. You can easily fit into your spare time your training for a career in plastics. You won't need to lose one minute from your present work . . . simply devote a few hours each week to enjoyable home study, like thousands of other men and women are doing who are helping their country while helping themselves. The Plastics Institute course is an easy, practical tested method which will help fit you for this promising and interesting field—and if you are now working with plastics, it equips you for advancement. During the entire course your training is supervised by men well known in the plastics industry, in which they have been recognized as authorities for years.

### TIME IS PRICELESS—ACT NOW!

Find out how the Plastics Institute can help YOU. Mail the coupon for your copy of the large FREE, illustrated booklet, the "World of Plastics." It is crammed with valuable information about plastics, tells about the new plastic airplanes and other uses for this revolutionary new material—as well as about the opportunities for YOU in plastics. Decide NOW to let plastics point the way to YOUR success—send the coupon TODAY

### STUDENTS REPORT SUCCESS

"I wish to acknowledge, with thanks, the receipt of my final examination papers, my certificate of graduation, and the lesson binders you sent me.

"I have really enjoyed your excellent course of study, and the friendly help and cooperation you have given me, and feel that the time and money expended on my training has been well worthwhile

R.F.P.

## PLASTICS INDUSTRIES TECHNICAL INSTITUTE

1220-D Chenin Bldg.  
New York

626-D LaSalle-Wacker Bldg.  
Chicago

194 So. Alvarado St.  
Los Angeles

AMERICA'S ORIGINAL  
PLASTICS SCHOOLS

### MAIL COUPON FOR FREE BOOK

Plastics Industries Technical Institute  
626-D LaSalle-Wacker Bldg., Chicago

Gentlemen: Please send me the booklet "World of Plastics" and information on your training program. I understand there is absolutely no obligation.

Name \_\_\_\_\_ Age \_\_\_\_\_

Street \_\_\_\_\_

City \_\_\_\_\_ State \_\_\_\_\_

Dept. 11





# Specialists Wanted

## IN MANY BRANCHES OF AVIATION

### Train in Miami!

This is the day of unequalled opportunity in aviation. IF you have the right kind of training. You can get such training in beautiful Miami and build a career in one of the world's fastest growing industries. Choose the branch of aviation in which you want to make your success. Embry-Riddle can train you for an important, big-pay job in that branch. Check, fill in and mail coupon AT ONCE for 24-page booklet of valuable information. Don't delay.

**Embry Riddle**  
**School of Aviation**  
 MIAMI 30, FLORIDA

Dean of Enrollments, Dept. 9: Please send me information about aviation training at Embry-Riddle.

- |  |  |
|--|--|
| <input type="checkbox"/> Instrument Technician                           | <input type="checkbox"/> Aircraft Mechanic |
| <input type="checkbox"/> Radio Communications                            | <input type="checkbox"/> Link Instructor   |
| <input type="checkbox"/> Drafting and Design                             |  |
| <input type="checkbox"/> Aircraft Engine Mechanic                        |  |
| <input type="checkbox"/> Check here for details of ALL available courses |  |

Name \_\_\_\_\_

Address \_\_\_\_\_

## Learn Profitable Profession in 90 days at Home

THE COLLEGE OF SWEDISH MASSAGE  
 100 E. Ohio St., Dept. 870 Chicago 11

## STUDY AT HOME

**With A Chartered Educational Institution**  
 Courses in **ENGINEERING:** Electrical, Civil, Mechanical, Drafting, Architectural, Steam, Aeronautical, Radio, Structural, Mining, Industrial, Highway, Petroleum, Marine, Chemical.  
**Courses in ARTS AND SCIENCES:** Philosophy, Education, Lettering, Public Health, Medical Jurisprudence, Psychology, Sociology, Physics, Chemistry, Geology, Botany, Science, Theology, Law, Business and Commerce, Accounting, Mathematics, Statistics, Agriculture.  
 McKinley-Roosevelt Incorporated, 4810-AC, Sheridan Road, Chicago, 40

Now you can own these  
 "Western Union" Electric

## RADIO TELEGRAPH & RECEIVING SETS

Is Your Gas  
 TELEGRAPH  
 OPERATOR?

IT BUZZES!

IT FLASHES!

IT CLICKS!

RADIO WAREHOUSE MARKET

362 Wooster Ave., Akron, OH

FREE!

395  
 POST PAID



Money  
 Back  
 Guaranteed

Each set a  
 complete  
 portable  
 unit

Tear out this ad, write name and address in margin, mail \$3.95 and we will send outfit at once POST PAID. Or order C.O.D. pay postman for outfit plus postage

## HEAR a world of sound through a MAICO



MAICO  
 Vacuum Tube  
 Hearing Aid

Small, light and easy to wear, yet enables hard of hearing person to carry on normal conversation at 20 feet—to hear even a whisper with loud noises cushioned.

Send name of relative, friend or your own name for a new experience in hearing. No obligation. Address Maico Co., Inc., Dept. 50-K, 2632 Nicollet Avenue, Minneapolis.

A product of the Maico Company which provides 90% of America's precision hearing test equipment. Choice of ear physicians, hospitals, universities, clinics, airlines, U. S. Army and Navy.

## RADIO

ENGINEERING, Broadcasting, Servicing, Electronics, Aviation, Marine & Police Radio taught thoroughly. 48 weeks Engineering course equivalent to 3 years' college radio work. School established 1874, all expenses low Co-educational. Catalog free.

Dodge Institute, Dept. 503 Valparaiso, Ind.

MAKE  
 Extra  
 MONEY  
 FAST

See ILLUSTRATED COMIC BOOKLETS for adults (west pocket size) and other novelties. 10 different sample booklets sent for 50c or 25 assorted for \$1 or 100 assorted for \$2. Shipped prepaid. Wholesale novelty price list sent with order only. No C.O.D. orders. Send Cash, Stamps or Money Order. GRATCO, Dept. 21 Box 520, B. P. O., New York

# DRAFTING

**MORE DRAFTSMEN NEEDED** in all manufacturing and building trades—\$30 to \$50 a week and 15¢ an hour. Learn to draw in 12 weeks. Sample Drafting Booklet \$1.00. Write NOW for FREE Booklet. No obligation.  
**American School**  
 Dept. DD448, Drexel & 58th, Chicago 37

## REFRIGERATION

**MECHANICS SPARE TIME COURSE**  
 Learn at home—how to start your own repair shop on little capital. No previous experience needed. Common school education sufficient. Splendid opportunity for older men. Prepare now for after the war. FREE Illustrated booklet.  
**MECHANICS TRAINING SCHOOL**, Dept. PS-8 4701 W. Pico, Los Angeles 8, Calif.



## MECHANICAL DENTISTRY AT HOME!

To make Crowns, Plates, Bridge work, etc. for Dentists. Learn at home. No previous experience needed. Try at home. No obligation. Write for FREE Booklet. **McGARRIE SCHOOL OF MECHANICAL DENTISTRY**, 207 N. Grand St., Dept. 820, Philadelphia, Pa.



## JOKE BOOKS FOR ADULTS

The kind they like. You will be both a host and the life of the party with a set of these pocket size joke books. They are full of fun, entertainment, fun and humor. A set of six books only \$3.95 or a special assortment of 12 books \$7.95 different for \$1.00. Print name and address—send cash or stamps for.

**TREASURE NOVELTY CO.**  
 72-8th Ave., Dept. 1411, N. Y. 11, N. Y.

## DO YOU

WANT a permanent business profession of your own? Then become a foot corrector. Earnings of men and women in this greatly needed profession run as high as \$50-\$100 weekly after a few weeks home training—not medical or chiropody—easy terms, no further capital needed. So good to buy. 4th year. Write for free booklet.


Stephenson System of Foot Correction, 62 Back Bay Boston, Mass.



# Get into \* **RADIONICS** now


*Learn*

## INDUSTRIAL ELECTRONICS TELEVISION & RADIO



*Out of the War is emerging the Age of Electronics, with immediate opportunity for you to enter America's new Industry*

\*Radionics is a general term embracing Industrial Electronics, Television and Radio. Electronics for harnessing the forces of Industry. Television to bring the world's sights into the home. Radio with revolutionary improvements—these are developments that constitute a tremendous field. You can project yourself into this mighty field. You can become part of it. You can earn good pay as a Radionics Expert, with independence insured during and after the war. When the war ends, Radionics will boom even faster than now. But you can't successfully enter this field unless you have TRAINING. Let's speak plainly. You have the desire and you realize the tremendous future of Radionics. But you lack training. So here's the way to get into Radionics. Have National Schools train you right in your home. National is always in the lead. As industry advances, National offers training to fit. This was never more true than



*How you can qualify as a Technician in the fascinating field of RADIONICS—including Electronics, Television & Radio*


today. National's training covers all phases of Radionics. You learn by following fascinating lesson assignments, based on practical shop-laboratory methods. Instructors give you the same fundamental training that you would receive if you were actually in the school. It's an amazing extension of resident school training.

## TESTED HOME TRAINING BY PROVED SHOP-FIELD METHOD

For more than 38 years National Schools has trained thousands of men. Many graduates hold top positions in hundreds of leading industries. Unlike ordinary correspondent courses, National's Radionics Course is based on shop-practice, shop-tested, shop-routine training, adapted to Home Study. Replacing dry text books, fascinating Lesson and Experimental Assignments are provided. Instructors counsel with you. After the first few Lessons you are qualified to repair Home Radio Sets. Soon you master Communications and Sound Systems. Before you realize it you have practical knowledge of the 'workings' of countless Electronics Controls and how Electronics is applied to Industry. When you graduate you are qualified to accept a job that should pay substantially more than you are now earning. This is a real opportunity for you.

*See opportunity Book, all about Radionics, and FREE lesson mailed without obligation.*

ESTABLISHED 1905



Mail This Coupon Today

### FREE RADIONICS BOOK & LESSON

NATIONAL SCHOOLS DEPT. PS-11 (Paste on a penny postal)  
4000 SOUTH FIGUEROA,  
LOS ANGELES 34, CALIFORNIA

Send Radionics Book, Lesson and full details, post-paid without obligation.

NAME \_\_\_\_\_ Age \_\_\_\_\_

ADDRESS \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_

**NATIONAL SCHOOLS** of Los Angeles

*presents* **HOME TRAINING** IN RADIONICS

**MEN OF ALL AGES  
TRAIN TO  
SERVISE**

Radio Servicemen  
Electronics Engineer  
Studio Technician  
Television Expert  
Machine Control  
Engineer  
Communications &  
Sound Engineer

TRAINING IS BROUGHT TO YOU. Every day some new development in Radionics takes place. National's instructors are always on the alert to study each new invention and weigh its advantages. The Course reflects this up-to-the-minute checking so that you as a student get the latest first. The more time you can devote to this training the sooner you graduate. The Course is geared to your needs. You keep your present job while learning. Many students, soon after enrolling, earn extra pay by servicing neighbors' Radio Sets and working in established Radio Shops. Many students are men who have already devoted years to Radio and want to improve their abilities by obtaining thorough training in the entire field of Radionics. So regardless of your age or experience you can increase your pay and insure your future by enrolling.



# NEWS

Increased production



## MORE JOBS for MACHINISTS

and bigger pay for men who know their work

This big home study and reference course gives you the practical facts on machines and methods you need to advance in machine shop work. Take advantage of the other man's experience as found in books, to solve your problems, increase your efficiency, with

### The AMERICAN MACHINISTS' LIBRARY

6 volumes—2368 pages—2516 illustrations  
(A combined home-study course and reference library)

This library of machine shop practice was written for practical men. It gives you the best methods for every kind of machine shop work. It fully explains lathe, drill and other machine tools and their operation, automatic screw machines, speeds and feeds, gear design and production, jigs and fixtures, punch and die work, metal surfacing, etc., etc. Plainly written, completely illustrated—the best kind of help to the machine shop man who wants to advance himself.

No money down—special price—easy payments.

#### EXAMINATION COUPON

McGraw-Hill Book Co., 336 W. 42nd St., N. Y. C. 10

Send me for ten days' examination the American Machinists' Library. If satisfactory I will send you \$1.50 in 10 days and \$1.00 monthly until the price of \$10.50 is paid. If not wanted I will return the books postpaid. (For prompt shipment write plainly and fill in all lines.)

Name \_\_\_\_\_  
Home Address \_\_\_\_\_  
City and State \_\_\_\_\_  
Position \_\_\_\_\_  
Name of Company \_\_\_\_\_


## KEY TO A PRACTICAL UNDERSTANDING OF ELECTRICITY

\$5 PER MONTH

### AUDELS HANDY BOOK OF ELECTRICITY

\$4 HANDY SIZE

For Engineers, Electricians, Students and all interested in Electricity. A quick, condensed, ready reference, giving complete instruction and practical information. Easy to understand. A reliable authority and a handy helper that answers your questions.



#### INSIDE TRADE INFORMATION ON

The Rules and Laws of Electricity—Maintenance of Machinery—A. C. and D. C. Motors—Armature Winding and Repair—Wiring Diagrams—Home Lighting—Power Wiring—Cable Splicing—Motors—Batteries—Transformers—Elevators—Electric Cranes—Railways—Bells—Sign Flashes—Telephone—Ignition—Radio Principles—Refrigeration—Air Conditioning—Oil Burners—Air Compressors—Welding, and many other Applications explained so you can understand.

1340 PAGES  
2600 ILLUS.

THEO. AUDEL & CO., 49 West 23rd Street, New York  
Please send me Audels Handy Book of Practical Electricity for free examination. If satisfactory, I will send you \$1 in 7 days, then \$1 monthly until \$4 is paid. Otherwise I will return it.



READ FOR PROFIT!

Name \_\_\_\_\_  
Address \_\_\_\_\_  
Occupation \_\_\_\_\_  
Reference \_\_\_\_\_

Buy War Savings Bonds and Stamps regularly.

## Do You Make Mistakes in English?

EVERY time you speak or write you show just what you are. Mistakes in English reveal you as a person who lacks education and refinement. Lack of language power prevents you from presenting your thoughts in the strongest possible way. No matter what you do, real command of English will help you to your goal. Stop making mistakes in spelling, punctuation, pronunciation. Increase your vocabulary.



### WONDERFUL INVENTION

Only 15 minutes a day with Sherwin Cody a new invention and you can actually SEE your English improve. It teaches by HARRY makes it easier to do the RIGHT way. Wonderful self-correcting lessons include spelling, punctuation, grammar and expression.

**FREE BOOK ON ENGLISH** Lack of language power may easily be costing you thousands of dollars every year. See what Mr. Cody can do for you. It costs nothing to find out. Mail a postal card or enter this very minute for free book. How You Can Master Good English in 15 Minutes a Day. It will prove a revelation to you. WRITE NOW. Address:

Sherwin Cody School of English, 1811 Beards Bldg., Rochester 4, N. Y.

## LAW

STUDY AT HOME for PERSONAL SUCCESS and LARGER EARNINGS. 61 years expert instruction over 100,000 students enrolled. LL.B. Degree awarded. A flexible furnished. Easy payments. Send for FREE BOOK "Law and Executive Guidance".

AMERICAN EXTENSION SCHOOL OF LAW  
Dept. 22-B, 2 East Huron St., Chicago, Ill.

## REFRIGERATION

Repair and improve all refrigerators. New manual tells how. Charts and pictures to help you. Price only \$1.00 postpaid. Money back guarantee. Supreme Publications, 328 S. Jefferson St., Chicago, Illinois.

## MENTAL SCIENCE

### Awaken Your Hidden Powers!

You are a sleeping giant! Learn how to release your hidden powers for success. New reader practical reading course in everyday psychology. Teachers you can't master, influencing others, getting ahead, etc. Written by 34 psychologists. Low price. Not a fiction. Guaranteed. MAIL TO FALLON, W. & COMPANY, 321 N. Wabash Ave., Dept. 203, Chicago.

## Piles—Fistula Facts

### 122-Page Book—Sent FREE

Do you suffer pain, torture and broken health of neglected Piles, Fistula, or related rectal and colon ailments? Write today for 122-page FREE Book, Learn Facts. The McCleary Clinic, 1171 Elms Blvd., Excelsior Springs, Mo.

### 4 Painting-Size PIN-UPS

#### Reproduced in True-Life Colors

#### 4 BEAUTIFUL GIRLS

- The Bathing Girl • The Boudoir Girl
- The Mirror Girl • The Sunshine Girl

#### GET ALL 4 OF THESE

#### DIRECT FROM THE ARTIST

Masterpieces from the palette of George Petty, four different girls with the alluring, shapely figures that Petty has made famous. Faithfully portrayed in rich colors by photo-lithography on heavy paper. Large 7 x 11 1/2 in. size. Ready to frame or pin up. Shipped to reach you fresh and unfolded. Special packing used for overseas orders. NOW obtainable nowhere else. Your money back if you are not delighted. All four pictures for only \$2.00 for the set, postpaid. Supply limited, order today from—

GEORGE PETTY  
1224 Mound Avenue  
Racine, Wisconsin

MAIL THIS PETTY GIRL COUPON

GEORGE PETTY  
1224 Mound Ave., Racine, Wis.

I enclose \$2 ☐ Money Order ☐ Check ☐ Cash for which please send to the address below 1 set of 4 Petty Girls

Name \_\_\_\_\_

Address \_\_\_\_\_

City \_\_\_\_\_ State \_\_\_\_\_



**SEND FOR FREE RADIO LESSON!**

# GET FACTS ABOUT HOME RADIO KITS AND HOME MOVIES

to help train you quickly for a

**GOOD JOB IN RADIO  
and ELECTRONICS**

You be the judge! See for yourself how we help you build a future in one of America's most exciting, promising opportunity fields—**RADIO and ELECTRONICS**. How quick y. thoroughly you learn Radio at home—the interesting, practical DeFOREST'S way . . . How DeForest's provides you with **THREE** major home training advantages to **SPEED** you toward a good job in the great **RADIO INDUSTRY**. . . How we can help you to a better income in this Billion Dollar field with its most promising postwar future in F. M. Radio, Sound Movies, Peace-time Radar and other potential wonders of the "ELECTRONIC AGE". Send for Our big, free book, "VICTORY FOR YOU" plus a **FREE SAMPLE RADIO LESSON—TODAY.**

## YOU BUILD AND OPERATE THIS 5-TUBE RADIO RECEIVER

and **SCORES** of other fascinating projects at home, such as a **SHORT WAVE RECEIVER**, an **ELECTRIC EYE CONTROL**, an **AVIATION BAND RECEIVER**, etc. DeForest's handy "Block System" enables you quickly, easily to rearrange your parts. Work out 135 practical experiments. Get valuable Radio experience. Mail coupon for complete details. **FREE**


**DeFOREST'S TRAINING, INC.**

2535-41 N. Ashland Avenue, Chicago 14, U.S.A.

## YOU STUDY WITH THIS 16 MM MOTION PICTURE PROJECTOR

DeForest's Training provides you with (1) modern, loose-leaf assignments prepared under the supervision of **DR. LEE DeFOREST**; (2) the use of a genuine DeVRY projector and instructive, movie films to help you get a vivid understanding of Radio's fundamentals; (3) the use of standard **RADIO ASSEMBLIES and PARTS** to provide valuable "LEARN BY DOING" experience.

LET THEIR EXPERIENCE GUIDE YOU



Radio-Electronics Author-  
ity. Dr. Lee DeForest su-  
pervised preparation of  
DeFOREST'S TRAINING.

PUT  
YOURSELF  
IN THIS  
PICTURE



Dr. Herman A. DeVry—  
often called "Father of Vi-  
sual Education"—founded  
DeFOREST'S TRAINING.



**DeFOREST'S TRAINING, INC.,**

2535-41 N. Ashland Ave., Dept. E, Chicago, U.S.A.

Please send me—**FREE** and **WITHOUT OBLIGATION**—your  
illustrated book, "VICTORY FOR YOU" showing me how I can  
get your Home-Movie Training and Home-Laboratory Kits.

Name

Address

City

State

Age

*Mail this Coupon*



# SUPER STRENGTH THROUGH THESE EASY STEPS



## ADD INCHES TO YOUR BACK, CHEST, BICEPS

There is a way to build up your muscles with ease and comfort. The only way to build up your muscles is by using the Super Power Crusher Grip and Super Power Hand Grips. These grips are made of a special material that will help you to build up your muscles without any pain or discomfort. They are the only grips that will help you to build up your muscles without any pain or discomfort. They are the only grips that will help you to build up your muscles without any pain or discomfort.

# FREE!

## SUPER POWER CRUSHER GRIP "Moulder of MEN"

The only grip that will help you to build up your muscles without any pain or discomfort. It is the only grip that will help you to build up your muscles without any pain or discomfort. It is the only grip that will help you to build up your muscles without any pain or discomfort.

## WITH YOUR ORDERS SUPER POWER HAND GRIPS

## DOUBLE MONEY BACK GUARANTEE



# SEND NO MONEY

Just fill in and send coupon. When postman delivers your Super Power Crusher Grip and free Super Power Hand Grips, pay him only \$1.98 plus postage. Develop champion strength as champions do. Rush coupon . . . Now!

MUSCLE POWER CO., Dept. 6211,  
P. O. Box No. 1, Station X,  
New York 34, N. Y.

Send me the Super Strength Crusher Grip as described. I will pay the postman only \$1.98 plus postage. Also enclose the Super Power Hand Grips free with my order.

Name \_\_\_\_\_

Address \_\_\_\_\_

(SPECIAL) If you are aboard ship or outside the U. S. A. please send money order for \$2.15.

Buy War Savings Bonds and Stamps regularly.

## OSWALD RABBIT Cartoon Home Movies! Are ALWAYS Funny!



Screen several OSWALD RABBIT animated cartoons next time you entertain family and friends. Packed with laughable escapades. Show also an AVIATION feature for added thrill!

### OSWALD FEATURES

Doctor Oswald	10A
Sniffs and Sniffles	11A
The Filly and Express	12A
Adventure in Dreamland	13A
G Man Oswald	14A
Hi Peep a Sheep	15A
Above in 30 ft. 8MM at \$1.25, and 100 ft. 16MM at \$2.50	

Cartoon and Aviation HOME MOVIES are the popular and idea stream-lined type of entertainment today. Stage & HOME MOVIES show often!

Get at Your Dealers. Write for Catalog and Prices to:

HOLLYWOOD FILM ENTERPRISES, INC.

6060 Sunset Blvd., Dept. 116, Hollywood 28, Calif.



# PULVEX

## FLEA POWDER

25¢ AND UP

ALSO KILLS C. & T. MS.

## IT'S FUN TO MAKE THINGS—

and easy too, with the Guilderafter's Home Study Course in Arts and Crafts. Practical suggestions for hobbies, toy and nursery decoration, party favors and prizes, greeting cards, etc. Easy to follow directions, attractive suggested designs. It's a complete home study course for individuals or groups in hobby, notebook form. Complete course, \$6.00.

The American Crayon Company

239-339 Hayes Avenue

Sandusky, Ohio

## STAMMER?

This new 124-page book "Stammering, Its Cause and Cure" explains the Hogue Unit Method, for an entire cure of stammering and stuttering. Available for 12 years. Free—no obligation. Benjamin N. Hogue, Dist. 1835, Circle Tower, Indianapolis, Ind.

GET THIS FREE BOOK!



## Class Pins and Rings

Artistic pins, rings and emblems. Finest quality. Reasonable prices from 55c up. Write today. Dept. 6.

FREE Catalog

Metal Arts Co., Rochester, N. Y.

## LEARN MENTAL TELEPATHY



## STEP AHEAD OF THE CROWD!

ROCKET YOUR AMBITIONS into reality. Get things you want banish Fear, solve problems quickly! Proven methods and experience. Write TODAY for startling FREE booklet and convincing FACTS. Send \$1 for 5 amazing lessons and GREAT KEY THOUGHT. Atlantic Gold, Box 582 B, Harrisburg, Pa.

The Dennison Handy Helper Says:

"PLAN TO BUY U. S. WAR BONDS AND STAMPS REGULARLY ... AND STICK TO IT"

# Dennison





GUMMED LABELS STICK TO IT, TOO

DENNISON MFG. CO., Framingham, Mass.





# Learn to Mount Birds



## Fun—Fascination—Profits

Be a Taxidermist. All Secrets Revealed. Learn at Home



### Save Your Hunting Trophies

Mount (stuff) expertly your valuable game-birds, animals, fish, game-heads. Preserve them just like life. That is Taxidermy. Learn at home by mail. Decorate home and den with nature's art. Make undreamed-of profits in spare time, in your shop. You can. Will you? Win fame as a taxidermist. Investigate. Mail coupon NOW.

### FUN WITH A FEW LOADS

Yes. WAR makes shot-gun shells scarce. But just a FEW shells obtains a FEW DUCKS, and with TAXIDERMISTRY, you will have the grandest hunting season EVER. Taxidermy is fine beyond description for MEN AND BOYS. Be one of our 300,000 students. We invite YOUNG MEN, boys, youths.

"Eat your trophies and have them too"

### Mail Coupon

Or a postcard will do. No obligation on your part. The beautiful Book, with hundreds of entrancing pictures is free. Don't miss your Only Chance to get this remarkable book Free and Postpaid. Write today. State your Age.



**Northwestern School of Taxidermy**  
3398 Courtney Bldg. Omaha, Neb.

### Wild Game Not Needed

Use common specimens, squirrels, rabbits, chicks, pets, owls, pigeons—even frogs. Make useful articles like those shown here. Mount them in human and humorous positions. This is craft and novelty taxidermy. It's fun—and profitable. Ad included in our unique lessons. It's marvelous. Write the school this minute.

### BIG PROFITS From Your Shop in Spare Time

Many students earn from \$40 to \$75 monthly in spare time. Some earn thousands of dollars each year. Sportsmen bring their trophies to be mounted. Besides you can sell your own novelty groups for homes, dens and for merchants' window display.

### LEARN TANNING

The lessons teach tanning harness, shoe, crum leather, also furs. Expert methods. Very profitable.

### FREE BOOK

Northwestern School of Taxidermy, 3398 Courtney Bldg., Omaha, Neb.  
Gentlemen: Please send me now, your free 64-page book on Taxidermy without any obligation on my part. Tell me how I can learn beautiful Taxidermy at home.

Name.....Age.....

Address.....



and Animals—Send Coupon for Free Book







## Add a Language To Your Assets by LINGUAPHONE

★ In War, in Peace, ability to speak another language is an asset which will tip the scales in your favor... open new opportunities, earn promotion.

*Speak* { ITALIAN POLISH  
SPANISH NORWEGIAN  
PORTUGUESE FRENCH  
RUSSIAN GERMAN  
JAPANESE

or any of 20 other languages

Quickly, easily, correctly by  
**LINGUAPHONE Ear-Eye METHOD**

This amazingly simple and delightful way to learn to speak any of 29 languages in your own home is the work of 150 of the foremost language teachers of famous universities.

You merely LISTEN to the voice of native teachers. Your EYES follow the text and illustrations... and before you are aware you are repeating the questions and answers as naturally as speaking with a native.

Endorsed by educational authorities, Linguaphone is used by Army, Navy, Flying, Signal, Medical Corps and other services; by 14,000 schools, colleges and by more than one million home-study students. Do not confuse Linguaphone Ear-Eye Method with any other.

Send for FREE book. Call for FREE Demonstration.

**LINGUAPHONE INSTITUTE**

55 RCA Bldg. • New York (20), N. Y. • CI 7-0830

## LEARN MONEY-MAKING CARTOONING

Being taught method that has been used by creators of "Terry & Pirates," "Wash Tubbs," "Out Our Way," "W. C. Fields," "Reg'lar Fellers," "Strange As It Seems," "Secret Agent X-9," and many others. Earn while learning. Rush the for picture book "First money and how to get it" and full details a cartoonist.

THE LABRON SCHOOL, 4231 Railroad Building, Cleveland 14, Ohio

## YOUR OPPORTUNITY!

TECHNICAL BOOKS of All Publishers for Free Examination. Write today for free copies of catalogues. MODERN TECHNICAL BOOK CO., 55 West 42 St., New York 18, N.Y.


## Short-Cut Mathematics COMBINED WITH Practical Mechanics Simplified

NEW 2-in-1 reading course! Now you can learn the speedy, simplified system of calculation used by draftsmen, engineers, accountants, "master minds" on the spot. Learn easy way to multiply 4 figures by 4 figures without using old-fashioned multiplication; add long columns of figures this lightning short-cut method. Learn horsepower, slide rule, micrometer, logarithms, word measure, pipes, etc. etc. Large illustrated volume complete with answers. Satisfaction or refund. Amaze friends with your master-like mental powers.

**FREE** Complete details, mail coupon TODAY!

RELIQU CO. 321 S. Wabash Dept. E-204 Chicago  
Please send free detail about "Short-Cut Mathematics and Practical Mechanics Simplified." No obligation.

Name \_\_\_\_\_  
Address \_\_\_\_\_



## WANTED

### 1000 High School Seniors

TO COME TO CALIFORNIA TO ENROLL  
IMMEDIATELY IN THE AERO TECH  
COMBINED AVIATION AND 4TH YEAR  
HIGH SCHOOL COURSE

Make the most of the next twelve months by finishing your fourth year of high school at Aero Tech where you can combine with it aircraft mechanics or engineering studies. Even though you may be back in high school, if you act now, you can still enroll in these courses.

### GAIN A FULL YEAR OF AVIATION TRAINING

You will be doing for more for yourself and your country by combining your last year in high school with aircraft mechanics or engineering. Whether you go into military service or war industry at the end of your training, you will possess technical qualifications that will raise you above the average of others and open the door to specialized assignments.

### APPROVED HIGH SCHOOL AND AVIATION COURSES

State Certified and CAA licensed instructors supervise your high school and aviation training. When successfully completed you receive your High School diploma in addition to your Certificate of Award covering your aviation course. If you combine the High School and the Master Mechanics Courses you would then be eligible to qualify for CAA Airplane and Engine license.

### ONE AND TWO YEAR ENGINEERING

You can continue your technical studies by taking the Aero Tech one or two year Aeronautical Engineering Course. Advance training in post graduate subjects and research is also available.

### YOU CAN EASILY TRANSFER

Merely secure a transcript of your grades and full credit will be given you when you enroll at Aero Tech.

### IDEAL LIVING IN CALIFORNIA

You will probably choose to live in Aero Tech's new dormitories adjoining the campus. Under the supervision of the Students Welfare Council, you will enjoy comfortable lodgings, wholesome food and real companionship.



### SEND COUPON TODAY for Enrollment Application

**AERO INDUSTRIES TECHNICAL INSTITUTE**

5247 W. San Fernando Road, Los Angeles 26, Calif.

Gentlemen: Please send details and enrollment application on course checked below without obligation.

Master Mechanics with ☐ or without ☐ 4th year high school  
Aeronautical Engineering with ☐ or without ☐ 4th year high school  
Special Aircraft Production with ☐ or without ☐ 4th year high school

NAME \_\_\_\_\_ AGE \_\_\_\_\_

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ A-4-s








# WHERE OUR WAR WORDS COME FROM: **Strategy** means, *Leading an Army*

**STRATEGY** comes from the Greek verb *strategia*, "to be leader of an army." Both you and your children will enjoy the thousands of fascinating etymologies (word origins) in WEBSTER'S NEW INTERNATIONAL DICTIONARY Second Edition. It is truly the foundation book for home education! It tells you everything you want to know about words, 600,000 of them, 122,000 more than in any other dictionary. Mail the coupon today for free illustrated booklet of interesting word origins and ask any bookseller to show you the Genuine Webster—the Merriam Webster—identified by the circular trade-mark. G. & C. Merriam Company, 364 Federal Street, Springfield 2, Mass.

Advt. Copyright by G. & C. Merriam Co.

**WEBSTER'S  
NEW INTERNATIONAL  
DICTIONARY  
Second Edition**





**This  
Amazing Chart**

**Makes  
TRIGONOMETRY  
EASY**

**40 TRIGONOMETRIC EQUATIONS** quickly found on TRIG-EASY CHART. All errors through use of wrong equations eliminated. Angles and dimensions accurately determined **Without Knowing Higher Mathematics**

With this amazing TRIG-EASY Chart YOU quickly solve Trigonometry problems. War Workers! Math Students! Qualify NOW for big pay in Tool and Die—Machine Shop—Sheet Metal—Die Bore—Patterns—Layout—Inspection—Drafting Departments, etc. Prepare for a more important job in America's busy wartime industry. TRIG-EASY Chart is the short cut. Send only 50c (coin) for TRIG-EASY Chart with full instructions—**MONEY BACK GUARANTEE.**

**QUALIFY FOR BIG PAY—EARN A RAISE**

E. H. NEEDHAM (Trig-Easy) Dept. 1-L. Culver City, Calif.  
Dear Sir—Enclosed find 50c for Trig-Easy Chart and instructions

Name \_\_\_\_\_  
Address \_\_\_\_\_  
City \_\_\_\_\_ State \_\_\_\_\_

NOVEMBER, 1943




# HAVE THIS STAFF OF SPECIALISTS HELP YOU **PATENT** *your* **IDEA**

**NO MATTER HOW GOOD** your invention may be, the commercial value of your patent protecting that invention depends upon the careful preparation of strong claims covering it. This firm of Registered Patent Attorneys has helped and wisely advised individual inventors for almost half a century. Our staff is made up of specialists—men who are intimately familiar with those particular classes of inventions to which they devote their entire time. The object of this organization is to secure for its clients the strongest possible patents which their inventions warrant.



**Present War Production  
A GOLDEN  
OPPORTUNITY  
for Inventors**

Don't forget—your patent will give you 17 years' exclusive right to make, use and sell. Inventions adopted now as substitutes for materials and equipment not obtainable will have become regular articles of our daily lives when the Victory is won. The time to act—to protect your idea for immediate and future commercialization—is NOW!



**Send at once for these Books**

**FREE** Here are two plainly written books which tell you step by step how to safeguard your invention. Give you valuable ideas on commercializing your patent. With these two books you can protect your idea. We will send you a set of the books and "Evidence of Invention" form. Don't delay—get the coupon below from the mail AT ONCE!



**VICTOR J.  
EVANS & Co.**

*Merlin M. Evans*

**REGISTERED PATENT ATTORNEYS  
MAIN OFFICE: 740-M MERLIN BLDG.  
WASHINGTON, D. C.**

Please send me your books, "Patent Protection" and "How to Sell an Invention" without cost or obligation.

NAME \_\_\_\_\_  
CITY AND STATE \_\_\_\_\_

Buy War Savings Bonds and Stamps regularly.





LET

*Bernarr Macfadden*

Help You

## STRENGTHEN YOUR EYES

### A Revolutionary Series Of Exercises

Are you bothered with eye strain? Like thousands of others, you may relieve overworked, suffering, tired eyes if you follow the advice of Bernarr Macfadden. *Remember Mr. Macfadden, at 75 years of age, has perfect vision—needs no glasses!* Now you can know some of the secrets of eye strengthening he has discovered.

Entirely different—based on revolutionary principle, this course of exercises comes to you in a 24x22 in. chart in color, complete with easy-to-understand instructions. They'll amaze you with their beneficial results.

**SOLD WITH AN UNCONDITIONAL MONEY-BACK GUARANTEE—ONLY \$1.00**

So sure is Mr. Macfadden that after a short time you probably will be able to see and feel tangible results from these exercises that he offers them to you with an unconditional money-back guarantee. If you are not satisfied, you may return chart within 10 days and your money will be refunded. **AREN'T YOUR EYES WORTH A DOLLAR BILL TO YOU?**

#### SEND NO MONEY

Merely pay the postman \$1.00 plus 12c postage and handling charges. Or if you send your check or money order of \$1.00 with the coupon, we will be glad to pay postage.

MACFADDEN FOUNDATION, DEPT. 27  
535 FIFTH AVENUE, NEW YORK, 17, N. Y.

Please send me Bernarr Macfadden's "Thousand Shifts" eye course. I will pay the postman \$1.00 plus 12c postage and handling charges.

I enclose \$1.00 (check or money order).

Name \_\_\_\_\_

Address \_\_\_\_\_

City \_\_\_\_\_ State \_\_\_\_\_

## PATENTS PERSONAL SERVICE

My Personal service assures strictest confidence on all your patent problems. Send me a model or drawing or sketch and description of your invention, and \$5.00. I will make a search and report promptly as to its patentability and send you a copy of my 72 page booklet. Or, if you prefer to read my booklet first, write today for FREE copy. Registered Patent Attorney

L. F. Randolph, 340-D Columbian Bldg., Washington, D.C.

To secure this booklet, send this advertisement to L. F. Randolph, 340-D Columbian Bldg., Washington, D.C.

## don't WORRY

Why put up with years of needless discomfort and worry? Try a Brooks Automatic Air Cushion. This marvelous appliance permits the opening to close, yet holds reducible rupture securely, comfortably—day



and night. Thousands report amazing results. Light, neat-fitting. No hard pads or stiff springs to chafe or gouge. Made for men, women and children. Durable, cheap. Sent on trial to prove it. Never sold in stores. Beware of imitations. Write for Free Book on Rupture, no-risk trial order plan, and proof of results. All correspondence confidential. **BROOKS COMPANY, 160-C State St., Marshall, Mich.**

### AIRCRAFT Designing & Engineering



RYAN STUDY  
COURSE OF  
AIRCRAFT  
DESIGNING &  
ENGINEERING

You can learn to design airplanes. A Ryan Home Study Course in Aeronautics, Engineering will prepare you quicker for a job with good pay and a future. Easy to understand. No experience necessary.

**FREE 24 Page Valuable Illustrated Booklet**

**RYAN AERONAUTICAL INSTITUTE**

4111 Lindbergh Field, San Diego, California

## Inventions Wanted Patented or Unpatented

Inventions can now be safely sold without patenting expense. If you have a practical, useful idea for an invention, either unpatented or patented, write today!

**Chartered Institute of American Inventors**

Dept. 3, 631 Pa. Ave. N. W., Washington, D. C.



# PATENTS

## AND TRADE MARKS

### C. A. SNOW & CO.

Registered Patent Attorneys Since 1875

Write for Free Book and "Certification of Invention" form

427 SNOW BUILDING, WASHINGTON 1, D. C.



**PATENT YOUR IDEAS**  
SEND FOR FREE BOOK

**HOW TO OBTAIN A PATENT**

Written by Former Member Examining Corps (1822-1840) U.S. Patent Office

**CARL MILLER, Registered Patent Attorney**  
Former Member Examining Corps U. S. Patent Office

Woolworth Bldg., Dept. 113 C New York. Bond Bldg., Dept. 113 C Washington, D. C.

**Learn PHOTOGRAPHY at Home**

Spandid opportunities. Prepare in spare time. Easy plan. No previous experience needed. Common school education sufficient.

**American School of Photography**  
2315 M Street, N. W., Dept. 113 C, Washington, D. C.

## ARC WELDING

The **HOBART School** is a Non-Profit Institution. Founded to furnish industry with trained operators and to further the interests of arc welding the Hobart School from the beginning has been operating on a basis of the students sharing in material costs only. Nevertheless, the Hobart Course is an intensive one designed to prepare you for a big pay job as soon as you graduate. In individual booths welders let you get the most from the course. Learn the Hobart way for bigger pay. *Write for Further Details*

**Pays Big!**

**HOBART TRAINS YOU IN SIX WEEKS. A big demand for welders will continue after the war. Start now! Costs little.**



**HOBART**

**SCHOOL OF ARC WELDING, Box P-1131, TROY, OHIO**


**FREE booklet**

on how to obtain a patent



# IMAGINE THEIR JOY WHEN THEY FOUND THEY COULD PLAY

This easy-as-ABC way:



## LEARNED QUICKLY AT HOME

"I didn't dream I could actually learn to play without a teacher. Now when I play for people they hardly believe that I learned to play so well in so short a time."  
\*R. S. C., Calif.



## Plays at Dances

"Your lessons have been most satisfactory. I can play all of the popular songs. I have earned money playing at dances."  
\*E. N. J., New York



## Plays on Radio

"I can't keep from telling you that I have a good position playing from KTHS Hot Springs, Ark., every morning."  
J. S., Okla.

## What Instrument Would You Like to Play?

JUST name your instrument and we'll show you how you can learn to play it—quickly, easily, in spare time at home. Never mind if you don't know one note of music from another—don't worry about 'special talent'. And forget all you've ever heard about music's being hard to learn.

The truth of the matter is that *thousands now play who never thought they could!* Yes, men and women everywhere have discovered this amazingly easy way to learn music at home. Now they are enjoying the thrilling satisfaction of playing the piano, violin, guitar, saxophone or other favorite instruments. Some of them are playing in orchestras and over the radio; others are teaching music, making money in spare or full time. And thousands are having the time of their lives playing for their own enjoyment and the entertainment of their friends.

### LEARN TO PLAY BY NOTE

Piano Guitar  
Violin Saxophone  
Organ Mandolin  
Tenor Banjo  
Hawaiian Guitar  
Piano Accordion  
Or Any Other Instrument

A USEFUL XMAS GIFT!

## AUDELS Carpenters and Builders Guides 4 vols. \$6



### Inside Trade Information One

How to use the steel square—How to file and set squares—How to build furniture—How to use a square box—How to use the chalk line—How to use rules and scales—How to make joints—Carpenter's or hammer—Solving measuring problems—Estimating strength of timbers—How to set girders and sills—How to frame houses and roofs—How to estimate costs—How to build houses, barns, garages, bungalows, etc.—How to read and draw plans—Drawing up specifications—How to estimate—How to use settings 12, 13 and 17 on the steel square—How to build bents and scaffolds—sky lights—How to build stairs—How to put on interior trim—How to hang doors—How to lay—lay floors—How to paint

**Audels Trade Information** for carpenters, builders, joiners, building mechanics and all woodworkers. These Guides give you the short-cut instructions that you want—building new methods, ideas, and plans, over 1000 and every building instruction. An easy reference to find the information and at first a practical daily helper and Quick Reference for the master worker. Carpenters everywhere are using these Guides as a helping hand to speed their work, better work and better pay. To get the advantage for yourself, simply fill in and mail the FREE COUPON below.



THEO. AUDEL & CO., 49 W. 23rd St., New York City

Mail Audels Carpenters and Builders Guides, 4 vols., on 7 days' free trial. If O.K. I will remit \$1 in 7 days, and \$1 on each until \$6 is paid. Otherwise I will return them. No obligation unless I am satisfied.

Name \_\_\_\_\_

Address \_\_\_\_\_

Occupation \_\_\_\_\_

Reference \_\_\_\_\_

PSM

## 10 INCH SLIDE RULE FREE

With Complete and Simple Instructions for use!

Magnifying Indicator to genuine LUCITE Scales A-B-C-D-E-F



Anyone Can Learn

**DON'T** let Slide Rule scare you. Learn in few hours to do lightning calculations. Divide, multiply, and ratios, percentages, squares, areas, etc. Send name on coupon below for this wonderful course of instruction. The Slide Rule and How to Use It and get the 10 inch Slide Rule FREE with your course. Full price for course and Slide Rule both, only \$2.98. Limited quantity! Rush your order!

WILCOX & FOLLETT CO., Dept. 311  
1255 S. Wabash Avenue Chicago (3) Ill.

WILCOX & FOLLETT, Dept. 311  
1255 S. Wabash, Chicago (3) Ill.

Mail the new "Slide Rule and How to Use It" including work sheets, answer book and 10" Mannheim Type Slide Rule with Lucite Magnifying Indicator, all in one cover

☐ I enclose remittance in full for \$2.98.  
☐ Ship COD, I will pay postman \$2.98, plus charges.

Name \_\_\_\_\_

Address \_\_\_\_\_

City \_\_\_\_\_

State \_\_\_\_\_



# The Greatest ENCYCLOPEDIA of FARMING

FACTS, METHODS, IDEAS, SHORT-CUTS, TABLES and PRACTICAL INFORMATION

## Ever Packed Into One Volume!

32 FARM EXPERTS Show You How to Select and Operate a Small Farm for Security and Profit

IF YOU are hankering to enjoy the independence which only a farm can give, here is the book you absolutely need. A PRACTICAL GUIDE TO SUCCESSFUL FARMING was written under the editorial supervision of Wallace S. Moreland, by 35 outstanding authorities on modern farming enterprises, including POULTRY FARMING, DAIRYING, RAISING COWS, PIGS, SHEEP, RAISING VEGETABLES, TREE FRUITS, GRAPES and SMALL FRUITS, CHICKENS, etc. Comprehensive sections on FARM FINANCE and MANAGEMENT, FARM EQUIPMENT, PEST CONTROL, SOIL CONSERVATION, etc. You get the latest methods of producing for profit. Here is the long needed complete encyclopedia of farming for either beginner or veteran!



Over 1000 Pages  
400 Illustrations

**SEND NO MONEY Read 7 Days on Trial** Just mail coupon. A copy will be sent you on approval. Examine the 400 pictures, read about what it costs you, then decide whether you wish to own it at the low price and easy terms. Garden City Publishing Co., Inc., Dept. 1115 N.Y., Garden City, N.Y.

GARDEN CITY PUB. CO., INC.

Dept. 11 P.S.M., Garden City, N.Y.

Yes, send me a 1 volume Guide to Successful Farming on approval for 7 days for examination. When the time comes either return it or keep it and send \$1.95 as first payment plus a few cents postage and 10c monthly for two months until the special low price of \$3.95 is paid.

Mr. \_\_\_\_\_  
Mrs. \_\_\_\_\_  
Miss \_\_\_\_\_  
PLEASE PRINT

Address \_\_\_\_\_

Occupation \_\_\_\_\_  
If you send \$3.95 in full payment, we pay postage. Same day ad. applies. Slightly higher in Canada—100 Broad Street, Toronto.

## AUDELS NEW MACHINISTS HANDYBOOK NOW READY!

**1600 PAGES FULLY ILLUSTRATED**

**\$4 COMPLETE • PAY ONLY \$1 MO.**

## Prepare!

A KEY TO SHOP PRACTICE

A READY REFERENCE

5 PRACTICAL BOOKS IN ONE!  
60 FULLY ILLUSTRATED CHAPTERS

Get This Information for Yourself  
Mail Coupon Today. No Obligation  
Unless Satisfied. ASK TO SEE IT.

THEO. AUDEL & CO., 40 WEST 23rd STREET, NEW YORK  
Mail AUDELS MACHINISTS & TOOLMAKERS HANDY BOOK. \$4.00 7 Days Free Trial. If I will refund \$1 in 7 days and \$1 monthly until \$4 is paid. Otherwise I will return it.

Name \_\_\_\_\_  
Address \_\_\_\_\_  
Occupation \_\_\_\_\_  
Reference \_\_\_\_\_

## Get this Handy OHMITE Ohm's Law Calculator!

**10¢**

**Figures Ohms, Watts, Volts, Amperes—Quickly, Easily!**

Solves any Ohm's Law Problem with one setting of the dial. Requires no slide rule knowledge. All values are direct reading. Scales on two sides cover the range of currents, resistances, wattages and voltages commonly used in Radio and Electrical Work. Size 4 1/2" x 9".

Send only 10c in coin to cover cost of handling.  
**OHMITE MFG. CO., 4943 Flourway St., Chicago, Ill.**

## SPRAY PAINTING

## OPERATORS NEEDED

**Make Big Money—Learn At Home**

This book gives you detailed instructions for industrial and commercial spray painting essentials to war production. Full information on pigments, thinners, varnishes, techniques, spray guns of all types, fancy finishes with a special section on W.A.R. work. Easy to understand. Cloth bound. 125 pages—fully illus. Only \$1.50 Postage prepaid if cash in advance.

**Order Today**

**FREDERICK J. ORR & CO., Dept. P-111, 600 W. Van Buren St., Chicago, Ill.**

## Learn TOOL DESIGN

Quickly, as Machine or Tool Designer through spare time home study. Many making \$100 to \$125 a week. No previous industry or tool design experience necessary. Rush name and kind of job wanted today for full details.

**OHIO INSTITUTE OF TECHNOLOGY, Box 128, Greenville, Ohio**

## THERE'S MONEY IN CARTOONS!

**RAYE BURNS** will teach you HOW to BEAT ORIGINAL CARTOONISTS at home that you may BEAT. Course includes 20 lessons and over 400 illustrations. All for Only **\$2.85**

Send name and address for free details.

**RAYE BURNS SCHOOL, Dept. B, Box 128, CLEVELAND 3, OHIO**

## STUDY ENGINEERING AT HOME

**With A Chartered Educational Institution**

Courses in ENGINEERING: Electrical, Civil, Mechanical, Drafting, Architectural, Steam, Aeronaut, Radio, Structural, Mining, Industrial, Highway, Power, Marine, Chemical.

Courses in ARTS AND SCIENCES: Philosophy, Education, Letters, Public Health, Medical Jurisprudence, Psychology, Sociology, Physics, Chemistry, Geography, Political Science, Theology, Law, Business and Commerce, Accounting, Mathematics, Statistics, Agriculture.

**McKinley-Roosevelt Incorporated, 4610 N.C., Sheridan Road, Chicago 40**

## NEW PRACTICAL RADIO FOR WAR TRAINING

**ONLY \$2.95 COMPLETE**

## RADIO Made Easy

**DO RADIO WORK IMMEDIATELY**

Begin doing practical radio work with the first chapter. For any spare time and a few minutes in the day. No previous experience. Learn how to find parts and parts. Simple, clear, picture-clear explanations make basic radio knowledge easy to understand and to apply. This large manual is just like a complete course in radio. Repair radio for fun and profit. Get a wage paying radio war job, earn higher rank and pay in the Army.

**GET PRACTICAL RADIO TRAINING**

This unique, different home study manual will teach you quickly to do radio work. At first you will learn about parts, tubes, tests, simple circuits. Later chapters cover receivers, transmitters, test sets, trouble-shooting. New up-to-date 1942 edition, includes material on Electronics and Radar. Follows U.S. Office of Education syllabus.

**SEND NO MONEY**

Examine the complete Practical Radio Manual for 10 days, without risk or obligation. See how easy it is to learn radio the new way. Send no money. Simply pay your mailman only \$2.95 plus a few cents postage. You must be satisfied or your money will be refunded in full. Write today.

**SUPREME PUBLICATIONS, 328 E. Jefferson St., Chicago 6, Ill.**





R. C. HOOPES  
President

On duty with the Army and Navy Fyr-Fyter Extinguishers serve America in all parts of the war. On the home front, too, they help protect the nation against crippling fire losses. Businesses and institutions essential to the war effort can now under preference rating, secure Fyr-Fyter Extinguishers. After the war Fyr-Fyters will be available to all. Valuable Fyr-Fyter Distributorships will then be open for our enlarged and improved line. Send us some information about yourself if you would like to be considered for our post-war organization.

**THE FYR-FYTER CO.**  
Dept. 92 Dayton 1, Ohio

**Fyr-Fyter**

**BIGGER PAY for ELECTRICAL & RADIO Trouble Shooters!**

**GET THIS SENSATIONAL NEW TROUBLE-SHOOTING MANUAL**  
ELECTRICIANS! RADIO MEN! Beguine, old timer! This new COYNE Trouble Shooting Manual saves time, avoids errors. Helps you do better work, make more money. Examine 5 days FREE-mail coupon.

**4 BOOKS IN ONE!**

Big 4x11" volume contains:  
• 300 Shop Prints, Wiring Diagrams on Motors, Radios, Electronics, etc.  
• New "Step-by-Step" Trouble Shooting Course.  
• Electrical-Radio Dictionary.  
• Spare Time Work Lessons.  
**FREE 1 Yr. Technical Service** by mail from Coyne Staff, on your trouble-shooting problems.

**SEND NO MONEY!**

See amazing offer below. You need this practical book NOW! Act!

**FREE TRIAL COUPON**  
M. C. LEWIS, Pres. Dept. 81-4  
COYNE ELECTRICAL SCHOOL  
800 S. Paulina St., Chicago 12, Illinois  
Send postpaid, new COYNE Electrical & Radio Trouble Shooting Manual. Within 5 days after receiving I'll either return it or send \$1.95 and then \$3 monthly until total of \$7.95 is paid. Cash price \$7.15—YOU SAVE 16%, same 5-day free trial and return privilege.

NAME \_\_\_\_\_  
ADDRESS \_\_\_\_\_  
CITY \_\_\_\_\_ STATE \_\_\_\_\_

**5 DAY FREE TRIAL**

**COYNE ELECTRICAL and RADIO TROUBLE SHOOTING MANUAL**

# HOW YOU CAN BUILD A MIGHTY ARM



**THIS BOOK Shows You HOW TO BUILD A MIGHTY ARM AND 16-in. BICEPS ONLY 25c TO YOU**

## A COMPLETE PICTURE COURSE ON ARM BUILDING

Why not get an arm of might with the power and grip to obey your physical desires? Weakling—whose arms were merely pieces of skin and bone have taken this course and in a short time developed themselves into strong men of powerful proportion with bulging biceps and heavy forearms. Strong, solid arms of power that are respected by men and admired by women.

## Learn The WORLD'S GREAT SECRETS OF ARM STRENGTH

This course is especially planned to build every muscle in your arm. Many pupils have developed a pair of biceps shaped like a horseshoe, and just as strong. And a pair of forearms that show the double bicep formation. The new call a "horseshoe" bicep and a "bow" are deep and thick with well-carved lines. The forearm bulges with bulk, the great outer wrist is as big as a horse's knee. The forearm bulges with bulk, and their wrists are alive and writhing with every kind of power. Would you like to have a magnificent arm like the figure pictured above?

You can't make a mistake. The strongest armed man in the world wrote this course for you. He's great even to stand as proof that you too can succeed. You get his secrets, the secrets of strength development illustrated and explained as you learn it. Rush now! You are not limited to the 5-day trial. Molding a Mighty Bicep, Molding a Mighty Chest, Molding a Mighty Grip, Molding a Mighty Leg.

**SEND FOR THESE FIVE FAMOUS COURSES FORMERLY \$5.00 EACH. NOW IN BOOK FORM ONLY 25c EACH OR ALL 5 FOR \$1.00.**

Mail your order now and "NERVES OF STEEL, MUSCLES LIKE IRON" will be included FREE! It is a priceless book to the strength fan and muscle builder. Full of pictures of marvelous and old men who will show you what The Jowett Institute Power Course has done for them and how it can do it for you. A man of marvelous muscular symmetry and dynamic strength. Reach out... Grab this last chance—limited time offer.

Jowett Inst. of Physical Culture  
210 Fifth Ave., N. Y. 1, N. Y.



**Book With Photos of Famous Strong Men FREE**  
...and how you can become one of them!

**Use Your Mail Coupon NOW!**

**JOWETT INSTITUTE OF PHYSICAL CULTURE**  
210 Fifth Ave., New York, 1, N. Y. Dept. 3811

George F. Jowett: Your proposition looks good to me. Send, by return mail, prepaid, the courses checked below for which I am enclosing:

- |  |  |
|--|--|
| <input type="checkbox"/> All 5 courses for \$1   | <input type="checkbox"/> Molding a Mighty Grip, 25c  |
| <input type="checkbox"/> Molding a Mighty Arm, 25c   | <input type="checkbox"/> Molding a Mighty Chest, 25c |
| <input type="checkbox"/> Molding a Mighty Back, 25c  | <input type="checkbox"/> Molding a Mighty Leg, 25c   |
| <input type="checkbox"/> Send all 5 courses P. O. O. (\$1 plus postage). No orders less than \$1 sent P. O. O. |  |

Name \_\_\_\_\_ AGE \_\_\_\_\_

Address \_\_\_\_\_

**GEORGE F. JOWETT**  
"Champion of Champions"  
Holds more strength records than any other teacher or athlete.



## ADVERTISING

**MAIL-Order or agent ad reaching 1,000,000 families throughout United States \$15.40 inch Newspaper, magazine, mailing-list, catalog, free Chicago Advertising Agency, 20-22 West Jackson, Chicago**

**ADVERTISE** -newspapers, magazines, Publishers Rates, Main Agency 121 Madison Avenue, New York City

**ADVERTISE** 34 words, 145 newspapers, 40-50 Lasts Free Advertising Bureau, 4615 P Cottage Grove, Chicago 15.

## AGENTS WANTED

**START Your Own Business** on our capital. Always your own boss. Hundreds average \$3,000 to \$5,000 annual sales year after year. We supply stocks, equipment on credit, 200 home necessities. Selling experience unnecessary to start. Wonderful opportunity to own pleasant, profitable business backed by world-wide industry. Write Raleigh Co., Dept. K-C-P-84, Freeport, Ill.

**CALL On Friends with Sensational Personal Christmas Cards** 50 or 1.00 up. Personal, 8 assembly. Also magnificent 3. Card 1.00 assortment. Profit 50c. Experience unnecessary. Samples on approval. Write B. B. 225 Fifth Ave., Dept. B-35, New York

**GOOD Paying Business** Silvering mirrors, plating autopaarts, reflectors, bicycles, bathroom fixtures, etc., by late method. No tools or shop required, outfit furnished. Free sample. Gunmetal Co., Ave. O, Decatur, Ill.

**EXCELLENT Side Line for Printing** Salesmen. Decalcomania Name Plates in small quantities. Also make money selling in auto on Automobile. Free Samples. Raico, 1483 Washington, Boston (U.S. Mass)

**BIG Bargains for Big Profits.** Men's used pants 25c, suits \$1.50, overcoats 50c, shoes 12.5c. Over 100 sensational values. Experience unnecessary. Free Wholesale Catalog. Superior 1830-K, Jefferson, Chicago

**Write me and I will send you Four Samples of aprons.** Christmas-New Year greeting cards and much more. Send your try signs with picture and letter particulars. Absolutely free. Paul H. L. Amark 1224 Park Ave. Edinboro, Pa.

**TAKE orders for new sensational Plastic Lifetime Reproductions of any photo or negative. Amazingly beautiful.** Big earning opportunity. Part or full time. Get details quickly. Quaker Service Co., 514 Walnut St. Philadelphia 14

**DISTRIBUTORS** agents permanent commission attractive. Automatic delivery. No competitor. Low cost. High profit. Send for details. Chan Chan Company, 515 A B. 11th Street, Los Angeles

**AGENTS** Coin Money. It's New. It's Hot. Everyone wants a radiant plastic plaque of loved ones. Commission advanced. We deliver. Collect. Kondon, Box 131 Upper Darby, Pa.

**STRANGE** Try Shoe Polisher. Seize the Wild. Replaces thrifty patch. Saves. Simply glide over shoes. Samples sent on trial. Write 129 Astor, Chicago

**ADVENT** 100% Profit on Gold Leaf Window Letters, stores and offices. Free samples. Melaine Letter Co., 417 N. Clark, Chicago

**LICK After-war layoff?** Start own business home office. Book of describing "Conversion of 17 Tested Plans" free. Kutz Co. 24A Grand St. New York

**FREE** Water and oil concentrates, makes flavors, lotions, shampoos 72 products, labels, bottles furnished. Quaker, P-30039 Russell, Detroit

**LUMINOUS** Paint (shines in Dark) Spectacular Dollar Seller. Rush name for profitable de. and free sample. Ward, 87B, Barbrank, Connecticut

**SCIENTIFIC** Manufacturing Processes. Simplified. Profitable. Trade Secret. Profits to 1,500. Lists free. Thermograph, Florida 4, Ill. no.

**PLAYING** card game 250% profit. Sample game 25c. Box 441, Denver 1, Colorado

ANTIQUES, RELICS  
INDIAN GOODS

**SWORDS,** rapiers, daggers, pistols, armor; illustrated catalog 25c. Robert Abels, 8401, Lexington Ave., N. Y.

**25 GENUINE** Indian Arrow heads, \$1.00. Catalog, Geo. Holder, Glenwood, Ark.

## AUTHORS SERVICE

**BEGINNER WRITERS**-Ten Basic Lessons 50c. Anderson, Vineburg, California.

**NEW Writers** Wanted to re-write ideas in papers, magazines, books. Spend opportunity to break into profitable writing. Send Rush postcard for Free Details. Comfort Writer's Service, 210-M, South Beach, (21), St. Louis, Mo.

## AUTOMOBILES

**NOTES** On Automobile Ignition Systems. A collection of all the latest systems employed in 1938-1942 automobiles. Includes order number design, wiring orders, diagrams, basic construction of equipment and principles of operation. \$1.00. Write: Electric Ignition Service Box 245, Main A, Dallas, Texas

**With \$12.48** Take home \$3 gives surprise. 16.50. 24.00. 31.50. 39.00. 46.50. 54.00. 61.50. 69.00. 76.50. 84.00. 91.50. 99.00. 106.50. 114.00. 121.50. 129.00. 136.50. 144.00. 151.50. 159.00. 166.50. 174.00. 181.50. 189.00. 196.50. 204.00. 211.50. 219.00. 226.50. 234.00. 241.50. 249.00. 256.50. 264.00. 271.50. 279.00. 286.50. 294.00. 301.50. 309.00. 316.50. 324.00. 331.50. 339.00. 346.50. 354.00. 361.50. 369.00. 376.50. 384.00. 391.50. 399.00. 406.50. 414.00. 421.50. 429.00. 436.50. 444.00. 451.50. 459.00. 466.50. 474.00. 481.50. 489.00. 496.50. 504.00. 511.50. 519.00. 526.50. 534.00. 541.50. 549.00. 556.50. 564.00. 571.50. 579.00. 586.50. 594.00. 601.50. 609.00. 616.50. 624.00. 631.50. 639.00. 646.50. 654.00. 661.50. 669.00. 676.50. 684.00. 691.50. 699.00. 706.50. 714.00. 721.50. 729.00. 736.50. 744.00. 751.50. 759.00. 766.50. 774.00. 781.50. 789.00. 796.50. 804.00. 811.50. 819.00. 826.50. 834.00. 841.50. 849.00. 856.50. 864.00. 871.50. 879.00. 886.50. 894.00. 901.50. 909.00. 916.50. 924.00. 931.50. 939.00. 946.50. 954.00. 961.50. 969.00. 976.50. 984.00. 991.50. 999.00. 1006.50. 1014.00. 1021.50. 1029.00. 1036.50. 1044.00. 1051.50. 1059.00. 1066.50. 1074.00. 1081.50. 1089.00. 1096.50. 1104.00. 1111.50. 1119.00. 1126.50. 1134.00. 1141.50. 1149.00. 1156.50. 1164.00. 1171.50. 1179.00. 1186.50. 1194.00. 1201.50. 1209.00. 1216.50. 1224.00. 1231.50. 1239.00. 1246.50. 1254.00. 1261.50. 1269.00. 1276.50. 1284.00. 1291.50. 1299.00. 1306.50. 1314.00. 1321.50. 1329.00. 1336.50. 1344.00. 1351.50. 1359.00. 1366.50. 1374.00. 1381.50. 1389.00. 1396.50. 1404.00. 1411.50. 1419.00. 1426.50. 1434.00. 1441.50. 1449.00. 1456.50. 1464.00. 1471.50. 1479.00. 1486.50. 1494.00. 1501.50. 1509.00. 1516.50. 1524.00. 1531.50. 1539.00. 1546.50. 1554.00. 1561.50. 1569.00. 1576.50. 1584.00. 1591.50. 1599.00. 1606.50. 1614.00. 1621.50. 1629.00. 1636.50. 1644.00. 1651.50. 1659.00. 1666.50. 1674.00. 1681.50. 1689.00. 1696.50. 1704.00. 1711.50. 1719.00. 1726.50. 1734.00. 1741.50. 1749.00. 1756.50. 1764.00. 1771.50. 1779.00. 1786.50. 1794.00. 1801.50. 1809.00. 1816.50. 1824.00. 1831.50. 1839.00. 1846.50. 1854.00. 1861.50. 1869.00. 1876.50. 1884.00. 1891.50. 1899.00. 1906.50. 1914.00. 1921.50. 1929.00. 1936.50. 1944.00. 1951.50. 1959.00. 1966.50. 1974.00. 1981.50. 1989.00. 1996.50. 2004.00. 2011.50. 2019.00. 2026.50. 2034.00. 2041.50. 2049.00. 2056.50. 2064.00. 2071.50. 2079.00. 2086.50. 2094.00. 2101.50. 2109.00. 2116.50. 2124.00. 2131.50. 2139.00. 2146.50. 2154.00. 2161.50. 2169.00. 2176.50. 2184.00. 2191.50. 2199.00. 2206.50. 2214.00. 2221.50. 2229.00. 2236.50. 2244.00. 2251.50. 2259.00. 2266.50. 2274.00. 2281.50. 2289.00. 2296.50. 2304.00. 2311.50. 2319.00. 2326.50. 2334.00. 2341.50. 2349.00. 2356.50. 2364.00. 2371.50. 2379.00. 2386.50. 2394.00. 2401.50. 2409.00. 2416.50. 2424.00. 2431.50. 2439.00. 2446.50. 2454.00. 2461.50. 2469.00. 2476.50. 2484.00. 2491.50. 2499.00. 2506.50. 2514.00. 2521.50. 2529.00. 2536.50. 2544.00. 2551.50. 2559.00. 2566.50. 2574.00. 2581.50. 2589.00. 2596.50. 2604.00. 2611.50. 2619.00. 2626.50. 2634.00. 2641.50. 2649.00. 2656.50. 2664.00. 2671.50. 2679.00. 2686.50. 2694.00. 2701.50. 2709.00. 2716.50. 2724.00. 2731.50. 2739.00. 2746.50. 2754.00. 2761.50. 2769.00. 2776.50. 2784.00. 2791.50. 2799.00. 2806.50. 2814.00. 2821.50. 2829.00. 2836.50. 2844.00. 2851.50. 2859.00. 2866.50. 2874.00. 2881.50. 2889.00. 2896.50. 2904.00. 2911.50. 2919.00. 2926.50. 2934.00. 2941.50. 2949.00. 2956.50. 2964.00. 2971.50. 2979.00. 2986.50. 2994.00. 3001.50. 3009.00. 3016.50. 3024.00. 3031.50. 3039.00. 3046.50. 3054.00. 3061.50. 3069.00. 3076.50. 3084.00. 3091.50. 3099.00. 3106.50. 3114.00. 3121.50. 3129.00. 3136.50. 3144.00. 3151.50. 3159.00. 3166.50. 3174.00. 3181.50. 3189.00. 3196.50. 3204.00. 3211.50. 3219.00. 3226.50. 3234.00. 3241.50. 3249.00. 3256.50. 3264.00. 3271.50. 3279.00. 3286.50. 3294.00. 3301.50. 3309.00. 3316.50. 3324.00. 3331.50. 3339.00. 3346.50. 3354.00. 3361.50. 3369.00. 3376.50. 3384.00. 3391.50. 3399.00. 3406.50. 3414.00. 3421.50. 3429.00. 3436.50. 3444.00. 3451.50. 3459.00. 3466.50. 3474.00. 3481.50. 3489.00. 3496.50. 3504.00. 3511.50. 3519.00. 3526.50. 3534.00. 3541.50. 3549.00. 3556.50. 3564.00. 3571.50. 3579.00. 3586.50. 3594.00. 3601.50. 3609.00. 3616.50. 3624.00. 3631.50. 3639.00. 3646.50. 3654.00. 3661.50. 3669.00. 3676.50. 3684.00. 3691.50. 3699.00. 3706.50. 3714.00. 3721.50. 3729.00. 3736.50. 3744.00. 3751.50. 3759.00. 3766.50. 3774.00. 3781.50. 3789.00. 3796.50. 3804.00. 3811.50. 3819.00. 3826.50. 3834.00. 3841.50. 3849.00. 3856.50. 3864.00. 3871.50. 3879.00. 3886.50. 3894.00. 3901.50. 3909.00. 3916.50. 3924.00. 3931.50. 3939.00. 3946.50. 3954.00. 3961.50. 3969.00. 3976.50. 3984.00. 3991.50. 3999.00. 4006.50. 4014.00. 4021.50. 4029.00. 4036.50. 4044.00. 4051.50. 4059.00. 4066.50. 4074.00. 4081.50. 4089.00. 4096.50. 4104.00. 4111.50. 4119.00. 4126.50. 4134.00. 4141.50. 4149.00. 4156.50. 4164.00. 4171.50. 4179.00. 4186.50. 4194.00. 4201.50. 4209.00. 4216.50. 4224.00. 4231.50. 4239.00. 4246.50. 4254.00. 4261.50. 4269.00. 4276.50. 4284.00. 4291.50. 4299.00. 4306.50. 4314.00. 4321.50. 4329.00. 4336.50. 4344.00. 4351.50. 4359.00. 4366.50. 4374.00. 4381.50. 4389.00. 4396.50. 4404.00. 4411.50. 4419.00. 4426.50. 4434.00. 4441.50. 4449.00. 4456.50. 4464.00. 4471.50. 4479.00. 4486.50. 4494.00. 4501.50. 4509.00. 4516.50. 4524.00. 4531.50. 4539.00. 4546.50. 4554.00. 4561.50. 4569.00. 4576.50. 4584.00. 4591.50. 4599.00. 4606.50. 4614.00. 4621.50. 4629.00. 4636.50. 4644.00. 4651.50. 4659.00. 4666.50. 4674.00. 4681.50. 4689.00. 4696.50. 4704.00. 4711.50. 4719.00. 4726.50. 4734.00. 4741.50. 4749.00. 4756.50. 4764.00. 4771.50. 4779.00. 4786.50. 4794.00. 4801.50. 4809.00. 4816.50. 4824.00. 4831.50. 4839.00. 4846.50. 4854.00. 4861.50. 4869.00. 4876.50. 4884.00. 4891.50. 4899.00. 4906.50. 4914.00. 4921.50. 4929.00. 4936.50. 4944.00. 4951.50. 4959.00. 4966.50. 4974.00. 4981.50. 4989.00. 4996.50. 5004.00. 5011.50. 5019.00. 5026.50. 5034.00. 5041.50. 5049.00. 5056.50. 5064.00. 5071.50. 5079.00. 5086.50. 5094.00. 5101.50. 5109.00. 5116.50. 5124.00. 5131.50. 5139.00. 5146.50. 5154.00. 5161.50. 5169.00. 5176.50. 5184.00. 5191.50. 5199.00. 5206.50. 5214.00. 5221.50. 5229.00. 5236.50. 5244.00. 5251.50. 5259.00. 5266.50. 5274.00. 5281.50. 5289.00. 5296.50. 5304.00. 5311.50. 5319.00. 5326.50. 5334.00. 5341.50. 5349.00. 5356.50. 5364.00. 5371.50. 5379.00. 5386.50. 5394.00. 5401.50. 5409.00. 5416.50. 5424.00. 5431.50. 5439.00. 5446.50. 5454.00. 5461.50. 5469.00. 5476.50. 5484.00. 5491.50. 5499.00. 5506.50. 5514.00. 5521.50. 5529.00. 5536.50. 5544.00. 5551.50. 5559.00. 5566.50. 5574.00. 5581.50. 5589.00. 5596.50. 5604.00. 5611.50. 5619.00. 5626.50. 5634.00. 5641.50. 5649.00. 5656.50. 5664.00. 5671.50. 5679.00. 5686.50. 5694.00. 5701.50. 5709.00. 5716.50. 5724.00. 5731.50. 5739.00. 5746.50. 5754.00. 5761.50. 5769.00. 5776.50. 5784.00. 5791.50. 5799.00. 5806.50. 5814.00. 5821.50. 5829.00. 5836.50. 5844.00. 5851.50. 5859.00. 5866.50. 5874.00. 5881.50. 5889.00. 5896.50. 5904.00. 5911.50. 5919.00. 5926.50. 5934.00. 5941.50. 5949.00. 5956.50. 5964.00. 5971.50. 5979.00. 5986.50. 5994.00. 6001.50. 6009.00. 6016.50. 6024.00. 6031.50. 6039.00. 6046.50. 6054.00. 6061.50. 6069.00. 6076.50. 6084.00. 6091.50. 6099.00. 6106.50. 6114.00. 6121.50. 6129.00. 6136.50. 6144.00. 6151.50. 6159.00. 6166.50. 6174.00. 6181.50. 6189.00. 6196.50. 6204.00. 6211.50. 6219.00. 6226.50. 6234.00. 6241.50. 6249.00. 6256.50. 6264.00. 6271.50. 6279.00. 6286.50. 6294.00. 6301.50. 6309.00. 6316.50. 6324.00. 6331.50. 6339.00. 6346.50. 6354.00. 6361.50. 6369.00. 6376.50. 6384.00. 6391.50. 6399.00. 6406.50. 6414.00. 6421.50. 6429.00. 6436.50. 6444.00. 6451.50. 6459.00. 6466.50. 6474.00. 6481.50. 6489.00. 6496.50. 6504.00. 6511.50. 6519.00. 6526.50. 6534.00. 6541.50. 6549.00. 6556.50. 6564.00. 6571.50. 6579.00. 6586.50. 6594.00. 6601.50. 6609.00. 6616.50. 6624.00. 6631.50. 6639.00. 6646.50. 6654.00. 6661.50. 6669.00. 6676.50. 6684.00. 6691.50. 6699.00. 6706.50. 6714.00. 6721.50. 6729.00. 6736.50. 6744.00. 6751.50. 6759.00. 6766.50. 6774.00. 6781.50. 6789.00. 6796.50. 6804.00. 6811.50. 6819.00. 6826.50. 6834.00. 6841.50. 6849.00. 6856.50. 6864.00. 6871.50. 6879.00. 6886.50. 6894.00. 6901.50. 6909.00. 6916.50. 6924.00. 6931.50. 6939.00. 6946.50. 6954.00. 6961.50. 6969.00. 6976.50. 6984.00. 6991.50. 6999.00. 7006.50. 7014.00. 7021.50. 7029.00. 7036.50. 7044.00. 7051.50. 7059.00. 7066.50. 7074.00. 7081.50. 7089.00. 7096.50. 7104.00. 7111.50. 7119.00. 7126.50. 7134.00. 7141.50. 7149.00. 7156.50. 7164.00. 7171.50. 7179.00. 7186.50. 7194.00. 7201.50. 7209.00. 7216.50. 7224.00. 7231.50. 7239.00. 7246.50. 7254.00. 7261.50. 7269.00. 7276.50. 7284.00. 7291.50. 7299.00. 7306.50. 7314.00. 7321.50. 7329.00. 7336.50. 7344.00. 7351.50. 7359.00. 7366.50. 7374.00. 7381.50. 7389.00. 7396.50. 7404.00. 7411.50. 7419.00. 7426.50. 7434.00. 7441.50. 7449.00. 7456.50. 7464.00. 7471.50. 7479.00. 7486.50. 7494.00. 7501.50. 7509.00. 7516.50. 7524.00. 7531.50. 7539.00. 7546.50. 7554.00. 7561.50. 7569.00. 7576.50. 7584.00. 7591.50. 7599.00. 7606.50. 7614.00. 7621.50. 7629.00. 7636.50. 7644.00. 7651.50. 7659.00. 7666.50. 7674.00. 7681.50. 7689.00. 7696.50. 7704.00. 7711.50. 7719.00. 7726.50. 7734.00. 7741.50. 7749.00. 7756.50. 7764.00. 7771.50. 7779.00. 7786.50. 7794.00. 7801.50. 7809.00. 7816.50. 7824.00. 7831.50. 7839.00. 7846.50. 7854.00. 7861.50. 7869.00. 7876.50. 7884.00. 7891.50. 7899.00. 7906.50. 7914.00. 7921.50. 7929.00. 7936.50. 7944.00. 7951.50. 7959.00. 7966.50. 7974.00. 7981.50. 7989.00. 7996.50. 8004.00. 8011.50. 8019.00. 8026.50. 8034.00. 8041.50. 8049.00. 8056.50. 8064.00. 8071.50. 8079.00. 8086.50. 8094.00. 8101.50. 8109.00. 8116.50. 8124.00. 8131.50. 8139.00. 8146.50. 8154.00. 8161.50. 8169.00. 8176.50. 8184.00. 8191.50. 8199.00. 8206.50. 8214.00. 8221.50. 8229.00. 8236.50. 8244.00. 8251.50. 8259.00. 8266.50. 8274.00. 8281.50. 8289.00. 8296.50. 8304.00. 8311.50. 8319.00. 8326.50. 8334.00. 8341.50. 8349.00. 8356.50. 8364.00. 8371.50. 8379.00. 8386.50. 8394.00. 8401.50. 8409.00. 8416.50. 8424.00. 8431.50. 8439.00. 8446.50. 8



**BARR Says:** War time proves Barr leadership. Amazing selection of films still cameras Leica, Contax, Korvia Reflex, Argus new and used still available. Write for quotations. So selection guaranteed or your money refunded. Barr says can sell em, trades em. Barr Camera Company Dept. 8P, 179 W. Madison St., Chicago, Ill.

**Oil coloring photographs** a fascinating hobby or profitable business. Learn at home. Easy simplified method. Previous experience unnecessary. Send for free information and requirements. National Art School, 1315 Michigan, Dept. 174C, Chicago.

**CASH!** Spot cash for cameras, lenses, binoculars, movie or still, sound projectors. Send full description by mail, or wire for prompt cash offer. Over 34 years of dependable insured honorable dealings. Barr Camera Company 179 West Madison Street Chicago, Illinois.

**AT Last!** Air and Light defying patented developers. Will not stop when out in use. LT 30 soft working. LT 11 hard contrast. Quart 50c. Graphic Economy Developer Co., 1824 S. Trumbull, Chicago 21, Illinois.

#### CHEMICALS & APPARATUS

**WINN'S** new idea Home Laboratory Chemicals. Kits and apparatus outfits for home experimenting. Send \$c for literature and retail supply catalogue. J. E. Winn Co., Dept. 611 134 W. 21st St. N. Y.

**COLCHICINE** Kalaun chemical creates new medical plans. Illustrated booklet plus Experiment's Magazine 25c. Quantop Research Co., Mass.

**LABORATORY Spectroscopes** for chemical analysis \$2.50. McCutting Sons, Campbell, California.

**LABORATORY Catalog** 25 Pages. Glassware, Reagents, Apparatus. \$1.00. 15 Chemicals \$1.50. Rankin Oliver Bldg. Kansas City, Mo.

**286 PAGES** Apparatus Catalog sent for 50c. 132 Page Chemical Catalog 25c. Laboratory Materials. T. T. V. Co., Chicago.

#### DETECTIVES

**DETECTIVE** training Secret Investigations. Easy method. Fingerprints. Booklet Free. International Detective System, 1301 P. Monroe N.E. Washington D. C.

**DETECTIVES** Work home. Travel. Experience unnecessary. Write, Wagoner P. 125 West 26th St. N. Y.

**DETECTIVES** needed everywhere. New training method. Write Hanna 803 West Woodawn Tampa 1 Florida.

**DETECTIVE** training. Philip's Secret Service 1817-C North Kennebunk, Chicago, Illinois.

#### DOGS, BIRDS, PETS

**RABBITS**, Flemish Giants, New Zealand. Reasonably priced. Franklin Young Riverhead, Long Island, New York.

#### DRAFTING INSTRUMENTS

**MECHANICAL Drawing Set** 3 Piece complete in 1. \$1.50. 13 other essential drafting needs. \$4.50. Send for free complete catalog of drafting supplies. Gordon Co. 42-B Madison, Chicago.

#### EDUCATIONAL & INSTRUCTION

**PSYCHOLOGY** teaches about mind. How. Psychology teaches about power of mind over body. Why. How learn to use power of your subconscious mind. Study. Ground your ideas in. Invest in yourself. What other investment can yield better returns? Department 8 Taylor School of Business Psychology Chattanooga 1 Tennessee.

**PREPARE** yourself now for a well paying radio position after the war. Obtain your FCC commercial radiotelephone and telegraph licenses through our home study courses. Well on for the man who has forgotten higher mathematics. An easily read, easily understood course. Moderate tuition fee. Write for particulars. American Radio Institute, 44 East 23rd Street New York N. Y.

**WELDING**—Electric Arc. Learn quickly by actual practice at Hobart Welding School. Individual instruction at bare cost of materials used. 30c in stamps brings valuable welding lessons post paid and full particulars. Hobart Welding School, Box P-1132, Troy Ohio.

**BOOKS** Used educational books on all subjects bought and rented exchanged. Satisfaction guaranteed. Complete details and 64-page illustrated bargain catalog Free. Write Nelson Company 121 South Wabash Dept. 203 Chicago.

**CLINICAL Laboratory Technicians** in great demand. We train you in your spare time, in your own home. You can practice while studying. Write for free catalogue. Imperial Technical Institute, Box 973-B, Austin 5, Texas.

**LEARN** Drugless Therapy at home. Free literature. Diploma. Drugless Therapy Institute, Tama, Iowa.

**RADIO Engineering Broadcasting** Servicing. Electronics Aviation, Marine & Police Radio taught thoroughly. All expenses low. Co-educational. Catalog free. Dodge Institute, Dept. 100, Valparaiso, Ind.

**BE A Doctor** Learn chiropractic. Fast growing profession. Residence course only. Write for catalog. Texas Chiropractic College, San Pedro Park, San Antonio, Texas.

**BECOME a Doctor of Psychology (Ph.D.)** Teach secret of contentment, happiness. Solve mental worries. Free book. College of Universal Truth, 1441-A North Ashland, Chicago.

**MAKE** up to \$25-\$35 week as a Trained Practical Nurse. Learn quickly at home. Booklet free. Chicago School of Nursing, Dep. K 10 Chicago.

**TOOL** designing pays big. Home study course. Low cost. Easy terms. Free booklet. Ohio Institute of Technology, Box 119 Greenville, Ohio.

**LEARN** Correct English. Complete course quickly makes you master of words. Literature free. Popular Service, 652 Rutledge, Charleston, S. C.

**PROPHECY** Club reveals FOR a name approximated by six prophets who described new Christ. Christ is here. Data a dime. Nichols, Box 85, Waltham, Mass.

**EXCEPTIONAL Opportunity** Operate a Collection Agency-Credit Bureau. Quickly learned. Many make \$5,000 yearly. Write Cole Associates, Syracuse, N. Y.

**ACCOUNTING** Quality quantity inexpensive. request free booklet. Adams School 7.3 Ambassador Bldg. St. Louis.

#### ELECTRICAL SUPPLIES & EQUIP.

**ELECTRIC** Panel. Wires. Engraving all. \$1.00 postpaid. Boyer Mfg. 4515-C Cottage Grove, Chicago 13.

**FOR** Motors, Welders, Generators. Order 1 set of items. Write today Mfg. 823 LeJay Building, Minneapolis, Minn.

#### ENGINES, MOTORS, ETC.

**WINDING** Data, 225 Motors, single and three phase. \$1.00. Motor Data, Box 731, Kansas City 1, Mo.

#### FARMS, OTHER REAL ESTATE

**SEE** the Highlands of Louisiana where winter brings no idle acres. Choice cut-over land at low prices with terms. Send for descriptive book without obligation. Long Bell Farm Land Corporation, 807 N. A. Long Bldg., Kansas City, Mo.

**STROUT'S** Farm Catalog 64 Pages describing hundreds of properties in 13 states from Maine to Florida and west to the Mississippi—many pictures, rock-bottom prices. Write today for this money-saving time-saving book. Free. 6400 Realty 255-2B 4th Ave., New York 10 N. Y.

**GOOD** Farm Bargains, Washington, Minnesota, Montana, Idaho, Oregon, North Dakota. Dependable crops, favorable climate. Write for literature lists describing typical farms. Some to which state J. W. Hay 120 Northern Pacific Bldg., St. Paul, Minn.

**60 ACRES** near White River unimproved, poultry land. \$1.00 \$5 down, \$5 monthly. Free literature. Nabbe & 260 Grassman Bldg. Kansas City, Kans.

**ORLANDO, Florida** 6 acres on paved highway. Good fruit and vegetable land easy terms. Free booklet. Dept. Y, Interstate Development Co., Orlando, Florida.

**60 ACRES** good land \$200 \$5 down, \$5.00 monthly. R. W. Stewart, Investment, Florida.

#### FOR THE HOME

**AIR** Raid Protection.—Protect your home from incendiary bombs. Will be in reach of or 10 Pound package \$2.75 P. O. B. Stewart, 614 T. & A. Bldg. N. Y. C.

#### FOR INVENTORS

**INVENTORS** Learn now without obligation how to protect and sell your invention. Bureau Free Record of Invention form for establishing date of your invention and Free Book "Patent Guide for the Inventor", containing complete information about patent procedure and selling inventions. Delay may be costly. For prompt, confidential service—write to—Clarence A. O'Brien & Harvey Jacobson, Registered Patent Attorneys, 11A-L Adams Bldg. & Washington D. C.

**INVENTORS** Patent your invention. Send now for our new Free copyrighted booklet "Protect, Finance, and Sell Your Invention" and Invention Record form. This booklet guides the inventor from the first step toward patent protection to final profit making from his invention. Reasonable free consultation can be had. McManis & Berman, Registered Patent Attorneys, 441-X Abbe Building, Washington, D. C.

**PATENT** Your Ideal! Write immediately for two free illustrated booklets, "Patent Protection" and "When and How to Sell an Invention." 64 pages of valuable information for inventors. No obligation. Address: Victor J. Evans & Co., 743-M Meridian Bldg., Washington D. C.

**INVENTIONS** developed. Drawings made. Calculations computed. Models built. Good tools bought and sold. Clinton Davidson 434 C St., San Diego Calif.

**INVENTORS** New machinery and commercial inventions urgently needed by manufacturers. Write for particulars. Chartered Institute, Dept. 3-A, Washington, D. C.

**HAVE** you a Patent? Will manufacture on shares. Campbell, 378 Mt. Vernon, Detroit, Michigan.

**NEW** gland stimulating vitamin. Details accompany "Colchicine" offer. See "Chemistry".

**TOOL** manufacturer will purchase patent or patentable idea for Automotive tools. Tools 2124 Avenue U Brooklyn New York.

**CASH** for practical ideas and inventions. Mr. Hall, BB-3441 Pleasant, Chicago.

#### FORMULAS, PLANS, ETC.

**AUTHENTIC** Formulae 924 pages illustrated. 14,000 Money making formulae, recipes, instructions, substitutes. \$3.00 postpaid or C.O.D. (Foreign \$2.15) Catalog. Adams-Brown, Chestnut Hill, Mass.

**FORMULAS**—All kinds. Latest money-makers; literature Free. Kemikol, Park Ridge Ill.

**NEW** gland stimulating vitamin. Details accompany "Colchicine" offer. See "Chemistry".

**FORMULAS** Latest best. Analysis. Literature free. E. Belfort, Engineering Bldg. Chicago 4.

**101 REAL** Money Making Formulas 200 postpaid. Sign Farmington, Missouri.

#### HAIR PREPARATIONS

**USED** by thousands of men for years. Pro-Ker, a compound, cures hair scalp preparation for Hair Care. Loose Dandruff. Itch. Itch. Natural Hair Growth. Not greasy. Does not stain. Clean, fresh odor. No alcohol. For War Time Use. Developed by Charles Weaver, noted hair authority and author of "Our Vanishing Hair". Over 1,000,000 bottles sold. Money-back guarantee. Buy 10 cts. bottle \$1.50 postpaid or C.O.D. Hair Products, 443 Madison Ave., New York City 17.

#### HEARING AIDS & REPAIRS

**HEARING** Aids, Repairs, and Batteries. Quick Service. Wholesale, retail guaranteed. Marshall Brown, 10 East Congress & 1st St. St. Louis.

#### HIGHGRADE SALESMEN

**ADVERTISING** Book. Matchless America's largest manufacturer of Union Label Book Matches. Fast selling line. Large sales producing hit sample matches. Complete catalog 17 color combination makes selling easy. Commission in advance. Super Match Company 7536 Greenwood Ave. Dept. P-11, Chicago.

**EARN** your withholding tax and more, too, by giving us 10 minutes hours weekly. No capital or experience required. Box 3, Winona, Minn.

#### HOBBIES, COLLECTIONS

**BEAUTIFUL** Transparent colors are already out for you. Ten blanks and tubes makes you ten articles. In each kit are instructions which are very easy to follow for finishing. Price of each kit, postpaid \$2.00 or \$2.75 C.O.D. Hand left N.Y. Box 11, Somerville, N. J. We want no cash advance.

**FREE** Hobby Premiums—Send \$c for sample of our new Hobby magazine and offers. Paramount Distributors, Box 844-B, Denver 1, Colorado.

**BEAUTIFUL** Stones removed from rings, etc., 100 assorted \$2.00. Lowe's, Box M J.1 St. Louis Mo.

**NEW** gland stimulating vitamin. Details accompany "Colchicine" offer. See "Chemistry".

#### HUNTING

**FREE!** Full Guaranteed Bargain Catalog featuring thousands guns and "Hard to get" items, send 25c (refunded with first order) for handling costs. Swap guns and ammunition or Get Cash (Name your own price) We pay More and for less because we handle thousands upon thousands of new and used guns from \$5 to \$100.00. All models, gauge calibers, makes. We also buy sell or trade Ammunition. Recoilless Rifles. Outboards. Binoculars. Cameras. Watercraft. Write describing what you have to trade or sell, for cash. Money Back Guarantee backed by 50 years' fair dealing. Kline's Sporting Goods, Milton Kline, Pres., 5023 South Halsted, Chicago.



**NEW Product Ideas**—A reputable manufacturer will consider new patentable items (preferably of metal) for manufacture and distribution in the aircraft, automotive, marine, industrial, or household field. Ideas will be purchased outright or on royalty if accepted. Write briefly the nature and intent of your idea and if interesting, we will send complete instructions on how to submit full details for full consideration. Address P. O. Box No. 6798, Philadelphia, Pa.

**INVENTORS.** Have you a sound, practical invention for sale, patented or unpatented? If so write Chartered Institute of American Inventors, Dept. J-C, Washington, D. C.

INVENTIONS: Is your good patentable?  
 Write Mr. Meisler, 41 West 42nd,  
 N. Y.

**TWIN Cylinder Air Compressor** 512 x  
Motors—all sizes, Hoffmann 2740 Coy  
Cincinnati, Ohio

**HYPNOTIZE Anyone Quickly! Sure Fire**  
Method \$2.00. Mystic Sales, 7176 Pur-  
itan, Detroit, Michigan

REPRODUCE any snapshot on bank stamps, wood, leather, etc. Outfit \$1.00. M. stamps, Dissell Co., 4601 Rockwood Road Cleveland, Ohio

ENGINEER, Planes, Hundreds Of Hobb  
 1000 1/2 Ave of 25c G H Q, Dept. 87  
 40 E 10th St. N. Y. 10 N. Y.

SHIP Models and Catches, such as, complete  
in the 44 page Catalogue 20c Wm. Wild  
6 & F. 1, 19 New York City

**LEARN Metascience** - Remarkable drug... hearing No man... No appears... Unbeatable... and results... incentive correspondence course. Write Metascience, De Land, Florida.

**WANTED At Once! New Inventions. Cash or Royalty** Finley Brothers, 1204 Woodbine, Knoxville, Tennessee.

HANDWRITING character analysis, 26c  
3-10 pm 38-B Woodbury Street  
W. 42nd St. N. Y.

All The News of poultry Marketing & prices as breeding, feeding, raising & Raising the new One Year 25¢ 5 years \$ 0.00 Poultry Tribune Dept 182 Mount Morris Ill.

**DISTINCTIVE** Stationery at Reasonable  
Prices. Samples free. Stamp Printer  
South Whitley, Indiana








# Can a man have 'Comph'?

SURE

*Pipe Appeal!*



**PIPE APPEAL**—Prince Albert! Pleasing fragrance to keep her smiling. No bite—mildness to keep you smiling. Rich taste, yet so easy on your tongue. Crimp cut to pour, pack, and draw smoothly, and help a pipe to take up better. Better tobacco—world's largest-selling brand. Prince Albert for PIPE APPEAL!



ENJOY RICH TASTE  
THAT'S EASY ON YOUR  
TONGUE—

GET  
**P.A.**

BUY  
WAR  
BONDS  
AND  
STAMPS

**PRINCE  
ALBERT**

- 50** pipefuls of fragrant tobacco in every handy pocket package of Prince Albert
- 70** fine roll-your-own cigarettes in every handy pocket package of Prince Albert





# Planes Back Up Ground Forces in OUR NEW THEORY OF AIR POWER



**BATTLES ARE NOW FOUGHT  
IN THREE DIMENSIONS AS  
FLYERS LEND SUPPORT WITH  
BOMBS, GUNS, AND CAMERAS**

**By JOHN H. WALKER**

**A**LLIED victory in Africa and again in Sicily—first steppingstone to the invasion of Europe—was prepared and consummated under the protective web of air power, superbly co-ordinated with the attacks of the decisive ground forces and the maintenance of the essential sea lanes.

On one field of battle after another, the story was told: Allied heavy bombers plastering the enemy's rear-area air bases and supply ports; Allied medium bombers blasting his advanced fighter bases, tank columns, and infantry reserves on the roads; Allied dive and glide and fighter bombers slashing and strafing at his forward lines and strong points.

This expert collaboration between air and ground forces is the fruit of a new theory and technique in the use of air power. Developed by both the British and American air forces, this theory recognizes two basic kinds of support that air power can give to ground power. In Africa it found expression in the division of our air strength into *Strategic* and *Tactical* Air Forces. Its success marks it as the pattern for the future employment of the air arm and as one of the most impor-



## THIS IS A TYPICAL SETUP FOR AN AIR-SUPPORT CONTROL POST



**COMMUNICATIONS** lines are laid by a wire tasser mounted on a jeep. Carrying two reels with a mile of wire on each, it can string line at 30 miles an hour. Here the end of the wire is being anchored to a tree at the beginning of a run.



**RADIOTELEPHONE OPERATOR** sends messages by remote control through the transmitter, perhaps several miles away. Set is powered by batteries.



**TRANSMITTER** is camouflaged carefully to prevent destruction by the enemy. Carried by a 1 1/2-ton truck and trailer with gasoline-powered generator, it handles messages by remote control, monitors planes, airfields and headquarters. Its crew of two men serve as drivers, technicians, radio electricians. If it is knocked out, the operational truck can send directly.

tant recent developments in the art of war.

Strategic air power, in this technical sense, is represented mainly by large bombers, flying relatively long distances to strike the enemy in his home areas—war industries, communications, ammunition depots, barracks, port facilities. This can be a form of air support, as when Maj. Gen. Jimmy Doolittle's heavy bombers crippled the Axis African air force by bombing out the support fields in Sicily and Southern Italy. But it also may function independently, as in the strategic bombing of Germany by the RAF and the U. S. Eighth Air Force.

Air support in its purest, most direct form, is the job of tactical air power. No fixed limit is applied on space, although airmen have a rule of thumb that tactical operations will not usually penetrate farther

than 150 miles into the enemy's territory.

The British called this type of air power "close support," although no one has yet been able to give a satisfactory answer to the inevitable question, "How close is close?" Its main work is the bombing and strafing of the enemy at the precise time and place that will assist infantry or armored troops to overcome local resistance.

The old notion that air-ground support was entirely confined to light and dive bombardment has been completely overthrown. Any bomber, up to the giant B-17's and B-24's, may be used on a support mission. As a matter of military economy, however, light or medium bombers usually can perform an air-support assignment with greater speed and efficiency.

Air support can use a fighter plane to



Photographs by  
WILLIAM W. MORRIS

**CONTROL** unit is housed in the operational truck and a tent, both equipped for blackouts. It maintains constant communication with planes, headquarters, and airfields. Setup is typical for area where ground forces are making attack

**COMMAND** of the control unit, below, is a clearing house for information gathered by air and ground reconnaissance, requests from headquarters for attack missions, and reports of attacks made. Such a unit usually serves for a division

**TELETYPE** affords direct communication with headquarters and airfields, with a permanent record at both ends to reduce chances of errors and misunderstandings. Three men operate the machine carried in the control truck. Telephone and radio can be used to supplement the teletype

strafe the enemy, a glide or low-level bomber to drop delayed-action bombs on his columns, a dive bomber to plunk a load of high explosive on a strong point, a medium bomber to lay a stick or a salvo of ruin across a fortified position, or let down a string of delayed-action parachute bombs in a low-altitude sweep across a troop or truck concentration.

Liaison and reconnaissance planes complete the list of air equipment used, with all types represented from tiny "grasshopper" planes that can land and take off in open fields, to converted twin-engined Lightning fighters that can outpace or outclimb anything the enemy could put in the air.

Men and planes do the fighting, but the lifeblood of their work is communications, and here again every method is put to use,

from the simple act of wagging a plane's wings or dropping a message, to the most highly developed radio and wire equipment.

Basic communications from headquarters to air bases are carried out by teletype wherever possible. Teletype is unique in providing both ends with an instantaneous, permanent copy of the order or message, thus cutting the chance of error or misunderstanding down close to zero. The telephone and radio circuits supplement this, and radio naturally is invaluable for communication with planes in flight, when plans must be altered at the last moment.

Wire-tossing jeeps that lay phone and teletype wires at 30 miles an hour help keep the communications system functioning even during periods of rapid movement. Radio communication in the field is carried on



# AIR SUPPORT PERFORMS MANY IMPORTANT JOBS



**TRANSPORT.** Big C-47 transport planes like these carry paratroopers and tow gliders loaded with airborne troops far behind the enemy's lines. They also bring in important personnel and supplies, evacuate wounded

**LIAISON.** Tiny 'grasshopper' planes carry messages and transport officers behind the lines. Equipped with radio-telephone, they can perform reconnaissance in cases where high speed and armament are not needed for defense



mainly through a series of highly ingenious trailer trucks evolved by the Air Forces. The trailers carry their own generators, but tap into power lines where they are available. If the enemy air force is operating in strength, wire can be laid and the entire trailer operation carried on by remote control, with as much as seven miles between the broadcasting unit (which might be spotted by enemy radio direction finders) and the operational unit which is originating the messages. If the remote-control truck is knocked out by enemy bombing or artillery fire, the operational truck has duplicate sending and receiving equipment to continue work.




Into these communications centers pours the endless flood of battle information—requests from headquarters for attack missions, reports of attacks carried out, and disposition of enemy units observed by reconnaissance aircraft.

Liaison between air and ground forces is effected by the assignment of air officers to work in co-operation with the ground commanders. An Air Support Command normally is set up to function with an army or corps in the field. An Air Support Control works with a smaller unit, usually a division; a typical Control would include three officers and ten enlisted men with their communications *(Continued on page 202)*

**BATTLE SUPPORT.** Preparing for an attack by a combat team "X," bombers pound an enemy-held hill and communications lines

Infantry attack is launched. Team "X" meets unexpectedly stiff resistance by mortars, field guns. Artillery support is inadequate


Air reconnaissance reports heavy enemy armored striking force is coming up. Shall air support hit the tanks or help the infantry?







Fast fighters, such as this P-39 Bell Airacobra, serve as camera planes. Below, lenses of two K-17 cameras protrude from its belly, slanted for overlapping composite photos






**PHOTOGRAPHY** plays a big part in air reconnaissance. Pictures developed in the field are sent by wirephoto transmitter to headquarters, where maps are corrected accordingly. The two prints below show a crossroads as shot obliquely from a low-flying reconnaissance plane



A quick decision is made the tanks must come first. A reserve squadron of B-25s is ordered to smash the enemy armored column.

By radio, a squadron of bombers is diverted from a mission to bomb an enemy rail yard and "vectored" to help out the hard-pressed infantry.

After bombs have silenced the defending guns, combat team "X" is able to storm the hill and sweep on toward the river crossing beyond.








## ***KNOCKING OUT***

### **BABY FLAT-TOPS PACK PUNCH**


Planes based on tiny carriers spot and kill U-boats before they even see our convoys. One of these flat-tops, converted by U. S. shipyards from cargo vessels and called "Woolworth carriers" by the British, is pictured here by G. M. Davis, artist for the Illustrated London News

Sea-time aboard the converted carriers is welcomed by British as well as U. S. crews. The British like the cafeteria arrangement, calling it typically American. A crew's quarters are roomy, for a fighting vessel

This is one of the first views of the hangar of an escort carrier. The elevator mechanism is shown in the right foreground, while the elevator is raised. Wings are being extended on the plane at the left







Ad flying as well as navigation orders come from the bridge, situated outboard on the starboard side. The officer at the extreme right is in control of the take-offs and landings. Sometimes these are very tricky in a badly pitching sea.

Funnels, unnecessary in the operation of a motorship, are removed so the flight deck can stretch across the entire top to provide a maximum runway. The location of the plane elevator, shown flush with the deck, and other parts of these baby flat-tops, is given in the drawing below.





**BUNA BOOTS**, made to the specifications of regulation rubber boots, are among the latest products of the Government's synthetic-rubber program. Turned out in quantity on the production lines of the Connecticut plant of the United States Rubber Company for essential workers, they are made entirely of buna S and rubber cement.



**SEEING FOR THE BLIND**, an "electric eye" guards sightless sewing-machine operators by applying a brake when fingers near the needle. Developed by J. O. Kleber and M. G. Gregory, of the American Foundation for the Blind, it also signals a broken thread.


**MECHANIZED LAUNCHING** has replaced brawn at the Kaiser shipyards and cut man-hours on the job by two thirds. An air ram on rails now hammers in wedges at the rate



**CAN OPENERS** with a blade that folds flat are being furnished U. S. soldiers for use on tinned rations. The opener weighs a fifth of an ounce and fits on a key ring.



of 11 a minute to lift the cradle and shift the weight of a completed ship from keel-blocks to sliding ways. Eight rams, each handled by three men, are required to drive the 1,000 wedges used in launching a Liberty ship. The ram is the invention of Fred Schlotfeldt and Kenneth Hunter, Vancouver yard superintendents.





*With a watch  
and two charts  
you can find  
your position  
anywhere in  
the world.*



Aided by the brightly shining stars, these three men on a raft could be in the middle of the Pacific and still have a good chance of reaching the safety of shore. Currents, winds, clouds, reflections, birds and sea life will help if they know how to read their meaning.

*How to*



## *Navigate a Raft*

**ANCIENT ART OF THE POLYNESIANS IS REDISCOVERED  
TO AID SEAMEN AND FLYERS ADRIFT FAR FROM LAND**

**By SEYMOUR FREIDIN**

**S**UPPOSE you got tossed out on the ocean from a torpedoed ship or a plane that couldn't make it home after a bombing raid. Do you think you could find your way to land? You stand a good chance of doing just that if you have with you on your raft a watch in a waterproof case (or, better still, in a transparent, waterproof rubber sack that can be kept closed) and two charts, one of the heavens and one a navigational base chart of the world, and both drawn to the same scale.

Even without these basic implements,

Polynesian travelers of some 600 years ago made long voyages over the trackless Pacific—the last of them a great colonization trip from Tahiti to New Zealand, a distance of 2,500 miles. Their navigators used simply their eyes, their sense of hearing and of smell, and a primitive knowledge of the heavens and the sea.

But their method of navigation has been buried these past six centuries in a maze of Polynesian song and legend—known only to their priests and wise men and transmitted by word of mouth from generation to generation since economic necessity and tribal differences no longer prompted these great sea



migrations. Their secret has only recently come to light, and it is so remarkably simple that a system based on it opens the prospects of successful navigation to the most absolute landlubber.


Capt. Harold Gatty, who was Wiley Post's navigator on his first round-the-world flight and has passed most of his life in the South Pacific, has written "The Raft Book" (the George Grady Press, New York) based on extensive research in Polynesian legend. "The Raft Book" is intended as a guide for those lost anywhere on the world's oceans. Through the courtesy of Captain Gatty,

POPULAR SCIENCE is able to present here some of its more important features.

What value there is in following the stars, what various types of sea birds and fish indicate, how currents and winds may be used to advantage, what aid can be had from clouds and reflections in the sky—a knowledge of these things helped the Polynesians reach their destinations, and they will help the average man today as well, even if he is without training in navigation.

With neither charts nor watch, the Polynesians relied on a traditional lore of the stars, viewing them as moving bands of

## WATCH AND STAR CHART GIVE THE EXACT POSITION OF THE RAFT




Out on a raft in the Pacific at 8 a.m. Greenwich time October 1, the amateur navigator takes his bearings. He matches the zero hour on his star chart with the date on the navigation base chart and marks off eight hours (at the arrow)



Moving the zero to the new point and identifying the star above him as Markab, he spots his position on the base chart and finds he is east of Hawaii. The star chart is looked at as from above







Stars were looked upon by the Polynesian navigators of six centuries ago as moving bands of light that passed over the same islands night after night. Those passing over particular islands were memorized and used as beacons to lead the Polynesians to their destination. At right and in the diagram above, Sirius is an overhead star for Vanua Levu in the Fiji Islands at three minutes past midnight on January 1, 1944. All the stars are shown in their actual position for this moment. On each succeeding night they will appear in the same positions about four minutes earlier



LD 441 041011 1441  
THE EAST BIRCH







## WINDS AND CURRENTS DICTATE DIRECTION OF TRAVEL

— = WIND

— = WARM CURRENTS

- - - COLD CURRENTS

Next, the raft navigator turns to a chart of winds and currents in the area of the Hawaiian Islands and finds that if he uses a sail he may be blown far to the south, but that the current will carry him in. He can cast a sea anchor and drift with assurance

light. They knew all the stars of each band that passed over the islands in which they were interested, and knew what star would be over a given point at a given time. Then they simply set their course by this star. This required years of memorizing, however, and restricted the Polynesians to the stars passing over the islands with which their navigators were familiar.

Since stars and their positions in different seasons of the year cannot be memorized overnight, Captain Gatty simplifies this system of navigation by providing a chart of the stars with markings on the border in Greenwich time. If you are able to recognize a star overhead and identify it on the chart, it makes little difference whether you know its name.

One essential feature of Captain Gatty's star chart is that it is printed on transparent paper. Thus, with the stars visible from either side, the chart may be used both to check on the night sky and to find the position of given stars on the navigational base chart of the world. In checking on the stars overhead, the chart is looked at from one side; in locating them on the navigational chart, it is looked at from the other, as if you were yourself above the stars looking down on the ocean.

To complete the system of navigating by the stars, you must keep your watch running on Greenwich time or be able to make calculations from it in Greenwich time. This is necessary, since the transparent sheet is moved over the navigational chart in accordance with the time of day in Greenwich time and with the date.

Just as the Polynesians "chased the stars" to their destination, you can pick out a star on your course and follow it with equal assurance of success. The movement of your "guiding star" must be watched hourly, and your course set an increasing or decreasing amount to one side according to whether the star is moving away from your destination or toward it.

In weather when the stars are not discernible, there is a duration-of-the-day method of setting your course that will serve as well. This consists simply of measuring the length of time between sunrise and sunset, and using this knowledge along with the date to find latitude and longitude in hemisphere tables included on the navigational chart. Probably the only way to determine the duration of the day on a raft is the slow but sure one of taking readings from your watch at both sunrise and sunset.

Eyes and senses must also be brought to



bear to pick up and recognize signs that will help you guide your raft toward land. Use the winds and currents in propelling your craft, sailing if the wind is right, or using a sea anchor that will keep you drifting with the current. Before deciding which to try, however, decide whether the resultant winds—the sum total of the prevailing and the other winds—or the current will better serve you. You should know, too, that the winds may blow in one direction and the current may flow in one directly opposite. Captain Gatty has prepared winter and summer charts of the winds and both warm and cold currents covering all waters.

Birds can also be a big help in finding direction. The Polynesians saw land birds take off year after year in the same direction and knew that they could not rest on the ocean. In the great voyage to New Zealand, they followed the route of the long-tailed cuckoos after repeatedly observing the migration of these birds from Tahiti.

The Polynesians frequently carried frigate

birds as an aid in sighting shore. Released, these birds would fly upward, spot land if any were to be seen, and go directly to it, or else, if land were not in sight, they would return to the boat, from which they could be set loose again later on. Pigeons could be used easily as substitutes.

Captain Gatty has prepared pictures of the main sea birds along with a list of their characteristic markings to help in identifying them. Noting their flight is one of the most important ways of telling when you are near land and in what direction it lies. The type found over any area of the ocean depends on the temperature, depth, and salinity, and the movement and kind of marine life present. Identifying the birds will often give additional information.

Most tropical sea birds do not range far from their breeding grounds on islands and coasts, and as a consequence they are not often seen far from land. All of them are edible, and they are easy to catch. You can bag an albatross or other hook-billed bird


## SMALL CLOUDS AND SWELLS DISCLOSE THE NEARNESS OF LAND

Note: In Captain Gatty's "The Raft Book," these illustrations appear in full color




Because white sand reflects more heat than the sea, small clouds hover over all atolls

Parallel swells, curving to the shape of the land, are driven toward an island by the prevailing wind







## BIRDS TELL PROXIMITY AND DIRECTION OF LAND

Close watching of sea birds is a good guide to shore. These creatures cannot land on the ocean, and toward dusk they always fly back to the nesting grounds. Above are excerpts from Captain Gatty's book, giving pictures of sea birds and outlining their most helpful characteristics.

with a shiny metal object tied to a string.

Keep a sharp lookout for fish and other surface life, bearing in mind that rich marine life occurs in quantity only relatively close to shore. Far out, there generally are whales, porpoises, large sunfish, and ocean bonitos.

Polynesian navigators watched the sky, knowing that small clouds hovered over atolls. This is because the white sands reflect more heat than the surface of the water and cause a difference of temperature above. The cloud over your atoll will be a

little to the lee side, blown that way by the prevailing wind. You will be able to see on its underside a reflection of the bright turquoise lagoon long before the atoll appears over the horizon.

Deep water is a poor reflector, but lagoons and other shallow waters play their colors on a cloudless sky. In polar regions, this results in "water skies" and "ice blinks." The former, a sharply defined shadow in a bright sky, indicates open water in the midst of ice, and the latter, a patch of brightness in the gray, means floes or shore ice in open water.

Waves and swells tell their tale as well. The prevailing wind carries parallel swells toward an island, and they curve to the shape of the land as they near it. Those directly in front form waves that break on the reefs.


Sounds also can give you a good idea of how near shore may be. Gulls, with the exception of the kittiwake, are not found far out, and their cries in flight generally indicate near-by land. In fact, continued cries of sea birds from one direction usually signify a roosting place on the shore. There are such sounds, too, as breaking waves, fog whistles, and buoys. And, of course, if you hear a factory or train whistle, it's all over but the celebration.

But don't try to go head on into the shore when you actually sight it. It's usually dangerous to attempt a landing from the windward side of an island, and even on the lee side, heavy surf may make it hazardous. Don't risk everything by trying to fight your way in. If you have any doubts, remain outside the breakers and signal for help with any means at your disposal—a pistol shot, a flare, a distress flag, or a plain, lusty shout.

Navigating the high seas in a small boat is perfectly possible if you know how. The Polynesians did it—and so can you.




## CONEY ISLAND AQUARIUM TO BE WORLD'S LARGEST



**T**HE largest aquarium in the world, to be built by New York City at an estimated cost of \$1,500,000, has been tentatively planned for postwar construction at Coney Island. In addition to virtually every known type of fresh and salt-water fish, the aquarium will exhibit biological specimens and aquatic birds gathered from all parts of the world.


Covering a 10-acre area, the proposed aquarium will include a main building housing practically every fresh and salt-water fish known to man, outdoor pools for seals and penguins, and a special aquarium for children. There will also be restaurants, a lecture hall, and a promenade deck. The above is our artist's conception of how the 'oceanorium' will look.



Drawings by B. G. Seielstad

Among the interesting novelties proposed for the aquarium are glass-enclosed passageways through the giant tanks which will enable visitors to get unusual views of the fish. There will also be a catwalk at the top of each tank, and viewing windows in its sides.

Plans call for a special section in which waterfowl and aquatic birds will be housed.





# PARAFFIN PRODUCT FIREPROOFS, WATERPROOFS FABRICS



**B**Y BUBBLING chlorine gas through melted paraffin wax so that the chlorine replaces the hydrogen in molecules of the paraffin, industrial chemists are now economically producing a noninflammable wax which, when applied to textiles, renders them waterproof, fire-resistant, and mildewproof. The hydrogen that is eliminated from the wax is then made to combine with excess chlorine and thus produce hydrochloric acid as a by-product. The odorless, durable wax can also be used in making plastics.

Shown above is the chemical sequence in which chlorine gas, bubbled through paraffin wax, produces chlorinated paraffin. The hydrogen that is eliminated from the paraffin is then combined with excess chlorine to produce hydrochloric acid.



In a test of the wax's waterproofing qualities, as shown at far left, a treated piece of fabric resists water poured over its surface, while an untreated piece of the same fabric allows the water to pass through it into the receptacle.

At the immediate left, ordinary paraffin is shown burning steadily after having been ignited, while the chlorine-treated paraffin remains unaffected when it is placed over a match.



The third protection that the new wax affords textiles is to render them mildewproof. These pictures show the difference in the reaction of two pieces of the same material—one treated, the other untreated—after prolonged exposure to dampness.



# WHEN RUSSIA FIGHTS JAPAN



**A distinguished war correspondent forecasts a colossal conflict in the Far East—with the Japs the losers.**

**By WALTER KERR\***

**D**ISTANT Siberia may become one of the great battlefields of this war.

For years now, a defiant Russian army has glared southward across the Amur River into Manchukuo, where the treacherous Japanese maintain their powerful Kwantung Army.

Two strong forces poised to strike. Two traditional enemies. Mutual distrust. Mutual hatred. A conflict of interests that goes back more than 50 years.

When that war comes—and the people of Moscow told me it was inevitable—the world will find out that the Russians never took their eyes off the Japanese, even during the most critical days of the battles for Moscow and Stalingrad. They never weakened their Far Eastern force. On the contrary, they

Tough, well-trained troops like these will meet the Japs in the Battle of Siberia. Antitank gunners, clad in white for camouflage against snow, drag their ski-shod piece into position for point-blank fire. The Red Army's antitank tactics stopped the Nazi panzers—and will stop the Japs

strengthened it, and they will continue to strengthen it as they continue to wage successful warfare against the Germans in the West.

The Battle of Siberia will be no side show, but a war with a million men and more on a side.

In the last two years, the situation in the Far East has changed considerably. In the beginning the Russians had their hands full with the Germans, and the only question was: Will the Japanese attack? Now the Russians are fighting a winning war with Germany, and the question is: Who will attack first, the Russians or the Japanese?

When I first got to Russia, Germany's mechanized army was driving on Moscow, and the people asked me: "Do you think the Japanese will stab us in the back?" But this year, following the successful Russian counteroffensive against the Germans west of Stalingrad, an official of the Russian Foreign Office told me: "You have been here long enough to know that when Hitler is beaten we will take on the Japanese."

The only question then is which country

---

\* Reported crucial events of the war from Vienna, Prague, Berlin, Paris, London, and Moscow. Long service in Russia makes him an authority on conditions in that country.





Interstate enemies across the land in Manchukuo. Traversing the iron and coal fields of the Kuznetsk Basin and the rye and wheat fields of the Irkutsk area, the double-track line would be a prime objective of a Japanese attack. Hedging against the loss of this vital rail link, the U.S.S.R. has built a second railway paralleling the Trans-Sib far to the north. This new line could be more easily defended and kept in service



will attack first. The answer provides the clue to the nature of the campaign that will be fought.

If Japan attacks, in a suicidal move of despair, we can expect the Russians to withdraw into the Siberian wasteland until they are strong enough to counterattack. But if Japan waits until Russia attacks, we shall see Russian troops driving deep into the heart of Manchukuo. For Russia will attack only when Russia is ready.

Russia this summer was already on a war footing in the Far East. Its divisions were not organized into military "regions," the customary peacetime designations that correspond to our "corps areas." "Regions" had been replaced by "fronts." We began to hear of the "Far Eastern Front" and the "Trans-Baikal Front." In Russia the "front" is a wartime organization headed by a front commander who directs the operations of several armies. In each of his armies he has a separate air force, one or more tank corps, and anywhere from five to 15 divisions.

Out in Siberia the "Far Eastern Front" embraced the eastern part of the Russian line, including the great port of Vladivostok. But Vladivostok is difficult to defend, so front headquarters was established farther

to the north in the city of Khabarovsk. Here the commander was Army General Josef Apanasenko, a little Cossack called "Hercules" by his friends.

The "Trans-Baikal Front" was farther to the west—based, as its name implies, just east of Lake Baikal in the city of Chita. Its commander was Colonel General Georgi Kovalev, a big fellow with many years of service in Siberia.

If Japan attacked before Russia was ready in the Far East, Apanasenko would have to fight to defend the Trans-Siberian Railway, Vladivostok, and the new industrial areas that Russia built some years ago to supply its Far Eastern force. Kovalev would have to help Apanasenko by hammering at the Japanese flank, but his great mission would be to take a position astride the railway and prevent the Japanese from pushing along it to the west, toward the rye and wheat fields around Irkutsk and the coal and iron area of the Kuznetsk Basin beyond Krasnoyarsk.

The Japanese might be able to seize Vladivostok in a quick lunge from Manchukuo, and they probably could cut the Trans-Siberian Railway in a number of places. But the gains would be costly and would


"KATUSHA" is one of the surprises in store for the Japanese. An invention of Andre Kostikov, it is kept under wraps except at the front. Best guess is that it is an antipersonnel rocket gun that kills with a spreading flame. At right is a variation of it



CAVALRY will have its innings on the Siberian plains. The Red Army uses mounted troops effectively in masses of two or more divisions. Horsemen of friendly Outer Mongolia will help give superiority







lead to nothing. For the Russians have already moved their Pacific fleet from the waters around Vladivostok, and they have built a new railroad paralleling the Trans-Sib many miles to the north. This line, which can be presumed to be in operation, runs from Ust Kut, just northwest of Lake Baikal, across the tundra regions to Komsomolsk, north to Khabarovsk.

Let's go back and see why the Russians have made these preparations for war, why every soldier and civilian I met in 16 months in Russia hated the Japanese the way Americans have hated them since Pearl Harbor, why they feel that war between the two countries is inevitable and that the only question is which country will attack first.

We can begin with February 9, 1904, when the Japs, striking as suddenly and as treacherously as they did at Pearl Harbor, attacked the Russian naval base at Port Arthur, precipitating the Russo-Japanese War which ended in disaster for Russia. The people of Moscow have never forgotten that cold February day, nor have they forgiven. By the terms of the Treaty of Portsmouth the Japanese not only took Port Arthur but obtained a free hand in Korea and took possession of the southern half of the Russian

island of Sakhalin, lying north of Japan.


Then, after the Russian revolution of 1917, the Japanese joined the Americans and the British in a temporary occupation of parts of eastern Siberia. We pulled out in 1920, but the Japanese stayed on until 1922, and then they refused to surrender the northern half of Sakhalin. Finally in 1925 the Russians forced them to withdraw. Diplomatic relations were opened between the two countries.

Nothing much happened then until 1931, when the struggle for supremacy in the Far East came out into the open. The Japanese occupied Manchuria, which they renamed Manchukuo. Russia fought back by aiding the Chinese. Japan forced Russia to sell its interest in the Chinese Eastern Railway that crosses Manchukuo, the short cut to Vladivostok.

Then the aggressive Japanese cast covetous eyes on Outer Mongolia, but the Russians said "No." That country, they declared, was Russia's sphere of influence. Stalin said he would go to war to prevent Japanese penetration. Border incidents developed. The Japs began testing Russian strength. In 1938 they tried to take a piece of territory near Lake Khassan on the border south

Russia's first line of defense against the Japs in Manchukuo is a gunboat flotilla on the Amur River. Bottom: Soviet infantrymen armed with Degtyarev 7.62-mm. submachine guns ride a 26-ton medium tank.

The Red air force has proved its mettle against the Luftwaffe. These are YAK-1 light fighter planes, good on rough advanced airfields. Mongolian types, below, are common among Soviet Far Eastern troops.





of Vladivostok. The Red Army kicked them back in a battle that involved the use of tanks and planes as well as infantry and artillery. The Japs tried again the following year to move into Outer Mongolia. In one great battle that lasted only a week, the Red Army surrounded and annihilated the Japanese Sixth Army. Marshal Georgi Zhukov, who won the battles for Moscow and Stalingrad, commanded the victorious Russian force. After that the Japanese pulled in their horns. But by that time every Russian knew that only war could settle the conflict of interests between the two countries.

Now for the weapons the Russians would use in a war with Japan—weapons tried and found excellent in the war against Germany. The Japs would find the Russians among the best artillerymen in the world. Russian divisions are liberally equipped with 45-millimeter (1.8-inch), 76.2-millimeter (three-inch) and 122-millimeter guns. They use them boldly, up forward with the infantry. A great number of artillery regiments are reserved for use by the high command, enabling it to organize mass fire on the sectors it selects for attack.

Russian tanks manned by experienced crews will include the heavy 42-ton KV model and the medium 26-ton T-34, both armed with three-inch guns.

Siberia is good country for cavalry warfare, and the Russians, aided by the Outer Mongolians, with whom they have a pact of mutual assistance—should have clear superiority in this branch. The Moscow conception of the best way to use cavalry is to employ it in mass, in units of two, three, or more divisions.

No American knows much about the Russian air force, but it has been able to keep pace with the German Luftwaffe, so its fighter planes, such as the MIG-3, the YAK, and the LAGG, should be able to handle anything the Japanese can send up.

As for the Red Army infantry, it probably has few equals in the world. Its men are tough, trained to endure hardships, accustomed to the climate, disciplined, and good marksmen. The experience of the war against Germany shows they are not afraid to die. Rifle divisions are thoroughly trained for antitank warfare, and the Japanese are sure to find their armored columns cannot succeed where Germany's armored divisions could not. Every unit has its antitank detachment, and the troops are trained to use antitank rifles, fuel bottles ("Molotov cocktails"), and heavy antitank grenades.

Furthermore, the Red Army has a few cards up its sleeve which the Japanese know nothing about. One is a weapon that the soldiers call "Katusha," probably some sort

of a rocket gun that kills with a spreading flame. Russians say it won the battle for Moscow.

Back of the fighting forces is a new industry in the Far East, which has been developed since the revolution of 1917. North of Khabarovsk and Komsomolsk are coal, iron, and oil fields. Most of the oil comes from Sakhalin and is refined in Khabarovsk and farther to the north at Nikolaevsk. There are great cement plants at Vladivostok and Komsomolsk, and three steel plants producing everything from pig iron to rolled-steel products at Petrovsk-Zabaikalsk near Chita, at Komsomolsk (a new shipbuilding and metallurgical center), and at Irkutsk.

The armies of the "Far Eastern Front" and the "Trans-Baikal Front," equipped with excellent weapons and backed by a recently developed industry and an improved transportation system, will employ tactics developed during the war with Germany. There is nothing much about them that was not known to military science before the war, but through trial and error, defeat and victory, the Russians have found out the best ways to use their available manpower and equipment. They have learned to fight on a wide front, employing mobile striking forces to smash enemy attacks and to obtain superiority in the sectors selected for offensive action. In the early days of their war with Germany, they were a little inclined to slug it out with the enemy, regardless of the enemy's strength. Now they have learned to fall back rapidly and then to strike in counteroffensive at the proper moment. They have also learned a great deal about communications and supply.

The Japanese have had a healthy respect for Russian arms ever since they clashed with the Red Army at Lake Khasan in 1938 and at Khalkin-Gol in Outer Mongolia in 1939. That, undoubtedly, is why they never dared to cross the Siberian border in the first two years of the German war, although the Nazis in Berlin must have called upon Tokyo for help.


As time goes on, as the Germans continue to take a beating in the West, Russia will get tougher in the East—not, I am sure, to help America, Great Britain, and China in their war with Japan, but to settle old scores that go back to that February day in 1904, when the Japanese jumped the Russian fleet.

Whichever country is first to attack, the ultimate outcome is clear. Japan will go down in defeat. Its cities will be bombed from Russian soil, undoubtedly with American planes. Its Kwantung Army will be driven from Manchukuo and almost certainly from Korea. Siberia will be a battlefield, and perhaps the graveyard of Japanese treachery and aggression.



## Prehistoric Reptile Takes a Bow After 100,000,000 Years

UNEARTHED in a gypsum quarry near Fresno, Calif., this plesiosaur finds the scene changed considerably since he (or she) paddled the prehistoric seas 100,000,000 years ago. The skeleton, largest and most perfect of its kind ever mounted, has been assembled by paleontologists at the California Institute of Technology in Pasadena. Plesiosaurs were marine reptiles that flourished in the later Jurassic and early Cretaceous periods. As this specimen shows, they attained lengths of more than 30 feet.




This is the largest and most perfect plesiosaur skeleton ever mounted. Assembled by paleontologists at California Tech, it shows the small head, long neck, and paddle legs of this genus of marine reptiles, which lived before mammals dominated the earth.





**TESTING TORPEDOES** of the type carried by aircraft is simplified by a launching device used at the Naval Torpedo Station at Keyport, Wash. Constructed from salvaged metal by mechanics at the Keyport station, the device simulates the action of a low-


flying torpedo plane in dropping its "tin fish" in the water near an enemy warship. From a boxlike platform suspended above the water, an observer watches the performance of the torpedo as it plows its way toward its target.



**CONCRETE "SUBMARINES"** eel-like craft that will operate almost completely submerged as carriers of troops and cargo through waters infested by real underwater raiders, are envisioned by Hal B. Hayes and Hal Williams, both of Hollywood, Calif. At the left, Hayes is seen inside a 124-foot model, which is shown below under test on San Francisco Bay. If trials are successful, plans call for construction of full-size, 10,000-ton vessels of this novel type. The photograph shows the two V-8 motors that drive the model.







**"LONG TOM" AT THE FRONT.** U. S. troops in action have had welcome support from the huge shells hurled by our 155-mm. long rifle. Here one of the American-de-


signed big guns is creeping across a bad spot in a bomb-battered Sicilian mountain road, under the watchful eyes of engineer troops who have just cleared a path for it.



**WOODEN BELLY TANKS** are used by the Japanese to give extra fuel-carrying capacity to their planes. The two flimsy specimens shown at the left were found near the Munda airfield when that important New Georgia base was captured by the American forces. Apparently, the containers are made of molded plywood with some sort of gasolineproof lining—a poor job when compared with American aircraft fuel tanks designed for similar uses.

**JEEP ON RAILS.** Still another job for the Army's versatile quarter-ton is indicated by the picture below, which shows officers trying it out in the new role of switch en-

gine somewhere in Australia. Fitted with flanged steel wheels, the jeep proves that it can move a long string of loaded freight cars. A dump trailer doubles as tender.





# Helicat Has the Zero's Number



**S**OMETHING that would "go upstairs faster"—that's what our Navy fighter pilots asked for. And they have it now, in a new Grumman plane that makes the lethal Wildcat look like a fireside tabby. First war-plane to be based on combat experience in the Pacific, the F6F Helicat was in quantity production before the first model flew.

While the Navy intends to let the Japs learn about the Helicat the hard way, it is

no secret that the new fighter has a wide margin over the Wildcat in speed, climb, guns, and armor. And, since the older plane chalked up a score of five to one against the fast but flimsy Zero, that's something.

The first full squadron of Helicats was delivered to the Navy last December, and there were F6F's in the Marcus Island raid. They are going to the U. S. Marine Corps and the British Royal Navy, too.



**LIFE LIGHTS**, with which men who have to jump from a sinking ship at night can signal to rescue parties, are being manufactured by the Celanese Celluloid Corp., of New York. Made of Lumarith plastic, the lamp is equipped with a 30-inch lanyard at one end of which is a safety pin that is fastened to the life belt. At the other end is a clamp, by which the lamp can be attached to a seaman's clothing. The light is turned on by screwing tight the lamp's domed cap.

**NONSKID SEA BOOTS** with thick, cleated heels and traction soles are being made by the U. S. Rubber Company for the protection of submarine-crew members while they work on the slippery decks of their ships. The new waterproof boots are roomy enough for insoles and three pairs of wool socks.





***They Cleared the Tracks for Victory!***

# **The Iron Horse Saves the Day**

America started the war under the threat of a transportation crisis . . . but then the railroads came through with a miracle.

By HICKMAN POWELL

TALK all you want about airplanes and electronics and motor transport—the part of this war effort which really rates a shout of amazement is the role played by the American railroads. The iron horse, which plowed the plains and spanned the mountains, was not what he used to be. For the last 20 years he had been getting creaky at the joints. To this Buck Rogers generation, millions of whom had never even ridden on a train, it seemed that he was inevitably doomed

to go out to pasture. But here is the old horse now, snorting in the traces, hauling bigger loads and faster than anyone dreamed possible—least of all the railroad men who are making him do it.

With fewer miles of road than they had in 1918, with fewer employees, with 20,000 fewer locomotives and 600,000 fewer freight cars, the railroads of America in 1942 moved two thirds more ton-miles of freight than in 1918, and in 1943 are moving twice as much. In the first three months of this year, their passenger traffic, which had slumped off to a trickle in the 1930's, was virtually double what it was in the corresponding period of 1918. And this, mind you, is the accomplishment of a transportation system which in 1918 was almost at its peak and for two decades after that had been taking it on the chin from the

Careful maintenance has kept old rolling stock up to par on the heavy-duty job of moving war materials





1918



1942



1943



Drawings by Stanley Price

With less freckage, fewer employees, and less rolling stock, American railroads in 1942 hauled about two thirds more ton miles of freight than they did in 1918, and today are hauling almost twice as much.

truck and bus competition of the motor age.

We Americans of the motor age, indeed, have only God and the railroads to thank for the fact that we avoided national disaster in 1942. Pearl Harbor was bad enough, but when the U-boat packs fell upon our defenseless oil tankers on the eastern seaboard, they were striking much closer to the actual vitals of the country. The whole industrial Northeast was dependent on gasoline, and the devastating success of the submarine was cutting off that supply.

It was the railroads that came to the rescue and averted the collapse of motor transport. A fleet of 70,000 old tank cars

used by the oil companies for odd jobs of storage and short hauling—were put to work, hitched into solid trains, and shuttled back and forth across the country on fast daily schedules as precise as passenger service. Railroad men had been laughed at when they first thought they might be able to move 200,000 barrels a day in this fashion, but soon it was proved how wrong they were. For by this last summer the old tank cars—stopping occasionally to get new wheels—were moving five times that much!

The East still starved for gas. But that was because the railroads had been so successful that the Army and Navy dared to

Freighted management has also seen to it that cars don't sit around for days waiting to be unloaded, that they are kept in first-rate repair by the company on whose rails they happen to be rolling at the

UNITS ENTRAINING  
FOR TENNESSEE


CAL.

UNITS ARRIVING  
FROM ARIZONA


ARIZ.

UNITS ENTRAINING  
FOR CALIFORNIA

UNITS ARRIVING  
FROM LOUISIANA







One of the means by which the railroads have accomplished their miracle of transportation is by seeing to it that cars are loaded to capacity whenever possible. Above shows how this increases payload ratio.

draw on eastern gas for their fighting supply.

While this battle of oil was being won, the loss of Malay rubber to Japan threw another great burden on the rails. We have managed to get by on our tire supply, because railways have absorbed the great expansion of traffic that would have been on rubber.


Transportation is a fundamental necessity in any war. Sea transport, because it is under attack, and air transport, because it is new, have had the spotlight; but the railroads have handled a far heavier load, because they move each item many times.

From mine to smelter, to mill, to part factory, to assembly plant, our goods move

from raw material to completion as engines of war, making each move by rail in a steady stream on which the flow of production is utterly dependent. Once assembled, the war machine goes to troops by rail, then moves with troops from training camp to maneuver area, back to training camp, and again to port of embarkation. Then, on its arrival abroad, the railroads resume the burden.

All the vast new factories, munitions depots, and training camps, springing up in sections where industry and population had been small, have been built and supplied with men and materials brought by rail. Freight traffic, which formerly moved pre-

moment, and that they never roll home empty. Typical of today's efficiency is the device, illustrated below, whereby cars moving troops are scheduled to receive a load as soon as they have discharged one.





dominantly eastward through yards and terminals built to take it, now runs west in almost equal flow—to the great Pacific ports of embarkation, to the plane factories of California, to the shipyards of the Northwest. Why, for just one of Kaiser's Liberty ships, it takes a trainload of steel, which must arrive on time. And then the train returns, carrying copper or timber which ordinarily would have moved via the Panama Canal, now closed to merchant trade.

All this has gone on while trains rushed off to the East; while millions of travelers, deprived of rubber, have rushed to the railroads; and while troop movements have reached a fantastic level. Where soldiers of 1918 moved perhaps three times by rail while training, today's troops move six to eight times, on trips averaging 800 miles, often spanning the continent. Transportation has been used prodigally, because the railroads could provide it. And the remarkable thing is that they provide it with almost no new equipment. Sidings have been lengthened to hold longer trains, intricate electric traffic controls have been installed to accommodate far more trains on a single track, yards have been built. But in general the rolling stock is little more than it was in quiet 1939. The new streamlined trains have kept running at full speed. The new 4,500-horsepower Diesels have hauled away unceasingly, dragging great loads across the western mountains. But a great part of the increase has been through the intensive use of equipment which had seemed almost ready for discard.

Intensive management has done the trick. For instance, it takes about 1,300 cars—passenger and freight—to move an armored division. A few years ago such equipment would have been immobilized for days or weeks after making a special run. But last spring, within a period of six weeks, one set of equipment moved seven divisions, on trips of several thousand miles.

First the trains, carrying troops with their tanks, moved one division from Fort Knox down to Camp Polk, in Louisiana. As each train unloaded, it picked up a unit from another division, bound for the Arizona desert area. From then on to California, back to the Tennessee maneuver area, again to Louisiana and the desert, and back to California and Tennessee. That series of movements, which could be accomplished only by careful advance planning and scheduling, is one of the prize accomplishments of the military transportation section of the Association of American Railroads, a civilian unit quartered in the Pentagon Building outside of Washington, where it functions virtually as a part of the Army, moving more than 2,500 special trains a month.

At one time during the First World War

there were tied up in eastern terminals and yards more than 200,000 freight cars, far more than could be unloaded, while other parts of the country were suffering from car shortages. The job had been botched, so the Government took over the railroads and botched it some more. But all the fault was not on the railroads or the Government. Much of it was due to faulty planning by shippers.

The railroads and the Government both had more foresight this time. Locomotive power has been conserved by running longer trains, by keeping engines on the road for longer runs, and by loading cars more heavily. When a 20-ton car is loaded with 20 tons of freight, only half of what the engine pulls is payload. But load that car to capacity of 40 tons or more, and the locomotive is pulling twice as much freight while its total load is increased only by one half.

All purely military transportation—of troops, Army freight, and goods for Lend-Lease—is under direction of the Army Transportation Corps, set up after Pearl Harbor as a part of the Services of Supply, under command of Major General Charles P. Gross. In this country, the actual work is done by the roads themselves, co-operating under the leadership of their Association of American Railroads.

But once overseas, the Army takes control and its own railroad troops man the trains, in co-operation with our allies. Long before the war our railroad military units were set up as part of the Army reserves, entire skeleton outfits drawn from individual railways, with operating battalions modeled after the organization division, and shop and maintenance battalions.

On three rail systems across the north of Africa today American railroad men in uniform are working with a motley collection of French civilians, Algerians, and British soldiers, working with everything from the oldest of narrow-gauge engines to the newest of American cars and locomotives, uncrated and assembled on the spot. And as the African and Italian campaigns show, they have been getting results. Farther east, other American railway troops work in partnership with Persians, running the trans-Iranian Railway, from the Persian Gulf cross the mountains to Russia, moving the great flood of Lend-Lease supplies.

Over there they have new cars and new locomotives, thousands of them where they are needed most, and there will be plenty more when the troops move in on Europe. They are moving the stuff that will win the war; and whether or not they talk the same language, whether they are in uniform or not, they all understand each other on that. For they are all railroad men.





A flyer wearing the new A-14 rubber face mask used with the demand oxygen system. Around its edge the mask seats against the skin in an airtight seal.

By STEWART ROUSE

*Drawings by the author. Photographs courtesy of U. S. Army Air Forces.*

**Y**EARS ago, our Army developed the first aerial oxygen equipment, along with its first high-altitude planes. This "free-flow" system worked well enough in the earlier days of military flying; the oxygen was fed from the regulator into the mask, and the pilot turned a handle to increase the flow as he gained altitude.

# Something New in Fashions

**With the new demand oxygen mask, our flyers challenge the Axis enemy at any altitude.**

But in a modern warplane, under combat conditions, flyers have too much else to do. That's why the Aero-Medical Laboratory at Wright Field was set the task of designing oxygen equipment that would "do its own thinking." The solution they have come through with is a honey—the best oxygen system in the world, according to the Air Surgeon General, whose business it is to know.

It's called the "demand" system, because it automatically adjusts its flow to the demand of the flyer's body at any altitude. It gives him air without extra oxygen at ground levels. As he ascends into thinner atmosphere, it automatically begins to add oxygen to the air he breathes. And, it increases the proportion of oxygen as he goes up, until at 30,000 feet—when he needs it most—he's getting pure oxygen.

On night flight, simple adjustments vary the working of the demand system so that the flyer gets oxygen, in increasing quantities, all the way from the ground up. For, research has shown that lack of oxygen is a major cause of poor night vision. If oxygen

## ADVANTAGES OF DEMAND OXYGEN SYSTEM



It provides the user with the proper amount of oxygen at all altitudes and under all conditions up to 38,000 feet. Older "free-flow" system (right) is inadequate above 30,000 feet if physical activity is required. Action is fully automatic, needing no adjustments during flight. It is less subject to failure at low temperatures. Saves oxygen by delivering it only when the user breathes in, and only as much as is needed. Suspension of the mask gives a much more satisfactory and secure fit under abnormal pulsations sharp turns.






isn't used, night-vision efficiency drops with altitude. Effects are noted as low as 5,000 feet.

The "thinking" oxygen equipment looks complex but, in principle, it is relatively simple. The heart of the apparatus is the regulator, which gets its oxygen from specially designed, light but strong cylinders through a supply line or "trunk line." Air comes into the regulator through an air port which closes automatically at 30,000 feet. From the ground to 30,000 feet, the proportions of air and oxygen admitted to the automatic mixing regulator are controlled by a tiny aneroid bellows control, similar to that in a barometer, operating two valves. As the outside air pressure decreases with altitude, one of these valves opens the oxygen supply inlet farther and farther; the other closes the air inlet correspondingly.

One of the main drawbacks of the old-style equipment which the new regulator replaces was its tendency to waste oxygen. The older types supplied oxygen at all times. But the automatic regulator now incorporates a device which cuts off the oxygen flow every time the flyer exhales and renews it with each inhalation. This device, a little diaphragm working a valve, operates on the differential of pressure induced by the reversal of the flyer's breathing. When he



**BAIL-OUT BOTTLE.** If he has to jump, the airman discards his mask and sucks oxygen through a tube from a cylinder in a pocket of a trouser leg

breathes in, the diaphragm flips to one side and a little lever linkage opens the oxygen valve. But when he starts to exhale, the pressure moves the diaphragm and thus shuts off the oxygen-flow valve.

Sometimes, in flight, the pilot may want a momentary "shot" of oxygen. He gets this through a flip of the finger on the auto-mix button of the regulator. This cuts off the air flow when turned to the "off" position and thus gives pure oxygen at any altitude. If, for some reason, the mechanism should fail to function, there is another little handle labeled "Emergency"; this by-passes the entire regulator mechanism and causes pure oxygen to flow directly into the mask feed hose. (Continued)


## "WALK-AROUND" GIVES FLYER FREEDOM OF PLANE





To leave his station, a crew member in a bomber or cargo plane disconnects his mask hose from the demand-system regulator and plugs it into his walk-around. On returning to his station, he recharges the bottle as shown at the right. This operation is also illustrated in the Air Forces photograph on this month's cover








**DEMAND SYSTEM** is seen in detail in this drawing which shows it installed in a fighter plane. The pilot who has plenty to do in flying and fighting the plane doesn't have to control his oxygen.




**THE MASK** is a masterpiece of design based on an anthropological survey of 1,871 aviation cadets (P. S. M., March 43, p. 96) to assure fit.

## REGULATOR IS HEART OF DEMAND OXYGEN SYSTEM





## CONSTANT TESTING SAFEGUARDS FLYERS



Mask-testing apparatus at left is filled with pyrogalllic acid (which absorbs oxygen) and potassium hydroxide (which absorbs carbon dioxide and water vapor). Another safety device is the oxygen flow indicator, above, which shows if system is working

The mask of the new equipment also differs substantially from the type formerly used. The oxygen-air mixture flows directly into the mask through a flexible hose which divides into two lines as it enters the mask, each entry being opposite a nostril. Just below the tiny microphone, at mouth level, is the exit valve. When the flyer exhales, the foul air passes through this valve. The pressure of the oxygen-air mixture in the inlet system prevents the foul air from running down the inlet pipe and contaminating the supply. When the man inhales, the outlet valve—using a soft rubber washer—flaps shut and prevents an inflow of outside air. No low-oxygen-content outside air can enter.

The outlet valve feeds into a duct which carries exhaust air down to the chin and neck. This prevents fogging of goggles.

The new system is equipped with a number of safety and convenience devices. A bouncing-ball flow indicator, set at the side of the pilot's cockpit, tells whether the entire system is in correct operation. This gadget is so arranged that a little ball, within a glass pipe, bounces every time the user of the mask breathes. If the ball should fail to bounce, he would know that he is not getting the proper flow of air-oxygen mixture and would open the emergency valve. When pressure in the oxygen system as a whole drops below 50 pounds—that is, when only one seventh of the total supply remains—a lamp lights up near the bouncing ball. This tells the flyers that they'd better get the plane down below 10,000 feet pretty soon, before they run out of oxygen. Sometimes a blinker device, like a winking human eye, is used instead of the bouncing ball, to show


whether the regulator is in perfect operation.

On large planes—bombers and transports—each flyer has his own regulator and mask, plugging it into his station on the trunk-line oxygen-distribution system. Often, however, especially in battle the flyers have to walk around from one spot to another. For this purpose, each station has a small portable oxygen cylinder known as a "walk-around bottle." The flyer can plug this onto his mask hose when he wants to roam, re-plugging into the central system when he returns to his station. The bottle, when not in use, is recharged by means of a hose at the flyer's station.

Each crew member also has a small bail-out cylinder charged with oxygen under very high pressure. He wears this in a pocket in a trouser leg. If forced to parachute, he takes off his mask, puts the pipe-stem bit of the bail-out hose into his mouth, turns the valve, and jumps. He will have enough oxygen for his trip to earth.

Oxygen to supply the demand system is stored in light but very strong cylinders clamped to structural members of the plane. These are connected to a manifold or linkage of small-diameter pipes, so that all the cylinders deliver their oxygen at equal pressure to the trunk-line pipe, which passes through the fuselage and reaches each crew station. Every cylinder has its own check valve, so that if an enemy bullet punctures it the oxygen cannot blow back through the damaged cylinder and be lost. Cylinders are recharged as necessary from portable high-pressure cylinders carried on a truck, through a filler valve extending outside the fuselage.






## Our Medium Tanks Get a New Engine with Lots of Zip

**O**FF Ford assembly lines has come a tank engine that our fighting men hail as an Axis beater. It has what it takes to triumph in armored warfare—speed, dependability, and “zip.” What’s more, its compact construction makes it simple to service, and mass production is possible with a minimum change of available machinery. It powers our medium tanks and tank destroyers.

Ford and Army Ordnance engineers developed this engine. Its basic specifications were taken from a 12-cylinder aircraft engine of proved merit. The engineers cut it to eight cylinders, added clutch and flywheel, and altered the fuel, ignition and lubrication systems. The result is a liquid-cooled V-type engine weighing approximately 1,500 pounds and developing 500 horsepower at 2,000 revolutions a minute.

Some of its innovations: Crankshaft and flywheel are cast instead of forged; push



End view of new tank engine with cut-away of cylinder assembly. General view at top shows other details, including the accessory drive that simplifies servicing

rods are of one piece of copper-silicon steel; central power drive unit operates camshafts, water pump, oil pump, magneto, fan, and generator, simplifying service; centrifugally cast cylinder liners assure greater strength and longer wear.





Natural Brazilian rock crystals, which are almost pure silica, are the raw material for transparent fused quartz that has found wide use in industry

Crushed into fine pieces, the crystals are packed into a crucible, put in an electric furnace, and heated to the fusing point of 3,200 degrees F.

## FUSED QUARTZ REPLACES STEEL AND GLASS

Photographs Courtesy General Electric Company

**P**RECISION gauges of fused quartz, used to test parts for airplane engines, now release tons of the finest tool steel for other war needs. This new application stems from one of the many remarkable properties that General Electric research workers have found in melted and solidified rock crystal.


Because fused quartz reacts almost negligibly to changes in temperature, it proves ideal for standards of length and of angles. Its high melting point, exceeding that of glass by some 1,200 degrees F., especially suits it for use in high-temperature vacuum

tubes for lighting airfields. Probably the flattest things in the world are 10-inch disks of the material, ground for optical purposes by the National Bureau of Standards. Their surfaces,  $1\frac{1}{2}$  inches apart, vary less than  $4/10,000,000$  of an inch from perfect planes.

While healthful ultraviolet rays of sunlight cannot pass through glass, fused quartz transmits them freely. Some day the material may be made cheaply enough for windowpanes. Already, germ-killing rays of ultraviolet light are being emitted by sterilizing lamps employing fused-quartz tubes, and the infrared rays called radiant heat are as easily transmitted.


### EXPANSION

Its low coefficient makes fused quartz ideal for fine gauges and optical lenses and flats



### LIGHT TRANSMISSION

Ultraviolet rays of the sun or a lamp pass through fused quartz, but glass halts them



10

One end stuck into a furnace, a fused-quartz rod "pipes" sufficient heat to light a cigarette, yet its sides remain cool enough to be held by hand



9

Laboratory ware of clear and translucent fused quartz has a high melting point, low coefficient of expansion, and very great resistance to acids







3

After it has cooled off, the ingot into which the mass of crushed quartz crystals has been fused is lifted out of the furnace for further processing


## IN NEW USES

Drafts or spattering of molten metal from the arc lamps in motion-picture projectors sometimes crack their glass condensing lenses. Quartz lenses now eliminate the trouble. Resistance of fused quartz to chemical corrosion adapts it especially to laboratory flasks, beakers, and test tubes.

Though fused quartz has been familiar to scientists for more than a century, until recently it has been used mostly in the laboratory. Natural quartz crystals are melted in an electric furnace to make the transparent material, and a selected grade of pure sand is used for a less expensive translucent or opaque variety.

## HEAT RESISTANCE

Fused quartz is often used continuously at 1,800 degrees F. and intermittently at 2,300



8

Because of a high resistance to thermal shock and freedom from distortion caused by heat or friction, fused quartz is ground and lapped faster than glass


4

Rods are made from solid ingots, and tubes are worked from hollow ones. Both forms of ingots and fused-quartz rods and tubes are shown above



5

These fused-quartz blanks, 12 inches in diameter, will be made into 10-inch optical flats varying less than  $4/10,000,000$  inch from a true plane



6

When a hollow fused-quartz ingot is worked into a tube, it is first placed in a furnace where it is again heated—this time to make it pliable

Then, while part of the ingot remains in the furnace, it is drawn into a long tube of the diameter required. The solid ingots are worked into rods in the same way





# How to Ditch a Fortress



What happens to the crew of one of Uncle Sam's big land bombers when it is forced down on the sea? It may be only a matter of seconds before the plane sinks, but every man knows his job and does it.

WHEN the order, "Prepare to ditch," comes over the interphone system of one of our big bombers, 30 seconds may mean the difference between life and death for the crew. For that warning, sounded by the pilot, is notice that the big land plane is being forced down on the sea, and 30 seconds afloat without seaplane landing gear may be all that can be expected even under the most favorable conditions.

So well trained are our bomber crews, though, that these emergency landings on



## Recommended DITCHING PROCEDURE

AS COMPLETE EVACUATION OF THE AIRPLANE SHOULD NOT TAKE OVER 30 SECONDS PRE FLIGHT PRACTICE DRILLS SHOULD BE PARTICIPATED IN BY ALL CREW WHO ARE TO MAKE A FLIGHT OVER WATER, OR WHOSE OPERATIONS ARE GENERALLY OVER WATER.

WHEN IT BECOMES EVIDENT THAT THE PLANE IS TO BE FORCED DOWN AT DUE TO LACK OF FUEL, OR THAT ALTITUDE OF AT LEAST 1000' CANNOT BE MAINTAINED—



A COMPLETE AND CAREFUL INSPECTION OF EMERGENCY EQUIPMENT SHOULD BE MADE BEFORE EACH LONG OVERWATER FLIGHT. CHECK LIFE RAFTS, EMERGENCY KIT BAGS (PROVISIONS) AND EMERGENCY RADIO EQUIPMENT. THE KIT BAGS AND RADIO ARE STORED AFT OF THE RADIO COMPARTMENT.

FOR LIFE RAFTS: FIRST DISCONNECT CO. CABLES FROM LATCH HERE

THEN PULL THE BLUE LIFE RAFT HANDLES IN THE RADIO COMPARTMENT



PREPARE TO DITCH



— THE PILOT GIVES THE "DITCHING" COMMAND OVER THE INTERPHONE. **Warning!** THIS COMMAND MUST IF POSSIBLE BE GIVEN BEFORE THE FUEL SUPPLY IS LESS THAN REQUIRED FOR 15 MINUTES OF FLIGHT. THE CHANCES FOR A SUCCESSFUL DITCHING



ALL CREW MEMBER WILL ACKNOWLEDGE THE DITCHING COMMAND OVER THE INTERPHONE.



THE BOMBARDIER, AFTER ACKNOWLEDGING THE DITCHING COMMAND, WILL JETTISON OR BOMB BAY TANKS IF MORE THAN HALF FULL, AND CLOSE THE BOMB BAY DOORS. IF THERE IS INSUFFICIENT TIME TO RELEASE THE BOMBS AND CLOSE THE BOMB BAY DOORS, ASCERTAIN THAT THE BOMBS ARE "SAFE" AND LEAVE THE DOORS CLOSED.



THE NAVIGATOR WILL DETERMINE THE POSITION AND INFORM BOTH PILOT AND RADIO OPERATOR.

HE WILL TAKE WITH HIM NECESSARY INSTRUMENTS TO MAKE SAMPLES.



THE RADIO OPERATOR WILL FIRST JETTISON THE HATCH COVER...

THEN AS DIRECTED BY THE PILOT, HE WILL SEND AN APPROPRIATE DISTRESS SIGNAL AND POSITION. AFTER COMPLETING THE DUTY HE WILL BRING THE EMERGENCY



THE SIDE GUNNERS WILL JETTISON THE SIDE GUNS AS THEY MAKE VERY DANGEROUS BATTERING RAMS. IF THERE ARE NO SIDE GUNNERS THIS DUTY SHOULD BE GIVEN TO OTHER CREW MEMBERS BEFORE FLIGHT



WATCH SHOULD BE JETTISONED

TAIL GUNNER SHOULD CLOSE THIS DOOR BEHIND HIM

THESE DOORS ARE LEFT SNAPPED OPEN

AFTER COMPLETING HIS INDIVIDUAL DUTIES, EACH MEMBER GOES TO THE RADIO COMPARTMENT WHICH IS THE CRASH STATION FOR ALL BUT THE PILOT AND CO-PILOT



BOTH PILOT AND CO-PILOT WILL STRAP THEMSELVES IN THEIR SEATS

THE PILOT WILL DIRECT THE CO-PILOT TO CUT THE TWO INBOARD ENGINE IF THE TWO OUTBOARD ENGINES ARE EXHAUSTED AND TO FEATHER THEIR PROPELLERS

IF THE SIDE WINDOWS ARE TO BE USED, THEY SHOULD BE OPENED TO GIVE THE CREW FREEDOM OF MOVEMENT. LEAVE THEM CLOSED DURING DITCHING. CALCULATE PLACE AND WAY IN EVENT OF JAMMING

BE SURE ALL EMERGENCY EQUIPMENT IS IN THE COMPARTMENT. THROW ONBOARD ANY EQUIPMENT THAT MIGHT COME LOOSE



REMEMBER: ALWAYS USE YOUR HEAD PROTECTION & TAKE CARE POSITIONS. DO NOT TAKE A POSITION IN CENTER OF COMPARTMENT AS DANGEROUS UPPER STRUCTURE MAKES THIS UNSAFE. BRACE HEAD AGAINST SOLID STRUCTURE IF POSSIBLE. DO NOT LEAVE THESE POSITIONS UNTIL PLANE HAS COME TO REST AS THERE WILL LIKELY BE MORE THAN ONE SHOCK.

water have lost much of their hazard, at least insofar as it relates to loss of life or injury in the actual landing. Each man knows his station, and he goes to it, ready to act instantly with the final impact of the plane on the water. Each has his specific duty to perform, and he does it without hesitation and without delay so that he and his mates will be assured of at least a fair chance of survival in their life rafts. In addition, each man also knows duties of the others in the crew so that no hitch will oc-

cur should any be too seriously injured to carry out his part.

Specific instructions, known officially as the "ditching procedure," have been prepared by the Boeing Aircraft Company and the Army Air Forces. The steps apply particularly to Boeing's big Flying Fortresses, but in general they are also followed for a water landing made by any other multimotored land plane. Illustrations and instructions from the "ditching procedure" are given on this and the preceding page.

THE PILOT SHOULD ATTEMPT TO SET THE AIRPLANE DOWN IN A TROUGH (THIS IS USUALLY CROSSWIND). THE TWO OUTBOARD ENGINES ARE USED FOR CONTROL AND TO FLATTEN THE APPROACH. THE LANDING GEAR SHOULD BE UP. THE FLAPS LOWERED MEDIAN AND THE IDENTIFICATION SWITCHES CUT A FOOT OR SO ABOVE THE WATER.




Do Not Stall In!




IF TAIL IS DOWN FUSELAGE IS LIKELY TO BREAK HERE

WATER SHOULD BE TOUCHED AT ABOUT 90 MPH. COME IN AS LEVEL AS POSSIBLE. ALL MEMBERS SHOULD HAVE LIFE VESTS ON. PARACHUTES REMOVED AND SHOULD HAVE ON ALL EXTRA CLOTHING TO BE WORN ON RAFTS. NIGHT VISION GOGGLES IF ALL BRIGHT INFLUENCE LENSES AND USE WITH THE AMBER LAMPS



LIFE RAFT HANDLES


AS SOON AS THE AIRPLANE HAS COME TO REST THE PREDESIGNATED MEMBER



IF MAN OUT AT NIGHT DO NOT HAVE LIGHTS ON. IF THERE ARE LIGHTS ON, THEY SHOULD BE TURNED OFF. IF THERE ARE LIGHTS ON, THEY SHOULD BE TURNED OFF. IF THERE ARE LIGHTS ON, THEY SHOULD BE TURNED OFF.

IF THERE IS A FIRE, MEN SHOULD BE ASSIGNED TO EXTINGUISH DUTIES. EACH MAN SHOULD BE FAMILIAR WITH THESE SO THAT IN CASE OF A FIRE HE CAN TAKE ACTION.

PILOT AND CO-PILOT WILL EXIT THROUGH THEIR SIDE WINDOWS OR THROUGH THE RADIO COMPARTMENT HATCH (DECIDE WHICH BEFORE FLIGHT) CAUTION: NO CREW MEMBER SHOULD INFLATE HIS LIFE VEST UNTIL HE HAS EMERGED FROM THE AIRPLANE



THE RAFTS SHOULD BE FASTENED TOGETHER, SO THEY WILL NOT DRIFT APART



ONCE ABOARD THE RAFTS A CHECK SHOULD BE MADE TO LOCATE LEAKS. REPAIR THEM WITH THE KIT PROVIDED IN THE RAFT. KEEP AWAY FROM THE AIRPLANE IF IT FLOATS BUT STAY IN THE VICINITY IF POSSIBLE. DO NOT REMOVE WET CLOTHING. DO NOT TALK MORE THAN NECESSARY. IT

DO NOT JUMP ON AN INVERTED RAFT AS THIS WILL EJECT AIR TRAPPED UNDER IT AND RIGHTING BECOMES MORE DIFFICULT



IF THE LIFE RAFT IS INFLATED UPSIDE DOWN ONE MAN SHOULD JUMP IN THE WATER AND RIGHT IT. IF THERE ARE HANDLING PATCHES ON BOTTOM OF RAFT GRASP THEM WITH BOTH HANDS AND WITH KNEES ON BUOYANCY CHAMBER. LEAN BACK AND PREPARE TO BE SUBMERGED FOR A MOMENT. EVEN THE LARGEST RAFT WILL TURN OVER.




A SIGNAL KIT CONTAINING A PISTOL AND FLARES IS IN A WATERPROOF SEALED POCKET OF THE LIFE RAFT. IT MAY BE ADVISABLE TO LEAVE THE KIT SEALED IN THE POCKET UNTIL A SHIP OR PLANE IS






1 This huge floor at the Army Air Forces School of Applied Tactics, Orlando, Fla., is a map of the China coast. To train officers in air defense, electric "jeeps" (left) roll over it representing bombers

## Electric "Jeeps" Aid Air-Defense Training




2 Wac "spotters" stationed in balcony posts on the four walls take sights on an invader and report its course, speed, height, and other data



3 At the main filter board, duplicating equipment of a defense center, this information is used to determine the objective and arrival time of attackers

4 From the plotting table, orders are flashed to "interceptor bases" on the big map floor, giving courses on which enemy can be headed off

5 Getting orders on a walkie-talkie, a Wac sets the controls of her interceptor "jeep." It should meet the "bomber" before the latter hits its target





# CARGO PLANES DOUBLE AS AIR AMBULANCES




**FLYING AMBULANCES**, converted from giant transports that carry men and matériel into battle, are being used to speed the wounded to base hospitals. Cargo planes going up to the front, they are hospital ships coming back. Many are big C-47's like that shown above at a demonstration at the School of Applied Tactics in Florida.

**STRETCHER SUPPORTS** that can be stored under the floor boards when not in use are easily attached to the bulkheads of the fuselage, as in the photo at right. Stretchers are held on with clamps so they will not be thrown off if the plane goes into a sharp maneuver. Medical equipment, under the control of a flight surgeon, is complete, including oxygen tanks, as shown below, and all other necessities for sustaining life on the flight to the base hospital. Soldiers' gas masks, with filter removed, are used for oxygen masks.




**A**IR evacuation of sick and wounded soldiers is being hailed as a great saver of lives in this war. Big cargo planes, flying matériel into battle zones, are converted into swift aerial ambulances for the trip back.

In New Guinea, where transfer over mountains would take three weeks, planes cut the time to less than one hour. A critically injured soldier was brought from Indo-China to the United States in eight days, Brig. Gen. David N. W. Grant, Air Surgeon, reported recently. By land and sea, the trip might have taken three months.





## new Tools



**ALL-PLASTIC GOGGLES**, set with shatterproof Plexiglas lenses that insure clear and undistorted vision, are now manufactured for war workers by the Watchmaker Optical Co., of Providence, R. I. Weighing less than two ounces, the full-framed goggles fit right over prescription glasses. Perforations in the frame prevent fogging, and special filters can be snapped on the lenses for glare protection.



**A CLEANING CAGE** that makes short work of small parts like gauges and bearings has been designed by the L. & R. Mfg. Co., Newark, N. J. Run by electricity, the unit is as simple to use as a washing machine and is easily operated by a woman. The speed of the whirling cage, which holds the dirty parts, can be adjusted for varying needs. Entire portable unit weighs less than 50 pounds.



**ONE-MAN RIVETING** with a vibrator that is controlled by the "travel" of the driving set has just been perfected by the Buffalo Airplane Division of Curtiss-Wright. This "jam riveting" can be done with either a hand or standing vibrator, and is especially valuable on tricky jobs like cowling manufacture. Since the gun is internally controlled, the work is unusually accurate.



**ELECTRODE HOLDERS** slim enough to work in tight places and weighing only 12 ounces are offered by Jackson Products, of Detroit. Insulated, the holder guards welders' eyes from flash and cuts out waste due to touching work with bare holders. It holds rods up to 3/16 inch.



# Brain-Teasers in Uniform

## SEVEN PROBLEMS WITH A WARTIME SLANT



### 1. His Dollars Make Sense

A MAN puts half his week's pay into war bonds and stamps. After buying them, he has left just as many cents as he

had dollars, and half as many dollars as there were cents in the envelope when he received it. What is his weekly pay?

### 2. Bombing by Halves

A BOMBARDIER is told to set fire to four enemy towns. Over the first one he drops half his bombs and half a bomb. Over the second he drops half the bombs he has left plus half a bomb. Over the third town he drops half the remaining bombs and half a bomb. Then, taking count, he finds that he has 36 bombs left for the fourth town. What was his original load?

### 3. Defense Without Design

A FIELD of pillboxes is laid out as illustrated here. Corporal Fussbudget, gunner, whose secret passion is design, is considerably upset by the fact that his pillbox, M, plays no essential part in the design created by the other boxes. How might the Army engineers have laid out the field to put all 13 into a similar pattern, and so satisfy the corporal's aesthetic sense?



### 4. Ships That Pass in the Jungle

BOATS A, B, and C, carrying men up a narrow jungle river, meet boats D, E, and F, bringing down wounded. There is no room

to pass, but there is a small basin at P which will admit any one of the boats singly. How can the boats pass?

### 5. It's Later Than They Think

A CERTAIN street corner in an occupied coastal city is guarded day and night by German sentries. The watch is changed every time the two hands of the clock coincide. At what times, within 24 hours, will the guard be changed? If no guard is on duty there more than once each week, how many will serve on that corner from a minute before Monday noon to a minute after Sunday noon?



### 6. Japs with a Price on Their Heads

SUPPOSE Army Intelligence offers a bounty on Jap prisoners brought in for questioning. Outfit A brings in half a dozen dozen Japs and is paid a dozen dollars the half dozen. Outfit B brings in a dozen dozen Japs and receives half a dozen dollars the dozen. Which outfit receives more money?

### 7. Getting in Under the Wire

IMAGINE, if you can, a row of telephone poles set up to girdle the earth at the equator. Suppose also the earth is a perfect and even-surfaced sphere of exactly 25,000 miles circumference. Now string on the poles a high-voltage wire 100 feet longer than the circumference of the earth, so that when the current is thrown on there is a charged circle around the earth concentric with the equator. Could a man pass under this wire at the equator without touching it? Could a ship pass under it?—E. J. DINTRUFF.

See page 220 for answers.





# How You Can See the Weather

Great currents in the atmosphere produce the changes that make us call it a "nice day"—or swear!

By DON ROMERO

Drawings by ERIC SLOANE

when, to every pilot who took his plane into the air, the weather, instead of being a subject of casual conversation, would be a matter of life and death.

Up to now, most of us have looked upon weather forecasting as pretty much a hit-and-miss affair. Meteorologists talked solemnly of rising pressures and departing storm centers, but few of us had faith in the prediction that tomorrow would be "fair and warmer." Often we were just as ready to listen to some old-timer who, with


an eye for the weather, would cast a knowing glance at the sky and then recite some ancient jingle such as "Mackerel sky, not three days dry."

Today, however, meteorology largely through the medium of aviation—is bringing home to many of us a new and entirely

WHEN Mark Twain said that everybody talks about the weather but nobody does anything about it, he did not envision the spectacular advances that lay ahead in meteorology. Nor did he foresee the day when the airplane would be as common as the horse and buggy and

## WHERE AMERICA GETS ITS WEATHER

Governing the weather of the United States are a number of huge bodies of air, each of which takes its name from the region from which it comes and where it has matured. Sweeping across the country in the directions indicated on the drawing below, these major air masses determine almost entirely the weather of the areas over which they pass. In turn, however, they are often affected





understandable concept of the enormous mass of air that floats over our heads. It is taking that gigantic ocean and showing us not only how to "see" it, but also how to feel it and smell it!


Known as Air Mass Analysis, this new concept is based on the studies and experiment of Vilhelm Bjerknes, who, with other Norwegian meteorologists, was one of the pioneers in the science of "long-distance" weather forecasting. Instead of visualizing the atmosphere as one vast sea whose vagaries accounted for weather that could be predicted with certainty only a few hours in advance, Bjerknes discovered that the atmosphere actually is composed of several giant individual bodies of air, each of which is distinguished by its own heat, humidity, and clarity. Bjerknes also discovered that, at definite times of the year, these bodies of air moved in well-defined paths across the earth's surface. He also found that the weather that prevailed in a given area

by the temperature, humidity, and topography of the ground. Changes in the weather come as a result of one air mass invading an area occupied by another


was governed almost entirely by the type of air that was occupying that area at that time.

Known by the outlying regions from which they come and where they have been conditioned, several of these huge air masses dominate the weather of the United States. The Tropical Atlantic and Gulf airs are warm, humid currents that have been cooked up by the intense sun and warm sea water of the Caribbean region. The Polar Atlantic is a cold, low-clouded, drizzling current that sweeps down from the Grand Banks off Newfoundland. The Polar Continental is a cold and lively current of air. From the deserts of Mexico and Arizona comes the Tropical Continental—a burning, arid body of air that fortunately gets only as far as Oklahoma, Colorado, and Kansas. Up through Southern California comes the Tropical


## AIR MASSES AND THEIR "FRONTS"



"Fronts" are set up when two air masses of different types come in contact with each other. It is here greatest turbulence occurs



Here a mass is shown moving over a ground area. As long as it remains unaffected by the contact, the mass will have the same specific humidity and potential temperature at all "X" points





Pacific, a soft, lazy kind of air that is believed to originate in the South Seas. The cool, moist Polar Pacific that chills Seattle comes all the way from Siberia. The eighth body of air—Sec Superieur—is believed to originate in the stratosphere over the Galapagos Islands.

One thing that must be kept in mind is that while these bodies of air largely determine the weather, they, in turn, are often affected by the areas over which they pass. An air sweeping down over a lake region is very likely to bring weather that is raw as well as cold. A warm, moist body of air moving over cold ground will be responsible

for cloudy weather—caused by the air's lower layer being chilled and thus having some of its moisture condensed into visible form. A clear, cold body of air passing over a hot area will pick up little heat from the sun, but will allow its rays to continue to heat the earth's surface, and then absorb heat from that.

Even the topography of the ground can, for a time, change the character of an air mass. Coming in at a low level, a warm current can be carried up the side of a high mountain range and be tossed high into the air—with a resulting condensation of its moisture that may keep the mountain range

## What Do You Know About Weather?

This not-too-difficult quiz will help you to test your knowledge of meteorology. Under each question are some possible answers, only one of which is correct. Check your answers with those on page 94.



1. THE AREA AT "X" IS

- (A) A PACIFIC FRONT
- (B) TROPIC WINDS
- (C) A HIGH-PRESSURE AREA



2. THESE SYMBOLS ALL MEAN

- (A) CLOUD
- (B) SNOW
- (C) RAIN



3. HAIL FALLS FROM

- (A) CUMULUS
- (B) CUMULUS
- (C) CUMULONIMBUS



4. THIS WIND DESIGN SHOWS A

- (A) LOW-PRESSURE AREA
- (B) HIGH-PRESSURE AREA
- (C) CYCLONE AREA




5. "X" IS A — "Y" IS A —

- (A) COLD FRONT
- (B) WARM FRONT
- (C) OCCLUDED FRONT



6. TRADE WINDS BLOW

- (A) FROM THE NORTH
- (B) EAST TO WEST
- (C) WEST TO EAST




7. STRATOSPHERE TEMPERATURE THIS BALLOON MEASURES

- (A) 10°F
- (B) -67°F
- (C) -20°F




8. THIS BALLOON MEASURES

- (A) TEMPERATURE
- (B) PRESSURE AND HUMIDITY
- (C) WINDS ALOFT



9. WIND SOCK IS BLOWN BY

- (A) GENTLE BREEZE
- (B) STRONG BREEZE
- (C) STRONG GALE



10. SMOOTHEST FLYING IS

- (A) OVER CUMULUS
- (B) THROUGH CUMULUS
- (C) UNDER CUMULUS



11. CIRRUS IS FORMED BY


- (A) HAIL
- (B) DUST PARTICLES
- (C) ICE PARTICLES



12. "CAVU" MEANS

- (A) CLOUDS AND VAPOR UNSAFE
- (B) CEILING AND VISIBILITY UNLIMITED





Being heavy, the invading cold air will tend to come in low, lifting the warm air as it pushes it back. In the northwest will appear a solid cloud bank—the actual "front"—which will build up as it advances.



Invading warm air, being light, will come in "over the top." First warning will be "mares' tails," followed by progressively lower clouds, and rain. An invading cold air will then start the cycle all over again.

snow-capped through an entire hot summer. Crossing the mountain peaks and rolling down the other side, this same air mass will be heated up again by the increased atmospheric pressure, and in its now drier state will be so thirsty for moisture that it will suck the surrounding sky dry of every cloud.

Picking up heat from its contact with a warm area, the lower layer of a cool air mass will become light and will start to rush upward in the form of giant air bubbles, some of them hundreds of feet in diameter. A plane, flying along in cool, stable air, will get a sudden jolt as it is caught up in one of these swiftly rising currents, and then will be dropped with equal suddenness as it escapes from the bubble area. Although

pilots of passenger planes naturally strive to avoid such turbulent spots, they can be of help to a pilot who has to gain altitude quickly. All he needs to do is to keep circling in one of these bubble areas and let it shoot him skyward at a much faster rate than he could climb. The same is true—and of greater importance—to the glider pilot, who must rely solely on upward currents of air to stay aloft.

As important as the discovery of the air masses themselves is the locating of their "fronts"—the border lines that separate one mass from another. Modern meteorology is teaching us to "see" these invisible masses by observing the action that results when one mass drives out another, for it is at



these fronts that "cloud" banners most clearly define the otherwise invisible air currents. The greatest local disturbances are associated with these fronts.

One of the ingenious methods by which schools of meteorology are teaching students to "see" individual air masses involves the use of warm water that has been colored red, and cold water that has been colored blue. When poured into a glass and viewed from the side, these two types of water can be seen to set up the same kind of "fronts" that occur in the atmosphere; the cold, heavy water tending to push downward; the warm, light water surging upward.

"Feeling" and "smelling" the weather, long considered whimsical notions of forecasting, have also been reinterpreted for us in a practical and understandable way. "Smelling rain in the air," for instance, means that we are in a low-pressure, or storm, area; odors from swamps or other low, moist places, formerly held captive by the high pressure of good-weather air, have now been released into the atmosphere. When we say that "it feels like rain," it merely means that we are reacting to a falling pressure,

### ANSWERS TO QUIZ ON PAGE 92

- |     |        |      |
|-----|--------|------|
| 1—A | 5—A, B | 9—A  |
| 2—C | 6—B    | 10—A |
| 3—C | 7—B    | 11—C |
| 4—B | 8—C    | 12—A |

which has a definite physiological effect on us, such as making us depressed or irritable. Other similar storm signals are the game leg that starts to pain, and the corn that begins to ache.

Almost simultaneously with the discovery of "long-distance" weather forecasting came the realization that here was a

powerful weapon of war. Soon after the Norwegian pioneers announced their findings to the world, the Germans started an intensive study of modern meteorology. Following close on their heels came the Japs, who today have a first-rate weather bureau.

How well the Germans have learned the new science is evidenced by the spectacular escape of their battleships *Scharnhorst* and *Gneisenau* through the English Channel under the very noses of Britain's land-based bombers. At the time, it seemed as if the Germans had taken a 100-to-1 chance, and won. Actually, with characteristic Teutonic thoroughness they had timed the escape to the day—a day which their meteorologists long in advance had advised the Admiralty would bring the worst weather that the Channel had seen in years. Even if the

## MOTION PICTURES TEACH PILOTS HOW TO

These drawings are from one of a series of aerological



Carrier-based planes are sent on scouting mission that will take them through cold front on both outward and return flights



2 Cumulus clouds appear on northwest horizon, and extend far to left and right. Plane drift is northward, indicating southerly winds. Air is unstable



3 Section leader now knows that he is approaching the cold front. Low cloud bases and a dark, unbroken rain area indicate a storm

On return trip, flight is at a low level, for cloud bases have lifted and clear spaces are to be found in heavy rain area

8 Selecting a light area, the leader goes into the front at right angle. To avoid the storm, he flies as close to the ocean surface as safety permits

9 Close on the tail of their leader, the other planes wing their way into the "hole" he has found. The direction of the wind is now northerly






British bombers had known that the ships were in the Channel, they would have been helpless, for a "pea-soup" fog enveloped the vessels as they raced for the open sea.

When Germany launched its invasion of Poland, the Poles, fighting fiercely to resist an already overpowering foe, cursed the luck of the invaders in the excellent weather that was aiding their advance. Actually, the Germans had waited for months for the weather to become their ally, and had not dared turn a wheel before their experts had guaranteed them two absolutely dry and clear weeks in which to move their tanks and trucks.

Most Americans like to believe that the Japs chose December 7 for their attack on Pearl Harbor because it was a Sunday, when normally the base would be enjoying "a day off." More likely the truth is that they carefully selected a time when it would be good sailing weather for their carriers, good flying weather for their planes, and a clear day for bombing an unsuspecting foe. In one notable instance, however, Jap meteorologists badly misread the signs. In the Bismarck Sea engagement, the Jap armada was advancing under the protective screen of a thunderhead when suddenly the clouds evaporated into a clear sky and left their battleships and transports sitting like ducks on a calm lake. *(Continued on page 220)*



**RADIOSONDE** An invaluable weather device, this robot broadcaster sends down to earth a steady stream of atmospheric data as it ascends at the tail of a balloon. In the stratosphere, the balloon bursts, and the radiosonde floats to earth supported by a parachute.

## AVOID THE DANGERS OF A "COLD FRONT"

training films made by Walt Disney for the U. S. Navy



**4** Leader avoids storm by climbing. When temperature of outside air drops, he makes drift correction to right to make up for change in wind



**5** Once the flight section is past the storm line, the leader takes it down until the surface of the water can be seen through the clouds



**6** At this point the planes descend to scouting level and proceed on their assignment of searching the designated area


**10** In a few minutes the air temperature begins to rise, indicating that the planes are through the front and in southerly winds

**11** In another minute or two, all of the planes have popped out the other end of the "hole," and in front of them is nothing but clear sailing

**12** Accomplished with apparent ease, this mission could have cost lives if leader had not shown good weather sense








ARMY  
CREATION

**INFRARED DE-ICING RADIATORS** are proposed by J. D. Altemus, of Roslyn, N. Y., as a new solution to one of aviation's most insistent problems. Mounted on the nose and propeller hub, the radiators would focus their beams on the propeller blades and leading edges of the wings to keep them above icing temperature.



**TRACER BULLETS** that ignite fast enough for use in short-range Tommy guns have been designed by Col.

Sterner St. P. Meek, U.S.A. By increasing the exposed area of the igniter compound on which the propellant powder acts, and shortening the fire's path through the compound, the tracer material is made to ignite almost instantly after the discharge.



**A NEW DIRECTION FINDER** employing a cathode-ray oscilloscope has been developed for planes by Donald G. Little, of Baltimore. As the loop antenna revolves, a circular wave pattern appears on the oscilloscope screen which is calibrated to 360 degrees. When radio signals begin to come in, a depression appears in the pattern to indicate the direction from which they are being sent.




# IDEAS



**FLAME-THROWING TANKS** that are said to be able to spew out their jets of fire a distance of 110 yards are reported to be among Germany's new "secret weapons." The tanks are also said to be equipped with a smoke-screening device that makes it possible for them to envelop themselves in a thick artificial fog in a matter of a few seconds.

**MINE-LAYING U-BOATS** are now believed to be in use by the Germans in an effort to destroy the bridge of ships carrying supplies to our allies and overseas forces. In addition to torpedoes, the U-boats carry a substantial load of mines which they can plant while submerged by dropping them from slotted chambers.



MINES PLANTED FROM SLOTTED CHAMBERS IN BOTTOM OF SUBMARINE



# Fighting on a thousand fronts is

## OUR NEW WEAPON IN THE DARK

By JEAN ACKERMANN

**A** LEADER of a night scouting party consults his map. As he is near the enemy lines, it would be suicide to strike a match or use a flashlight. No need. Printed in luminous ink, lines of the map shine dimly but clearly in the dark.

The party moves on. Lest his men become separated from him, the leader wears a faintly glowing button on his back. Similarly, to the rear, ghostly processions of blacked-out tanks and troop-loaded trucks are advancing in follow-the-leader style, each guided by a spot of luminous paint on the one ahead.

Now the scouts have completed their mission. To mark directions for the secret troop movement, they have daubed roads and trees with splotches of ordinary-looking paint. When a soldier turns the invisible beam of a special black-light flashlamp upon one of the painted direction markers, it lights up as plainly as a traffic signal.

Through 30 centuries, from the time when

ancient Egyptians used light-emitting minerals to create a mysterious glow around temple altars, the phenomenon called luminescence remained no more than a showy novelty. It turned up in the theater, where seemingly unoccupied shoes tapped brightly across an unlit stage, and where costumes and scenery gave striking luminous effects. It came down to earth, and into everyday life, in fluorescent lamps for homes, offices, factories, and outdoor displays. From this beginning, its practical uses on war and home fronts are multiplying constantly.

According to a recent order, all ships of more than 3,000 tons using New York Harbor must have doors, stairways, control valves, steam pipes, and other important points marked with luminous paint. Thus, in case a torpedo puts the regular lighting system out of commission, sailors can still make repairs or find their way to lifeboats. Direction markers pointing to air-raid shelters, and the shelters themselves, may use "firefly" illumination in total blackouts. Setting an example for motorists in air-raid

**CIVILIAN USE.** Street curbs, doorknobs, stairways, light switches, and other similar points can be covered with luminous paint to guide people safely through a blacked-out area

Fashion has not neglected to avail itself of the novel effects made possible by luminescence, using it on hats, dresses, coats, stockings, hairdress, and jewelry. In the theater, too, it often appears in settings and costumes





# THREE KINDS OF LUMINESCENT MATERIALS

	FLUORESCENT GLOW DURING EXPOSURE TO ULTRAVIOLET RAYS	PHOSPHORESCENT GLOW AFTER EXPOSURE TO LIGHT OR ULTRAVIOLET RAYS	AUTOLUMINESCENT GLOW FROM SELF-CONTAINED SOURCE
NATURAL FORM			
ARTIFICIAL FORM (POWDER, PLASTIC PAINT OR FABRIC)			
DURATION OF USEFUL BRILLIANCE			
WAR USES			
HOW IT WORKS			

**MILITARY USE.** A radioactive material sealed in a plastic case has been designed by Army engineers to serve as a "tail light" for military vehicles moving through a darkened area. In a complete blackout the marker can

be seen clearly at 100 feet. A similar marker worn by the leader of a night scouting party serves to keep the leader in constant view of his men and prevents the party from becoming separated.





## "LIGHTING" DANGER SPOTS IN THE HOME



In an air raid, more damage is likely to result from people bumping into things in the dark than from the bombs. Pasting luminous material on such dangerous spots as pointed desk corners helps to prevent accidents

precautions; New York's Mayor La Guardia uses a car with phosphorescent fenders and bumpers. Many London streets and sidewalks now are outlined with luminous strips or curb markers, which we may possibly adopt in coastal areas.

Fluorescent powders can be used for testing the soundness of a gas mask. They are spread on the outside of the mask, the wearer takes several breaths, and the interior then is examined under black light for telltale glow.

Cases of arson and other forms of sabotage committed with pilfered explosives have been cleared up by injecting traces of fluorescent dye into the waxed-paper wrappings of sticks of dynamite, and the gums and glues that go into bombs. It is impossible to handle them without getting traces of the dye into the pores of the skin. Suspects, rounded up and questioned in a routine way, are then suddenly exposed to black light. The dramatic evidence of glowing hands seldom fails to obtain confessions. Senders of false fire alarms, and passers of counterfeit money, have been trapped by

somewhat similar means.

In a standard industrial test for flaws in castings and stampings, the piece is magnetized and dusted with metallic powder, which outlines any cracks or internal defects. A recent improvement on this scheme makes the powder luminous under black light, giving a more conspicuous and sensitive test. The method will also test a surface for freedom from oil.

Medical workers find a new tool in fluorescent stains. Cancerous and other cells treated with these dyes and examined under a microscope with black-light illumination reveal characteristics that can be observed in no other way.

For "blackout parties," originated in raid-darkened London, luminous clothes and furniture provide the only light in the house—except in such games as "blackout golf," played with a self-glowing club, ball, and indoor putting green. Fashion fads include luminous dresses, capes, hats,

stockings, hairdress, and jewelry.

More practical domestic uses of modern luminous paint will reduce our yearly toll of 30,000 fatal home accidents. Danger spots such as stair treads and electric fans glow all night when outlined with long-wearing phosphorescent preparations. Applied to street numbers, doorknobs, keyholes, and light switches, they serve a home owner's convenience without using electricity.

Scientists classify luminescent materials into three or more distinct kinds, according to their behavior, which in turn decides which is best suited for a given use.

Fluorescent substances glow just so long as they are exposed to ultraviolet rays—popularly known as black light—and no longer. This property has suggested the war use of fluorescent buoys to guide friendly ships through channels in mine fields, when illuminated momentarily by a black-light searchlight. Of the many known fluorescent minerals, some are ores of strategic war metals. Important deposits of tungsten ore have been located by night prospecting with black-light equipment.



Phosphorescent materials soak up illumination from the sun or from artificial light. Then they proceed to reradiate it for several hours, without exterior stimulation. Luminous paint made from such substances provides all-around service and is unaffected by power failure. One of its former disadvantages—that it could not be extinguished at will—is now reported to have been overcome by Gilbert T. Schmidling, a pioneer American research worker in the field. By illuminating it with strong red light, he says, the phosphorescence can be “put out.” Sub-

sequent illumination with sunlight turns it on again.


Self-illumination, or autoluminescence, occurs spontaneously from a variety of chemical and physical actions. The firefly, nature's prize example, owes its glow to a slow form of chemical oxidation, which has been duplicated in the laboratory. Crystals of saccharin emit light when crushed or rubbed together. The luminous paint employed on watch dials provides permanent light by bombarding a metallic sulphide with rays from radium.

## LUMINOUS MATERIALS HELP INDUSTRY TO “PLAY SAFE”

To protect its workers in the event of a power failure or blackout, a Philadelphia plant has outlined the doorway and ramp shown below with a phosphorescent paint. Note that the workers also wear luminous arm bands. A luminous metallic powder is also being used to detect manufacturing defects. Dusted on the magnetized coil shown at the right, it glows under black light to reveal a flaw down the full length of the coil







## *What do You Know About*

**Nature gave you a marvelous pair of hearing instruments . . . Modern tests show how they are best protected and used.**

**Drawings by JOHN GILMORE**

**S**AY "Good morning" to the first 15 people you meet, and at least one of them probably will have to guess at what you said. Or, if all of them hear you clearly, you may be the one in 15 who has defective hearing. That, according to a recent estimate made by the New York League for the Hard of Hearing, is the average ratio of deafness, whole or partial, in the United

States. Some people are born deaf, but most defective hearing is acquired as a result of disease, injury, or neglect. Economic as well as personal and social problems are a result; more than 40 percent of those with acquired deafness have had to change their occupations.

Fundamentally, the human ear is a simple mechanism and shouldn't be hard to take care of. It is a funnel which catches sound waves, converts them into nervous impulses, and sends them to the brain to be sorted out and classified. Man has taken the same basic principles and made the relatively simple telephone transmitter, which catches sound waves and converts them into fluctuating electrical impulses. In detail, however, the ear is a complicated set of physical gadgets, like most of nature's machines.

There are three major parts: the outer ear, the funnel which catches the sound; the middle ear, which transmits the sound; and the inner ear, where the auditory nerve picks up the vibrations and sends them along to the brain. The middle and inner ears are the most complicated, the most easily injured, and the hardest to repair.

The outer ear consists of the familiar flap of cartilage sometimes called the "shell," and the auditory canal which extends inward to the eardrum. The eardrum is a membrane that stretches across the auditory canal and separates the outer from the middle ear. Another name for the eardrum is the tympanic membrane, and it acts like the head of a drum, vibrating when sound waves strike it as a drumhead vibrates under a drumstick.

On the far side of the eardrum, in the middle ear, are three small bones called ossicles. The "hammer" rests on the eardrum and responds to the sound vibrations, which it in turn taps out on the "anvil." The "anvil" passes them along to the "stirrup," which fits into an opening in the inner ear and touches the cochlea, the apparatus which changes sound vibrations into nervous impulses.

The cochlea is a tiny organ, coiled like a snail shell and filled with a thick fluid. On its inner walls are sensitive, hairlike


terminals of the auditory nerve. When the sound waves are tapped out on one end of the cochlea by the "stirrup" bone, the fluid inside is set to vibrating, the nerve terminals are agitated, and the message is started along the auditory nerve toward the brain.

The cavity of the inner ear, where the cochlea lies, is in one of the hardest bones in the body, a fact important in the use of one type of hearing aid. Also in that cavity are the "balancers," three little tubes coiled into connected semicircles and set at right angles to each other so that they look something like a distorted pretzel. They have nothing to do with the sense of hearing; they are the center of the sense of equilibrium—the body's leveling instrument. Head colds and ear infections sometimes disturb them and cause dizzy spells. When a cold affects the sense of hearing, it is because the Eustachian tube, which connects the middle ear with the throat, is swollen partly shut. The Eustachian tube's function is to equalize the air pressure on the two sides of the eardrum.

A serious infection in the aural passage, or even the rupturing of the eardrum, can be caused by sticking a match stick, hairpin, or the corner of a towel into the ear to re-

Below, left, is seen a cross section of the cochlea, the receiving instrument of the inner ear. The fluid with which the canals are filled is set in motion by sound waves. At right, an enlarged view of one section of a canal. The hairlike antennae of the auditory nerve pick up the vibrations of the fluid and transmit them to the brain. In the lining of the cochlea there are said to be more than 23,000 tiny nerve cells

## Your Ears?





move water, wax, insects, or other foreign matter. In such cases only a few drops of warm oil should be used. If that doesn't remove the object, then a physician should be consulted promptly.

Treatment of impaired hearing is in many cases both simple and effective. Far more trouble is caused by refusing to admit that one's hearing is not up to par, or by trying to conceal the fact, than by poor hearing itself. The person who tries to answer a question or follow an order only half heard may say or do something inexcusably stupid in the attempt to "cover up." More jobs are lost by trying to conceal poor hearing than by the difficulty itself.

Thanks to scientific research, partial deafness can now be repaired almost as easily as nearsightedness. The chief problem is to find the trouble—and to get the patient to acknowledge it to himself.

Tests in schools have been especially effective in spotting deafness at a time when medical aid can be of particular help. Many children who seem to be backward or stupid are found to be only hard of hearing, and treatment often brings them up to par in their studies.

The old-fashioned hearing tests, based on voice tones or the tick of a watch, served in their day but gave no accurate measure of the degree of deafness or the reason for it. Now the audiometer is used, an instrument which Dr. Fred W. Kranz, physicist and research director of the Sonotone Corporation, calls the first accurate device for measuring hearing. With the audiometer, standards of normal hearing have been established, and tests with it show not only the degree of hearing loss in any individual but whether

the source of the affliction is in the middle or the inner ear.


Once the source and degree of deafness are ascertained, various kinds of hearing aids can be prescribed. The Sonotone Research Laboratories, for instance, have developed two types of electrical hearing aids, one for air conduction, the other for bone conduction. Both work on the same principle as the telephone: the transmitter picks up the sound waves, changes them to electrical

impulses, and sends them to a receiver which changes them back to sound waves or vibrations where the defective ear can best make use of them. The air-conduction type of hearing aid sends the receiver's sounds directly into the ear passage. The bone-conduction type, which is worn behind the ear rather than in it, sends sound vibrations through the bone directly to the cochlea in the inner ear.

Recently, radio principles have been adapted for use in hearing aids.


The transmitter in this type of instrument uses a Rochelle crystal instead of carbon grains. When the crystal is activated by the vibration of a diaphragm, the strength of the electrical current through the crystal is varied and the sound waves are converted into electrical impulses. Miniature vacuum tubes are used for amplification in the receiver. The result is very different, both in appearance and effectiveness, from the ear trumpet of grandfather's day.

With all these advances in understanding and treatment of hearing defects, there is seldom any excuse for a person who suffers from partial deafness. In the first place, you should know enough about your hearing equipment to give it reasonable care. If it fails naturally, give it scientific aid.



### *Helpful Earful*


- NEVER** box a child's ears, or hit him on the side of the head.
- NEVER** try to remove objects that a child has put into his ear. Take him to a physician.
- NEVER** clean the ears with a hard or pointed object.
- NEVER** dry water-filled ears with a towel. Tilt the head and let them drain.
- NEVER** fish for an insect that has got into the ear. Go to a physician or pour ear drops or warm oil into ear until insect drains out.



# THIS SHOE SHOULD FIT

Even to the partly deaf, some sounds are distorted and unintelligible, while others are wholly unheard. The diagram above shows how unevenly a typical sentence is heard by a deafened ear.

Below, two important functions of hearing aids are shown: distorted frequency waves must be corrected for clearness, and every sound must be amplified to suit the requirements of the user.








**HOW 10 TONS OF BOMBS** can be carried by a Flying Fortress is shown strikingly in this view of one of the big Boeing bombers on a practice flight near Mount Rainier in the State of Washington. Outside racks

with forklike fingers hold the extra bombs on the bottom of the fuselage near the landing wheels. This supplementary arrangement permits the carrying of an unusually heavy load for limited-range operations.


**SHREDDED AND NEATLY BALED** in 200-pound packages, tin cans, automobile bodies, old stoves, and all kinds of scrap iron are made ready for reprocessing in a huge machine devised by Clarence M. Gregg, president of the Los Angeles By-Products Company. Chrome molybdenum hammers or

cutters on the outside of a drum revolve at 1,800 r.p.m. to break up the pieces into tiny bits, which ride through a magnetic separator that deposits dirt and nonferrous metal in one bin and iron in another. Automatic balers then bind the iron scrap into bales of uniform density.




Scrap is fed into this giant machine on a conveyor, goes into a five-ton shredder, and comes out in neat bales.





**A BOMBPROOF LABORATORY** for processing photographic material at the front has been designed by the 165th Signal Photographic Company at Fort Sam Houston, Tex. As shown in the drawing by military artist Swanlund, the underground darkroom provides a working space of about six by 12 feet and is entered through a protective right-angle passageway. One of its features is a ceiling rack in which a camera can be



placed as demonstrated by Sergeant Smoody in the photograph above for use in making enlargements. Heavy sandbagging guards against damage by bombs and shells, so that work can be carried on under fire.



**LANDING GEARS** that stick need no longer threaten pilots or their planes. Engineers of Walter Kidde & Co. have developed a carbon-dioxide power unit which, in an emergency, can be used to lower landing gear or open and close bomb-bay doors. Because of the high compression of carbon dioxide, a two-pound cylinder is sufficient to operate even the heaviest equipment.

**GIANT ENCLOSED MOTORS**, such as the one shown below, are being built by General Electric for tankers of the U. S. Maritime Commission. Each motor has a sheet-iron cover as a protection against dirt, and is equipped with an air-recirculation system. Cool air entering at the bottom of the motor rises as it becomes heated and is then piped off into a cooling blower, which carries it back to the bottom of the motor.








**ALNICO MAGNETS** set in the bases of the standards are simplifying the setting up of experimental optical systems. Adhering to a metal table top or wall, the magnets hold the system in position and prevent any disarrangement even when adjustments are made. This use of alnico was devised by Norman Barnes of General Electric.

Although standards will adhere firmly to any steel surface, they can be easily moved when necessary. At right, a bottom view of a standard, showing an alnico magnet set in its base




**NEW GASOLINE OVENS** are being used by the U. S. Army Quartermaster Corps for baking in the field. Shown at right are eight of these two-chamber ovens, which can do the baking for 10,000 men. Tended by a bakery platoon of 36 men, and using 3,600 pounds of flour, this battery of ovens can turn out 5,000 pounds of bread in 24 hours. Below: fire-control units.



**A BRAKE TESTER** for airplanes has been developed by the Safety Equipment Co., of South Bend, Ind. The device cradles the plane's rubber tires between rollers that provide traction equal to that of dry concrete. When the brakes are applied, the force needed to turn the wheels is registered on a dial, which gauges the braking action.


*POPULAR SCIENCE*

**AMPHIBIOUS FLOATS**, attached experimentally to the Army Air Forces' C-47, may make this big cargo transport an efficient seaplane as well as a land plane. Tried out at Wright Field, Dayton, Ohio, the new floats enabled the plane to alight on water, taxi to shore, and climb on land under its own power. This may prove particularly useful in rescues of flyers on coral reefs in the Pacific. Further experimentation is being carried out by the AAF in the design and use of the floats.




**RUBBER-CLEATED SOLES AND HEELS** are being put on ski boots for our soldiers, who may be using them soon to cross the Alps for a closer crack at Hitler. Replacing the steel cleats and leather worn by mountain troops in World War I, this footwear was developed by Adams Carter, famous mountain climber and now a research specialist for the Quartermaster General, and experts of the Goodyear Tire & Rubber Company. The design, an improvement on a Swiss-Italian shoe, is light, warm, waterproof, and silent on flinty surfaces.

**CLEAR PLASTIC DOMES** are being mounted on open antiaircraft observation posts along the Atlantic seaboard to keep sky watchers dry and comfortable. Built of Lumarith, made by the Cellanese Celluloid Corporation, of New York, the domes offer shelter from rain, sleet, and snow without cutting visibility, and also improve communication by screening out noise.









Hauling a landing barge ashore on Attu with the help of a tractor and an odd but efficient movable dry dock called a "geeheebee"

**PLASTIC EAR STOPPERS** are now molded from Plexiglas to fit the ear canal. Designed by Arthur F. Farman, an employee at McClellan Field in California, they are manufactured by Rohm & Haas Company, of Philadelphia, Pa.



**TWIN THREADS** are a new idea for screws for wood, plastic, and combination assemblies. These screws, made by the Blake & Johnson Company, of Waterville, Conn., have straight sides, relieved shank diameter, and a single balanced point.




**TWO MEN OPERATING** this grid machine, developed by Lyle F. Pierce, chief of master layouts at the Boeing plant in Seattle, can make in one day a crosshatched background for full-scale mechanical drawings that once took six months. The machine scribes simultaneously 12 parallel lines 100 inches long and accurate to .005 inch.

Backgrounds thus made on painted steel are joined together, sometimes into sheets 20 by 30 feet, for bases on which full-size drawings are put for parts of Boeing planes.




**WATER JETS** that can peel the bark off giant logs more swiftly than knives are the basis of a hydraulic barking machine developed by the Weyerhaeuser Timber Co. of Everett, Wash. Twin nozzles on a moving carriage force streams of water up against a rotating log at a pressure of 14,000 pounds per square inch, producing erosion of bark and cambium. Steel arms steady the log. Six foot trunks can be stripped in a few seconds.



**"STICKY" BOMBS** that are thrown by hand and glue themselves against their targets have now been revealed as one of the secret weapons the British Eighth Army used so successfully in the African campaign. The bomb consists primarily of a glass flask filled with a short handle and filled with an explosive. Wrapped around the flask is a light-fitting wooden jacket that has been treated with a special adhesive. When hurled against a tank, the bomb fastens itself there leechlike and then explodes. For protection before it is used, the bomb is fitted with a finger ring, fastening held together by a narrow metal band wrapped around the neck of the bomb, as shown at the right.







Automatic computing sights now make our American bomber one of the sky's most deadly fighters

## *Why our aerial gunners are* **Outshooting the Axis**

By HAL BORLAND

Drawings by FRANK TINSLEY


**A**MERICA'S big bombers, which roared to fame as tough ships that could "lay eggs in a basket" from 20,000 feet and take terrific punishment, are even more famous now as killers of the sky. On one bombing mission, not long ago, a flight of them knocked out 74 Nazi fighters. Good to begin with, they are now superbly lethal.

How come? The answer is gunnery—gunnery that is more than weapons, more than power turrets, more than competent gunners. It is all these, plus an automatic computing gunsight that makes supermen of the bombers' gun crews. This automatic sight has given our big ships a fire-power

"reach" of more than 1,000 yards, or twice the effective range of Axis aerial guns.


Until recently this automatic sight was a secret weapon. Its details are still secret, but the veil has been lifted enough to show what it can do and, in general, how it does it. Basically, it is a compact machine that automatically calculates speed, drift, windage, trajectory, and range, and compensates for all these factors as it aims the guns where the bullets will do the most damage to an enemy plane. It does all this with a minimum of human effort, and reduces human error to a minor factor by eliminating virtually all guesswork. And, lastly, it is so simple to operate that three weeks' training with it can make an expert gunner out of a novice.

# LEAD—AND THE VARIOUS FACTORS THAT AFFECT IT




**LEADING** consists of aiming ahead of a moving target so that the bullet and target will arrive at the same point simultaneously. In sketch above, the hunter will miss his target because the duck will have moved ahead during the flight of the bullet.


**WINDAGE.** As the bullets leave the plane's guns, the wind rushing past the plane has a tendency to deflect them toward the tail. The degree to which this force of wind will change the direction of the bullets' flight is determined by the speed at which the airplane is flying.



The farther a bullet travels, the more gravity makes it drop. To get the range, therefore, gun muzzle must be elevated.



When a bullet is fired, it spins to the right, which has a tendency to make it "jump," or veer off, in that direction.



Any duck hunter or trapshooter has a rough idea of the primary problems of an aerial gunner. First of all, to hit a moving target he must "lead" it, that is, shoot far enough ahead of it to allow for its speed. Then he must take into account the range of his gun, the effect of the wind, and the characteristics of the shell he is shooting.

The duck hunter's target, however, seldom flies more than 60 miles an hour. The aerial gunner's target travels more than six times as fast. And while the duck hunter shoots from a stationary position, the aerial gunner is in a bucking, twisting ship traveling at least 200 miles an hour. The duck hunter uses a shell whose hundreds of tiny pellets are deadly over a three-foot circle

at 50 yards. The aerial gunner's weapon fires only one bullet at a time. To approximate the aerial gunner's task, the duck hunter would have to do his wing shooting with an automatic rifle while sitting in the rumble seat of a car going down a country road at 100 miles an hour. Accurate shooting from a big bomber with manually operated weapons and ordinary sights is phenomenal. Man simply is not physically equipped to do it.

Of his equipment, his eyes are probably nearest to the necessary perfection. When a bomber is flying at 200 miles an hour and an oncoming pursuit ship is moving at 400 miles an hour, the combined speed of approach is 300 yards a second, which is not





**SIGHT AND TURRET.** At the left, an officer carefully examines one of the automatic computing sights before it is installed between a turret's two guns. Above, a gunner grins as he crawls into the belly turret of a big bomber

very far from the speed of sound. Yet a gunner's eye can follow a pursuit ship traveling at that terrific speed. In a wink of the eye, however, the target will have moved about 25 yards. And we know from optical research that persistence of vision makes the eye incapable of registering an abrupt change lasting less than  $1/32$  of a second. The eye is fallible to a degree not yet fully determined; but, on the whole, it is good enough for the aerial gunner's job.

A man's physical reflexes are less dependable. But because of their importance, the Air Forces insist on high standards. Impulses from the eye or ear must be obeyed by the muscles without perceptible delay. Tests of thousands of automobile drivers have shown an average reaction lag of .44 second. Yet in half that time an aerial gunner's target may move as much as 66 yards. A trigger finger even a tenth of a second late in obeying the eye's order to fire would put the burst of fire completely off the target, even if no other factors were involved.

Mental processes are another factor. The best mathematical mind isn't fast enough to solve, at a given instant, a problem dealing with air speeds of hundreds of yards a second, particularly when such complex matters as windage, drift, trajectory, and range are also involved. That is why the guns in a fighter plane are in fixed mounts; they can be aimed by pointing the plane itself, and no complicated calculations are necessary.

Add to the gunner's problems the fact that high altitudes slow up both physical reflexes and mental processes, and then the situation becomes really complicated. Oxygen helps to compensate for the altitude, but low temperatures—it gets down as far as 45 below zero F. at 25,000 to 30,000 feet also tend to retard the reflexes.


The automatic computing sight was de-

veloped to minimize all these human factors. It is a mechanical Einstein that literally computes half a dozen complex and constantly changing problems, and delivers the correct answer at any desired instant. Although the gunner sights at the target itself, the computer aims the guns at the point where the target will be when they go into action.

Typical of several models is the sight developed by the Sperry Gyroscope Company for use with a hydraulically driven turret. Looking like an ordinary small black box, it is mounted between the turret's two guns. At one end of the box are knobs similar to the tuning knobs on a radio. On its top is a reflecting glass—the scanning sight with two parallel lines of light which can be spread apart or drawn together by manual control or a foot pedal. These light lines are the governors of the range finder.

Before the take-off, the computer is set for the type of ammunition used and windage jump, or deflection to the right caused by the spin of the bullet. After the take-off, another adjustment is made to compensate for the plane's speed. A power switch takes the manual labor out of the gunner's job by making the turret swing automatically in accordance with the "orders" from the sight.


The gunner has a pair of handle bars with firing buttons at his finger tips. When he spots an enemy plane approaching, he identifies it by type and sets a master knob on the sight at the plane's approximate wing spread. A Messerschmitt, for example, with a wing spread of about 33 feet, will call for a setting at that figure. Swinging the turret until the oncoming target is framed in his reflecting glass, the gunner brings the light lines to their minimum spread, which is governed by the master knob setting when he identified the enemy plane. Since



**ANGULAR RATE**, measured in degrees per second, is the speed at which the turret must be rotated in order to keep the guns on target

**LEAD IS COMPUTED** by multiplying the angular rate by the time it will take the bullet to reach a given range. To this figure must be added the distance that the bullet will be deflected by windage as well as the distance that its spinning through the air will cause it to "jump" to the right. This is all done by the computer in a split second. All the gunner has to do is to track the plane and press the firing buttons

## HOW COMPUTER GETS THE INFORMATION THAT IT NEEDS




**GUNS ARE AUTOMATICALLY AIMED AT POINT WHERE BULLETS AND TARGET WILL MEET (X)**

The speed at which gunner rotates turret in order to track plane gives automatic gunsight angular rate. Distance of plane (see below) gives sight the

time of bullet's flight. With correction previously set for windage and "jump," gunsight now has all information necessary for computing lead

## SCANNING SIGHT TELLS THE DISTANCE OF ENEMY PLANE



**1** As soon as he identifies the enemy plane, the gunner sets the master knob for the plane's approximate wing spread. He then brings the reticules as close together as setting will allow

**2** When the approaching plane fills the space between the lines, the gunner knows that it is within effective range, and that he can start tracking and pressing his firing buttons

**3** As the plane grows larger in the sight, the gunner moves the lines apart so that they always just enclose the plane. In this way he keeps gunsight "informed" of the plane's distance

the over-all dimensions of a fighter are approximately the same from any angle, he has only to keep the plane between the light lines, and as soon as the target fills the space between the lines it is within range. At that point, the gunner can begin effective fire, and can continue it as long as the light lines enclose the approaching plane's extremities.

Everything has been compensated for automatically—range, speed, windage, deflection, and angular rate. All he has to do is track the plane, and press the firing buttons.

All American medium and heavy bombers are now equipped with automatic computing sights and power turrets of one type or another. This accounts for the lopsided scores when bombers go out and run into fighter opposition. Neither the Japs nor the Germans have power turrets or computing sights, and, considering the development necessary to bring them to perfection and the precision work needed to manufacture them, it is unlikely that the Axis will produce such a sight unless the war drags on considerably longer than now seems likely.



# Make Hay While the Sun SETS!



DRY WEIGHT



Alfalfa cut in morning and late afternoon shows little difference until it undergoes chemical tests. Then the afternoon-cut fodder is found to contain more dry weight, sugar, and starch

**F**ARMERS who cut alfalfa, grass, and corn in the late afternoon instead of in the early morning may be storing in barns and silos hundreds of pounds more actual starch and sugars for their livestock. This is the conclusion of Prof. O. F. Curtis, of the New York State College of Agriculture, Cornell University, who is supervising the study of the food contents of forage crops cut at different times of the day. According to these tests, the carbohydrate content is lowest in the early morning and reaches its peak in late afternoon.

Tests with alfalfa showed that late-afternoon cutting produced an average of 90 pounds, or 90 percent, more starch and sugar to the acre, and 500 pounds, or 20 percent, more dry matter, than plots harvested in the morning. Afternoon-cut grass gained 50 percent more sugar.


By photosynthesis, a miracle of transformation not yet clearly understood, green plants take carbon dioxide from the air and water from the soil and, under the action of sunlight, change them into starch and sugar. This has long been known, but it is a revelation that such a great proportion of starch and sugar is lost during the night, apparently consumed in respiration and changed into cellulose.—KENNETH M. SWEZEY.

SUGAR

STARCH



# River Takes a Detour To Bare Iron-Ore Bed



A 1,300-foot rock tunnel drilled low into Finlayson Lake is draining it slowly so as not to flood the lower countryside

WHEN TUNNEL LOWERS LEVEL OF FINLAYSON LAKE 50 FEET, CUT WILL BE MADE IN RIDGE

TUNNEL TO BOTTOM OF FINLAYSON LAKE WILL GRADUALLY REDUCE ITS LEVEL

DAM TO BE MADE HIGHER

IRON ORE IS TO BE MINED AFTER LAKE HAS BEEN PUMPED DRY AND 40 FEET OF CLAY AND ROCK REMOVED

STEEPROCK LAKE




With a diamond drill, engineers probed 40 feet below lake bottom to find the ore first detected by electrical instruments

**B**IGGEST drainage job in North American mining history is uncovering iron-ore deposits under Canada's Steeprock Lake, into which flows the Seine River. By raising the dam at the lake's inlet, making cuts

between the higher Marmion and Finlayson lakes, and opening a drain tunnel into the bottom of the latter, the Seine has been directed into a new course. Pumps are now emptying Steeprock Lake.



# HOW INDUCTION FURNACES ARE MAKING IT



The Ohio Crankshaft Co.

These 500-pound-bomb casings are being induction-heated prior to the process of tail spinning. Note the absence of handling tongs, made possible by the unusual localization in this type of heating. The ends of these casings can be heated to 2,000 degrees F. in just about three minutes and 15 seconds.

By JACK O'BRINE

**W**AR industry is "cooking" with electricity these days. At almost any plant where the application of heat enters into metal processing, you'll find an induction furnace doing the job. Its magic coil is taking the place of fire to produce record-breaking quantities of fighting equipment. Improved cannon, armor-piercing shells, parts for tanks, planes, and submarines, and a great miscellany of war tools come magically from it.

On the civilian front, too, induction heating works like a Turk. It's far more useful than most of us realize. Nearly every time we shave with a sharp razor blade, get fine music from a long-lasting phonograph needle, plug in our radio, or do an exceptional job in our home workshop with good tools, we can thank an induction furnace. For, more than likely, it was used in melting, forging, brazing, case-hardening, welding, or soldering those items so perfectly.


This metallurgical master worker dates its success story from the last war. Edwin F. Northrup devised it as a means of speeding production. Though too late for use then, its debut attracted wide attention among American industrialists. Before 1942 our industry had installed induction heating equipment using 175,000,000 watts, and in that year war plants accounted for more in-

stallations than in any previous three-year period.

Northrup's basic principle still holds good, although furnaces themselves have undergone many refinements to attain production wizardry. It's the same principle that is used in an ordinary transformer. In fact, if you strip off the manifold mechanical gadgets from an induction furnace, you have little more than an insulated box built around a transformer whose core has been removed to make room for whatever metal you want to heat. Heating occurs almost instantaneously when you send an electric current through the transformer coil surrounding the metal to be treated. The induced voltage, encountering resistance in the metal, produces a power loss which appears as heat. By varying the frequency and strength of the current and the size of the coils, you can control the depth of heat penetration, the area affected by the heat, and the temperature. Just push a few buttons and you can give the metal any kind of treatment desired.

Engineers have compared induction heat with the radiant heat thrown off by the sun. When the sun's rays pass through space, there is slight loss of energy, and thus negligible heat is produced. But when they strike a dark body, its surface is heated. In like manner, high-frequency magnetic waves from the coil pass through all insulating ma-


# HOT FOR THE AXIS



THIS IS THE PRINCIPLE OF INDUCTION HEATING

## HOW THE PRINCIPLE IS APPLIED

Hundreds of electric heat treating furnaces, such as those shown below, are being used to harden precision parts required in planes and tanks. Made by Westinghouse these furnaces do their work at temperatures ranging between 1 500 and 2 000 degrees F. A gas mixture known as Endogas is introduced into the heating chamber to protect the work from scaling or softening





terials without dissipating their energies, yet create heat when they strike a metal body. Nonconducting materials which enter the magnetic field—intervening air, for example, or parts of the human body—are not affected. This explains why a man can place his hand within an induction furnace without suffering the slightest injury, though a piece of metal put there will soon be white-hot.

Induction furnaces now being used in the manufacture of so many of our weapons of war require an alternating current of high frequency. In that type of current, the magnetic lines of force change direction rapidly, threading the metal within the coil and setting up the current there that develops the heat. Direct current will not do the job.

In many installations, tubing is used instead of wire in the inductor coil. This is possible because of the "skin effect" characteristic of the alternating current, a tendency of the current to concentrate on the surface of the conductor, especially at high frequencies. Crowding of the current on the surface enables the induction furnace to attain remarkable results in hardening metals and gives it a "stirring effect" extremely valuable in melting operations. Because of it, shallow-layer objects, such as shell casings and crankshafts, can be heated so quickly that underlying portions are not affected, and alloys of homogeneous nature can be formed through thorough mixing.

Continuous furnaces—that is, relays of furnaces—have now been designed to meet needs in specialized industries. They are equipped with conveyors or mechanical carrying devices and have accurate time and temperature controls. Furnace ratings, depending on the particular operation, run anywhere from a few kilowatts to as many as 1,200 kilowatts. In some cases, engineers have designed ingenious mechanisms to handle materials entirely automatically.

Perfecting of protective atmospheres for use in the heating process is another step forward. By means of gases applied so as to surround metal parts, the operators are now able to prevent oxidation and decarbonization. The open-fire method of heat-treating never has been without possibility of distortion and chemical alteration of the metal, requiring lengthy and expensive sand-blasting, pickling, machining, and grinding operations after the treatment. Faster, better-controlled heating provided by the induction furnace saves time and money, since there are no blemishes or marring results. Equipment now available maintains a protective atmosphere in the furnace.

Induction heat often figures in the headlines these days from war-production lines. One of the most spectacular advances in gunsmithing—the centrifugal casting of gun

barrels—is a direct outgrowth of research in this field. Traditionally, gun barrels have been fashioned laboriously from ingots, forged, heat-treated by conventional methods, and then machined into shape. But ordnance experts hit upon the idea of simplifying the process with the aid of electric furnaces. Widely used today is a process in which ingredients which make up steel for the barrel are melted in an induction furnace, where alloying is rapid and melting losses low. Metal is carried in the furnace itself, which doubles as a giant ladle, and is poured into a horizontally rotating mold. The mold is turned until the casting solidifies. Now, when you remove the barrel from the casting machine, you find it easy to finish.



Centrifugal forces have done the lion's share of the work. As the rotating occurs, the barrel has taken shape, not as a solid ingot requiring expensive hollow-forging or machining operations, but as one already having a hole through the center. Moreover, any slag particles or impurities present in the mold, being lighter than the steel through which they are dispersed, float to the bore. You can quickly get rid of them in the machining process.

Induction heating is particularly well suited for forming, brazing, and hardening operations in making projectiles. Its chief advantages are speed and uniformity of heating, ease in controlling heat to specific patterns, the metal's freedom from surface scale after treatment, and greatly improved working conditions for operators. Another consideration recognized by farsighted industrialists is the fact that induction-heating equipment can be turned to peacetime use without investment loss. Indeed, post-war plans have inspired many industrialists to put in electric furnaces. For instance, while a frequency of 1,000 cycles is sufficient for heating many weapons, most manufacturers have installed 2,000-cycle furnaces because they can be more readily converted to automotive work after the war.

Great is the variety of tasks that induction furnaces perform. They are used to expand metal parts, or to shrink those parts for fitting; they treat the nichrome (nickel chromium) wire used in spark plugs, tune the tungsten contact points found in virtually all gas motors. Alnico magnet steel used in radio and meter parts is almost exclusively a product of induction heating. In radio and radio-control equipment, induction heating is used to drive off occluded gases from metal parts in sealing vacuum tubes. It's in nearly all Navy yards, Army ordnance plants, arsenals, and war plants where special alloys and castings are made. Every day they find new uses for this versatile furnace to put more heat on the Axis.




An induction machine heats the corner of a tool shank on which a tungsten-carbide tip is to be brazed




Induction heating can harden the teeth of a sprocket—and leave remainder unaffected

## INDUCTION PUTS THE HEAT JUST WHERE IT IS NEEDED



Ajax Electrotherm Corp.

In compounding alloys, an electric furnace's electromagnetic forces automatically "stir" the ingredients, and thus aid the mixing. Melting is speeded up by concentrating the current into small charges



Here is another instance of how induction heating can restrict its effect to a given area. The crankshaft above is about to get a heat treatment that will harden only its bearing surfaces

An extra-long crankshaft is shown below being hardened in a machine that carries an inductor block for each bearing. By varying the size of the coils, as well as the power and frequency of the current (which, for all induction work, must be alternating), both the depth and degree of hardening can be accurately controlled





# What You Should Know About Propellers for Our Fighting

The modern aircraft propeller is an amazingly ingenious mechanism designed to get maximum efficiency of engine and plane.

By JAMES L. H. PECK  
Drawings by STEWART ROUSE


**A**FTER a recent battle, American forces captured a German soldier who kept pointing upward and babbling about "big whirling swords." Some time later, doctors discovered the cause of his hallucinations. Lightning and Warhawk fighters had run interference for the Yank advance by carrying out one of their blistering strafing attacks at tree-top altitude. The Nazi had somehow escaped from his flaming tank and

survived the assault; but, in his fear, he had psychologically identified the sunlit, spinning propeller blades of the low-sweeping planes as whirling swords.

Indeed, in a more practical manner, the whirling prop blades of our warplanes do symbolize their deadliness. The propellers that pull our fighters and bombers—and those of our allies—through the skies over half a dozen war theaters are more than a little responsible for the superb performance that is affording American-made craft the air superiority they now enjoy. The prop is as much a part of the plane's power plant as is the engine. It translates the engine's power output into the "thrust" necessary for sustained flight.

If we consider the propeller as a screw working its way through the air and pulling the plane along—or pushing it along, if it is mounted aft of the engine, as in the case of


## A PROPELLER BLADE IS A SPINNING WING. HERE'S WHAT



Essentially a set of spinning airfoils, a propeller's blades are shaped like a plane's wings. However, since the tips travel at a higher speed than parts nearer the hub, the blade angle must be varied progressively, decreasing from the shank toward the tip.




A wing gets its lift from the partial vacuum created above it, and from pressure below. Corresponding forces give a propeller its pull.



Slip stream of a propeller is the equivalent of the downwash from a wing. It takes the form of a cork-screw spiral of air which upsets steering equilibrium.


# Planes

our Bell Airacuda and some of the new pusher-type fighters—just as a steel screw bores its way through a piece of wood, the principle of propulsion is reduced to its simplest terms. But, unlike the screw, which advances by pushing the rear face of its thread against the fibers of the wood, the prop advances by creating just ahead of its whirling blades an area of suction into which they are drawn. The propeller blades are shaped exactly like the wing section of a plane and act on the same principle. The prop is, to all intents



Feathering keeps a dead engine from being damaged by "windmilling"

## HAPPENS WHEN IT REVOLVES



The faster the propeller turns, the more thrust it produces, until its tip speed approaches the velocity of sound (1,100 feet per second), where there is a sudden and overwhelming increase in drag. Pressure waves set up at the leading edge cannot get out of the way of the moving blade and must be dragged along. This phenomenon puts limits on length of blades and on propeller speed

and purposes, a set of spinning airfoils.

Just as the airplane wing must move forward fast to maintain its lifting properties, the propeller must rotate swiftly in order to provide thrust. The faster it turns, the more thrust results—up to a certain point. And, just as the wing is tilted upward slightly in order to deflect the air downward (this setting is called "angle of attack"), the prop's blades are twisted so as to deflect the air rearward. This twist, or "blade angle," enables the blades to meet the air at an angle that is most favorable for thrusting efficiency.

In rotating, the tips of the propeller must travel around their greater radius within the same time that the prop hub completes a revolution. The tips, therefore, travel many times faster than the center of the prop. For this reason, the blades are not straight like a wing but twisted so as to permit the blades to meet the air at the optimum angle along the entire length of the propeller. The twist is most noticeable in the inner half of the blade. Within a foot or so of the hub, the blade merges from its flat shape into a round, thick section that provides no thrust whatsoever.

The very same laws of physics which permit a wing to lift or a propeller to thrust have decreed that we must pay a price for these aeronautical services. The steepest of these prices is drag. It is with drag that the propeller must struggle constantly as it pulls or pushes the plane through the air. Drag acts on the prop in the same way as on the wing, only more so because of the high speeds at which the prop rotates. Drag may be diminished by giving the wing section or prop blade a more streamlined shape. The new laminar-flow wing section—used




## GIVING PROP MORE POWER

With the use of more powerful engines, propellers must be adapted to absorb that power. The drawings at right show how engineers solve the problem, increasing blade surface while holding down length

## MATING PROP TO ENGINE


Another difficulty arises from the fact that props and engines have different speeds for maximum efficiency. The answer to this is a reduction gear that enables the prop to turn at lower speed than engine



**A** EARLY TYPE OF PROPELLER. IT ABSORBS THE POWER OF AN ENGINE OF ABOUT 100 H.P.




**B** WITH THESE CHANGES IT TAKES THE POWER OF AN ENGINE OF ABOUT 150 H.P.



**C** WITH THE POWER THAT CAN BE PUT IN IT

## PROPELLERS ON SINGLE ENGINES




**D** THE ABOVE TYPE OF PROPELLER AS USED ON A SINGLE ENGINE. IT TAKES THE POWER OF AN ENGINE OF ABOUT 150 H.P.



**E** THE ABOVE TYPE OF PROPELLER AS USED ON A SINGLE ENGINE. IT TAKES THE POWER OF AN ENGINE OF ABOUT 200 H.P.

## PROPULSION PROPELLERS ON COAXIAL SHAFT



**PLANETARY REDUCTION UNIT**


on the superb North American Mustang fighter-bomber and other American craft—has reduced drag almost 67 percent, and this same type of airfoil section is used by some of our propeller manufacturers.

Greater efficiency may also be achieved by increasing the area of the blade to provide more thrust, but it is here that the engineers encounter trouble. The diameter of the propellers is limited by three considerations: on single-engined craft, the prop must be short enough to allow clearance when the ship is on the ground on level keel. On multiengined planes, ground clearance is not such an important factor because these ships are larger and sit higher, but using bigger props means moving the engines farther apart (and the outboard engines farther out on the wing). When these difficulties are overcome, there remains still another: the larger the propeller's diameter, the higher the tip speed. When the tips of the prop reach the speed of sound—1,100 feet per second—they become literally barnacled with a peculiar and exaggerated drag condition called a "shock wave." There are limitations on the width of the blades, too. As the blade is widened, it must be made heavier for structural reasons, and this results in greater drag and weight. Compromise is necessary for other reasons which have to do with more involved aerodynamic laws, and the product is the neatly tapered, knifelike propeller blade we see on today's warplanes and airliners.

Notwithstanding these difficulties, the propeller is just about the most efficient part of the airplane. How it got that way is somewhat of a story. Some of the earlier props



## VARIABLE-PITCH PROPELLER HAS WIDE RANGE OF EFFICIENCY




**LOW PITCH ANGLE**  
FOR TAKE-OFF AND CLIMB  
PROPELLER ADVANCES SHORT  
DISTANCE EACH TURN BUT  
ALLOWS HIGH ENGINE SPEED  
AND POWER

**MEDIUM PITCH ANGLE**  
FOR CRUISING CONDITIONS PROPELLER  
ADVANCES FARTHER PER TURN AND  
ENGINE OPERATES AT ITS SPEED  
OF GREATEST EFFICIENCY

**HIGH PITCH ANGLE**  
FOR HIGH-SPEED LEVEL FLIGHT.  
PROPELLER ADVANCES A GREAT  
DISTANCE AT EACH REVOLUTION


### FEATHERED PROPELLER

PROPELLER BLADES  
OF DEAD ENGINE  
HAVE BEEN  
ROTATED AT THE  
ROOTS UNTIL THEY  
HAVE NO PITCH  
ANGLE, SO THEY  
KNIFE THROUGH  
THE AIR WITH  
LITTLE RESISTANCE  
AND NO TENDENCY  
TO "WINDMILL"



PROPELLER  
NOT TURNING  
(ENGINE DEAD)


### REVERSED PITCH




PROPELLER  
BEING TURNED  
BY ENGINE

HERE THE  
PITCH ANGLE  
HAS BEEN  
REVERSED  
SO THAT PROPELLER  
PUSHES AGAINST AIR,  
ACTING AS A POWERFUL  
BRAKE ON AIRPLANE'S  
FORWARD SPEED

## HOW PITCH OF PROPELLER BLADES IS VARIED IN FLIGHT




**HYDRAULIC.** In this Hamilton Standard Hydro-matic hub mechanism, a piston moved by hydraulic pressure operates gearing and cams to increase or decrease the pitch of the blades. A governor maintains pressure balance for constant-speed operation



**ELECTRIC** The Curtiss Electric uses a motor to turn the blades through a set of planetary and bevel gears. A brake on the motor locks the blades in the desired position when current is off. Constant-speed operation is given by governor, switches

## CONSTANT-SPEED PROPELLER KEEPS ENGINE AT MOST EFFICIENT SPEED





were nothing more than twisted airfoils, the blades being built up of wooden ribs and covered with cloth. Then they were hewn out of a solid piece of timber. The first really serviceable propellers were made of laminated wood; these proved reliable and aerodynamically efficient throughout the crucial years of aviation, and some of this type are still used for small civil planes and military trainers.

Early experiments with steel propellers were conducted in 1917, prompted by maintenance difficulties in World War I. During the next two years, several hollow steel props were tested by the Army Air Corps, and one solid steel model performed satisfactorily. In 1921, earnest development of the aluminum-alloy blade was undertaken, and the ease of making blades from solid stock, as compared with the expense of fabricating hollow steel blades by the then available methods, made aluminum more desirable. These dural blades and hubs gained wide popularity, and the steel-prop development lagged.

The improvement in performance and durability brought metal propellers into almost universal use during the late 20's; the most famous of these were the Hamilton Standard and Curtiss Reed, both made of dural. These props, of course, had a fixed blade angle, or pitch. As long as aircraft engines remained in the 500-horsepower bracket and 160 miles per hour was considered a lot of speed, the fixed-pitch propeller was adequate. As engines became more powerful and the demands for performance increased, power-plant limitations were relieved by the introduction of the adjustable-pitch prop, whose blades could be set to low or high pitch—or a happy medium—and clamped securely in the hub. In low pitch, the plane had fine take-off and climbing characteristics but was short on speed; in high pitch, with the blades turned to meet the air at a greater angle, the plane developed maximum speed but its take-off and climbing ability was not what it might have been. A compromise setting, however,



**NEUTRALIZING TORQUE.** The simplest way to counteract this turning effect on the plane is, of course, to have two engines with props rotating in opposite directions, as in the P-38

gave the craft good all-around performance.

As the pioneers had pointed out many years before, what the flyer really needed was a propeller whose pitch settings could be changed during flight. In 1933, the Collier Trophy was awarded to Hamilton Standard for the development of a successful controllable-pitch propeller whose blades could be set at high or low hydraulically through a control in the cockpit that actuated the hub mechanism. During the same year, Curtiss perfected an electrically controlled propeller. By taking off with the prop blades in low pitch, flyers got their ships off the ground in 35 percent of the distance formerly required and increased their rate of climb approximately 30 percent. When they reached the desired altitude, the shift was made to high pitch, with the result that top speed was increased almost 15 percent. For higher flights, an additional 20-percent increase in the plane's service ceiling was obtained. The ingenuity of Hamilton Standard and Curtiss-Wright engineers greatly influenced airplane and engine design by making possible the use of larger and faster military craft and transports. The Lycoming-Smith electric controllable-speed prop became popular for lower-powered civil airplanes.

But with the advent of 1,000-horsepower engines, this business of changing blade pitch required further refinement. The engine and prop have to be carefully mated; for maximum performance, each has to


## DUAL-ROTATION PROPS PERMIT MORE POWER FOR FIGHTERS

Suppose you were a designer and had the task of adapting an existing fighter type to use an engine of greater power. It would be easy to increase the size of the plane, but a single propeller large

enough to absorb the extra power would require a higher landing gear, and its tip speed would be dangerously high. Also, torque would be troublesome. A dual-rotation prop solves these problems








## DUAL ROTATION

Ultimate in props today is the dual-rotation job of four or six blades, consisting of two units on co-axial shafts which turn in opposite directions. At the left is a Hamilton Standard Hydromatic installation on a Douglas B-23 medium bomber. The small knob behind the rear blade tip is the constant-speed governor. Simplified drawing shows how prop works


make concessions to the other, and for every combination of engine and propeller there is an optimum speed for the two. The engine's top power output is gained at a constant r.p.m., or crankshaft speed. This is generally higher than the propeller's optimum speed, and reduction gears are set into the engine nose section to slow down the prop to three quarters or half the engine speed.

In its job of translating the engine's horsepower into useful thrust, the prop also acts as a brake on the engine. But this braking effect must be carefully controlled or the engine will not function

at its best. The two-position propeller is not sufficiently flexible in its operation to absorb the output of today's high-powered, highly super- (Continued on page 212)




## VARYING PITCH ON AN ELECTRIC DUAL-ROTATION PROP





# Keying Your Generator

## AUTOS



Sensitive relays for governing the output of the generator are the electrical nerve centers of a car. At the left is pictured a two-unit type. The air scoop is part of the air-cooling system of the generator.

By RALPH ROGERS

**G**ASOLINE rationing has in many cases taxed the capacities of automobile electrical systems to the utmost. Modern generator regulators are ingeniously designed to maintain, so far as possible, a full battery charge under all circumstances of car use. But when under rationing a car is not used sufficiently, even the flexibility of these devices may not be adequate to keep a battery from becoming discharged. Hence in some instances it is desirable to change the regulator adjustments somewhat to compensate for rationed driving.

About a decade ago, before defrosters, radios, heaters, and other electrical accessories were in general use, the low-output, third-brush generator provided ample current to meet the ignition and lighting requirements of the average automobile. With this type of generator, it was a simple matter to adjust electrical output. By moving the third brush in the direction of armature rotation, output was increased; by moving it against rotation, output was decreased.


To carry the additional load imposed both by numerous accessories and by more powerful lighting and ignition systems, the generator output in more recent cars has been greatly increased. This has necessitated the use of addi-

tional means to control the generator and thereby protect the battery and lighting system.

Today, most passenger-car generators are controlled by a three-unit regulator which consists of a cutout relay, a current-limiting device, and a voltage-limiting device. However, a few cars are equipped with a two-unit regulator consisting of a cutout relay and a voltage-limiting device; control of the current is provided by a fixed third brush on the generator which flattens out the curve of current output. The operation of the two units in this kind of regulator is the same as that of the corresponding parts in the three-unit type.

The function of the cutout relay, of

The way to make current and voltage adjustments on a common regulator is shown below. Bend one spring hanger at a time



# Output to Rationed Driving



course, is to disconnect the generator from the battery when the generator output is insufficient to charge the battery. The other two regulators provide control over the generator output under varying conditions of generator speed, electrical load, and battery charge. Each of the three units is, in effect, a magnetic switch. The cutout closes and opens the main charging circuit as motor speed increases and decreases. (Without the cutout, battery current would drain back through the generator when the motor is idling.)

The current regulator opens and closes the field circuit, rapidly inserting and removing resistance, when the generator has reached its maximum rated output. The voltage regulator also inserts and removes resistance in the field circuit when the voltage of the system reaches its safe maximum, thus preventing battery overcharge and excessive voltage.

Before you change any adjustments on the regulator, first make an inspection of the electrical system. Check the condition

of the battery and see that the generator drive belt has the proper tension. Examine the generator for worn or sticking brushes, dirty commutator, defective field coils or armature, a grounded brush-holder, or weak brush springs.



As a rule, the settings of a generator regulator will seldom change much during operation, although some variation may be caused by point wear, vibration, and temperature changes. The settings may sometimes need readjustment to compensate for some unusual condition of operation. For example, in semitropical climates, the voltage-regulator setting may have to be lowered somewhat, since a warm battery has a lesser resistance to current than a cold one.

With batteries handicapped by rationed driving, one common servicing job these days is to check on the efficient operation of regulators. The three drawings on this and the facing page show how to adjust common types of regulators. Because a regulator is a complicated and sensitive device, it isn't wise to change the settings yourself unless the need is clear-cut and no automotive electrician is available. Do not increase the current regulator setting to more than the rated generator output (which is obtainable from the manufacturer's data sheet if it is not stamped on the generator), because serious damage may result. Remember also that a slight bending of the spring clips will result in a substantial difference in regulator performance. An accurate ammeter and voltmeter are essential to precision adjustments; the dashboard meter will not do.

In servicing a regulator, there are also some specific rules to bear in mind:

1. Each type of regulator has been de-

Another typical three-unit regulator is shown at the left. The regulator at the right, which has no current-control unit, is used with a third-brush generator having a relatively constant current output





signed to operate with a particular generator and polarity system. For this reason regulators or relays must never be replaced by others of a different type or model. The only exception to this occurs when the manufacturer supersedes one

model with another. If a regulator with the wrong polarity is installed, the result may be a rapid failure of the regulator.

2. Do not close the points on the cutout relay by hand when the battery is connected. To do so will damage the relay points, and by welding them together may cause serious damage to the generator.


3. A regulator should be at its normal operating temperature when tests are made. If it has been demounted for service, it should also be tested in its normal operating position.

4. After any voltage-regulator adjustment, go through the following procedure before testing the new setting. Replace the cover and reduce the generator speed until the cutout points open; then speed up the motor until high output is achieved.

5. When any adjustment has been made on a regulator, the generator must be re-polarized by momentarily connecting a jumper lead around the regulator. This permits a brief surge of current to flow from the battery to the generator. A generator with reversed polarity will cause arcing and burning at the points.

6. If the regulator points need cleaning, use a thin, flat, fine-cut file. Cavities not deep enough to make replacement of the points necessary may be scraped with a spoon file or riffler. The points should then be cleaned with carbon tetrachloride.

It can be readily seen that a regulator should be treated like the delicate precision instrument that it is. Random tinkering with a screwdriver is rarely advisable because it may do more harm than good. If points are clean and all connections are tight, major readjustments will not often be needed. When they are required, the best course is to study the manufacturer's recommended checkup procedure, to make each readjustment singly, and to verify each new setting with an accurate meter.





## HOW A GENERATOR REGULATOR WORKS

THOUGH seemingly complicated, a generator regulator is not difficult to understand. As the generator picks up speed, voltage builds up in the two windings of the cutout, creating two magnetic fields which together overcome a spring pull and close the points. The battery is then being charged. If the generator output drops off to the point where the current would flow back from the battery, the direction of flow through the heavier winding is reversed whereas the flow through the other winding is not reversed. The two magnetic fields then cancel each other and the spring pulls the points open.


The voltage regulator operates on the principle that as a battery nears its full charge, the voltage in the charging circuit tends to increase. This regulator also has two windings; the heavier one is part of the field circuit so long as the points are held together by a spring, while the other carries battery current. As the battery approaches a full charge, the magnetic field built up in the two windings is sufficient to open the points. The field current must then flow through a resistance to the ground; and the magnetic pull in the regulator core is greatly reduced. The points then close again, and the cycle is repeated from 50 to 200 times a second.

In the current regulator there is a single heavy winding which carries the entire generator output. When the generator begins to exceed its maximum rated output, the magnetic field generated by the winding is sufficient to break the circuit, forcing the field current to flow through a resistance to the ground. This weakens the magnetic field, the points close, and the process repeats.


# USEFUL AUTO HINTS



**1** TIRE INSPECTION TOOLS can be made by inserting two 6" long screw hooks a short distance from the ends of two boards. If these are hooked over the beads of a casing and the ends of the boards are then pulled away from the tire, it is easy to look for breaks, other injuries, or nails. The tools cost little to make and may be conveniently carried in the car.—A. R.



**2** AN AUTO JACK BASE is handy whenever a flat tire must be changed on a wet, soft, or sandy shoulder where the jack might otherwise sink into the ground. The base is also valuable even on firm ground because it adds to stability and minimizes the chance that the car may fall off the jack. Bolt the two strap-iron clamps to a 1/2" metal plate that is at least 8" square. If you are unable to obtain a suitable metal plate, hardwood 1 1/4" thick will serve, provided that it does not raise the jack too high to fit under your car.—H. W.



**3** CELLULOSE TAPE is convenient for securing loose or dangling wires about the steering column and dashboard. The tape, which is inconspicuous because of its transparency, both removes a minor accident hazard and reduces the likelihood of short circuits or broken wires. It is also excellent for correcting rattles and squeaks of fittings under the dash.—E. M. G.



**4** GASKETS CAN BE HELD in place by thread when an oil pan (or any other large part using a gasket) is being reassembled. It is often difficult to insert the bolts through the proper holes even when heavy grease or shellac is used as a binder for the gasket. If ordinary sewing thread is looped through alternate holes, the pan can be bolted on easily. Once the bolts are drawn up tightly, the fine thread will not interfere with a perfect seal.—J. K.





Stan pulled into the Model Garage with a spick-and-span sedan in tow of the wrecker

# Gus Deals in Opposites

**HE PROVES THAT THE SAME SYMPTOMS DO NOT ALWAYS POINT TO THE SAME TROUBLE**

**BY MARTIN BUNN**

IT WAS getting along toward supper time of a warm fall evening, and a half dozen of us Model Garage regulars were sitting around Gus Wilson's shop watching him work, when his partner Joe Clark stuck his head in at the door that leads from the office and said: "Oh, Gus, I forgot to tell you—Alex Kerr called up a little while ago and said he wanted his car towed in. He didn't say what was wrong. I sent Stan for it. He ought to be back any minute now."

Alex Kerr is a mild-spoken, apprehensive-looking little man who runs the cigar store across the street from the railroad station in our town. Gus Wilson and he are about as different as any two men can be, but that doesn't keep them from being firm friends.

Big Ez Zacharias burst out laughing at mention of Alex's name.

"Betcha a dollar there ain't a derved thing the matter with his car," he offered, and took

a big bite off a plug of chewing tobacco. "He's worse'n an old woman with that bus of his—every time he hears a rattle he's dead sure his motor's comin' apart. He only drives it a couple of days a month, and I betcha every time he brings it home he washes it off an' polishes it."

Ez chuckled at the thought of Alex shining up his five-year-old bus.

"Why, I met him at the Pleasanton cross-roads one day, an' he flags me down an' asks me if the dirt road I'd jest come over was muddy. 'Muddier'n Jason's bog,' I tells him, 'but nothin' you can't plough through.'"

Ez laughed out loud and slapped his thigh with a resounding thwack.

"Alex shakes his head," Ez sputtered again after a pause, "and says he guesses he won't try it—he don't want to get his car muddy!"

"Well, Ez," Gus told him, "nobody ever will accuse you of taking too good care of your car. Maybe Alex is a little overcareful, but there's no *maybe* about your being over-careless!"

Ez grinned, pushed his postman's cap onto the back of his shaggy head, and shifted his quid over to his left cheek. "I can't afford to baby my automobiles," he said defensively. "I gotta get the mail over that rural route of mine, ain't I? Anyway, cars is

built to take it, and I aim to see that any car I drive goes any place I have to. When I'm deliverin' Uncle Sam's mail, I've got no time to be nursin' and foolin' around with a temperamental car."

A horn honked briefly outside the open shop door, and Stan—he's the Model Garage's current grease monkey—slowly maneuvered the wrecker and a respectable-looking '39 sedan into the shop. Alex Kerr got out of the sedan, looking even more worried than usual.

"Hello, genta," he told the Model Garage regulars briefly but courteously, and hardly waited for a reply to his greeting before jumping right to the point.

"Say, Gus," he said with a rush of words. "I'm in bad trouble. I guess I've stripped a lot of teeth out of my flywheel. That's bad, isn't it—a pretty big repair job?"

"Well, it is sort of a big job," Gus admitted. "You have to remove the transmission and clutch before you can take out the flywheel to change the ring gear. The old ring gear must be cut off; then the new ring must be heated to expand it so it can be pressed on the flywheel. It's what's called a shrink fit.

"But before we start worrying about that, let's make sure that we're doing our worrying about the right thing. Flywheel teeth don't get broken off so often. What makes you so sure you've stripped yours, Alex?"

Alex looked relieved.

"Well, it sounded as if I had," he said. "This afternoon I thought I'd go over to Pleasanton to see my sister."

"Ain'cha askeered of that Pleasanton mud hole and of using up your A coupons?" Ez asked, and he looked around at the rest of the boys with a sly twinkle.

"I got a right to see my sister," Alex retorted. "She's been sick in bed for the last month, and, anyhow, I haven't driven my car a mile in three weeks, and I always go easy on my A coupons."

Satisfied that he had justified himself, Alex turned back to Gus.

"Well, when I tried to start up," he said, "there was a terrible noise, and the motor stopped dead almost as soon as it started. I didn't know what was the matter, so I went into Henry Miller's hardware store and asked him. He came over to my garage with me, and I stepped on the starter again. The motor did the same thing—made that noise and stopped almost as soon as it started. Henry said: 'You've stripped some of the teeth off your flywheel—you better not monkey with it.' So I phoned Joe Clark, and he sent the wrecker—and here I am."

WE ALL had to laugh at the idea of anyone who was having car trouble asking Henry Miller's advice—Henry being strictly a Sunday driver and notoriously a left-handed mechanic. Even Gus Wilson had to grin at that one.

"About that noise," he asked Alex. "What did it sound like?"

"Oh, I dunno exactly—it sounded like broken teeth to me," Alex said. He scratched his head. "Wait a second, now—yes, I've got it. The noise was three or four clicks—loud ones."

"Clicks, hey?" Gus said. He got into Alex's car and stepped on the starter. The starting motor took off, but after it had turned the engine over maybe about a quarter of a revolution there was a sharp click-click-click-click, and then it stopped dead.

Gus switched off the ignition and got out of the car.

"You can quit worrying, Alex," he said. "There's nothing the matter with your flywheel—none of the teeth have been broken. The only bill you'll have to pay on this job is for the wrecker and for recharging your battery."

"Recharging my battery?" Alex looked incredulous. "What's my battery got to do with it?"

"Everything," Gus told him. "Your battery is so run down that it can't feed the starting motor enough juice to turn the engine over. Those clicks are the tip-off—some types of solenoid-starter relays always



"In the end she always starts off, and then runs all right all day, even on bad roads"



give off a series of loud clicks when you step on the starter if the battery is run down. I'll put a rental battery in your bus now, and you can stop by the day after tomorrow and get yours."

AS SOON as Alex had driven out of the shop Ez Zacharias slapped his thigh with one of his ham-sized hands and let out a bellow. "What did I tell you?" he demanded. "He's just like an old maid with that bus."

"Say, I've been havin' trouble somethin' like his—only I ain't heard any of them clicks. Sometimes when I try to start up in th' mornin' my motor acts th' same way—like broken flywheel teeth was jammin' the starter-motor drive gears. The starter turns the motor over pretty near a full turn, near as I can make out, and then she goes dead."

"But I don't start worryin'. No, sir! I just wait a couple of minutes, and then step on her again. Sometimes I have to do that a half a dozen times, but in the end she always starts off, an' then runs all right all day. First off I thought my battery was run down, but it ain't. Well, cars is built to take it. What's the use of gettin' in a stew every time somethin' ain't just right?"

"You're a wonderful guy, Ez," Gus told him. "I'll bet that car of yours uses mighty little oil, too."

"Huh?" Ez grunted. "How do you know that? I don't generally get down here to town to buy my oil. But you're dead right—I never saw a car that uses so little."

"Ever take a look to see what's in your crankcase?" Gus asked.

"Me? No!" Ez said. "Why should I? Car's runnin' fine, except for that hard start-in' some mornin's."

"Take a look," Gus advised. "It might save you some money."

Ez stared at him. Then he got up. "So you figger there's somethin' serious the matter, do you?" he said. "O.K., Gus—that's plenty for me. Wait a minute till I drive it in, and then you can take a look."

A half minute later Ez drove his mud-spattered sedan into the shop. "Have you ever washed that jalopy since you bought it?" someone asked when he got out.

"No, sir, I ain't," Ez said shamelessly. "What would be the use—I'd get it all mud-died up again next time it rained, wouldn't I?" He turned to Gus. "Go ahead, perfer-sor—let's see what's in the crankcase."

Gus placed a large can under the car and opened the crankcase plug. A black, pasty semifluid began dripping slowly into the can. Gus rolled a drop of it between his thumb and forefinger. "Sludge," he said. "Much more water than oil. Your crankcase is full of it—that's why you thought you didn't

need any oil. Man, you've been driving this car with practically no engine lubrication. You'll be darned lucky if you haven't scored your cylinders or your pistons."

Ez was looking serious now. "What do you mean—water?" he growled. "Where would all that water come from?"

"It came from one of the cylinders," Gus said. "The odds are about a hundred to one that it got into the cylinder from the water jacket through a loose or broken cylinder-head gasket, although there is just a chance that it got in through a crack or a sand hole in the cylinder. I'll have to do some checking to make certain, but probably the trouble is a bad gasket."

Ez looked relieved. "Well, that ain't so bad that it couldn't be worse," he said. "Get it fixed up as quick as you can, will you? . . . Say, Gus, how the dickens did you know there was water in my crankcase?"

Gus laughed. "Oh, I just used my head—that's what it's for," he explained. "You said that when you stepped on your starter in the morning—after your car hadn't been used for several hours—the starting motor would turn your engine part way over and then stop; and that after you had waited a while it would give it another part turn; and so on until finally it started."

"That made me guess that your starter motor was working against water in one of the cylinders—water in a cylinder can't be compressed by the piston, but if you continue to apply pressure to the piston it will force the water, little by little, through the ring gaps into the crankcase. The fact that your car was using very little oil was good supporting evidence—naturally, all that water in the crankcase kept the oil level up, although what you were using for lubrication wasn't oil, but watery sludge. . . . I don't think you've done much real damage this time, Ez, but if you keep on misusing your car, someday you're going to get into real trouble."

Ez bit off a fresh chew.

"Who, me?" he said. "I ain't worryin'—not while you're around to worry for me!"

## GUS SAYS:

Reduced antiknock in our wartime gas gives the motorists one more thing to watch—but it isn't all bad. Some drivers have discovered that they can cut down on knocking by easing up on the accelerator. And that is a good way to lengthen tire life and increase mileage, too!

# AUTO Ideas





**OVERSIZE TIRES** are now issued to Army motorcycle units for desert use. The tires, which are mounted on 15" rims, carry only a few pounds of air pressure for travel through sand. Armored Force officers say that they have jumped the motorcycle from the least maneuverable military vehicle in deep sand to the most maneuverable.



The photos above, taken at the Armored Force School, show the new tire undergoing hill-climbing tests and compared to a standard tire. Note the greatly increased road-bearing surface.

**PHANTOM RAYS**, sun reflections that may make a traffic signal seem to be lighted when the sun is low in the sky, are eliminated in a new type of light shown below. The silvered glass reflector is so shaped as to prevent the reflection of any light except that from the bulb within the signal.



**PORTABLE FLUORESCENT** lighting units have been developed for use in garages. These utility lamps each contain two fluorescent tubes which are protected from breakage by a clear plastic guard. The lamps may be used on casters under autos or suspended like droplights.




# HOME AND WORKSHOP



Here is another handsome and useful piece from the workshop of Joseph Aronson, who is well known to readers of **POPULAR SCIENCE** as a designer of authentic interiors. He developed it from furniture that has been in demand since its introduction by Tudor craftsmen. Duplicated in the home shop, it will serve as table and bench on a terrace


# OLD DUTCH SETTLE

## from Early Hudson Valley Days



A TABLE, BENCH,  
AND STORAGE BOX  
IN ONE WILL MAKE  
AN IDEAL PIECE  
FOR YOUR COUNTRY  
OR SUBURBAN HOME

By  
JOSEPH ARONSON



**T**HE box settle or table settle is an old furniture form. Tudor designs of this type reappeared in American furniture of the 17th and 18th centuries, and in simplified versions the settle still appears in country homes up to the present day. The model illustrated was designed for and used on the covered terrace of a modern American home, doubling as table and bench as the occasion required.

A storage compartment is an authentic part of this piece and accounts for its part-time name of box settle. One other name, Dutch settle, stems from its popularity with the Hollanders who settled in the Hudson Valley. The term "settle" itself has nothing to do with settlers, but is an old word for bench, especially a bench with a high back.


The basic construction of this table settle is elementary, and the materials may be of the average lumber-yard kind. Posts and top stretchers should be selected from the best sections of 2" by 3" pieces of fir or pine, planed and sanded smooth, and then doweled together. Note that the box ends are placed so that their top edges come flush with the top of the box lid, and  $\frac{1}{4}$ " higher than the

box sides upon which the lid rests. Both ends and sides are fastened to the posts with four dowels at each end.

For the box floor, if  $\frac{3}{4}$ " plywood is not available,  $\frac{1}{2}$ " material may be used. Ends and sides of the box are rabbeted to receive the floor, which has its four corners notched out to fit around the posts. The lid should be glued up and reinforced with cleats screwed to the underside. Metal hinges may be used, or dowel pins may be put into the lid from the posts, but be sure to get the dowel centers outside of the back of the box as shown in the drawing.

Material for the top should be selected from clear, straight stock and carefully glued up. Deep cleats, which are screwed on, will help keep the top straight. Pivoting of the top is by means of the turned pins inserted through holes in the cleats into cor-





Front and side views of the table settle, above, show in detail how this triple-purpose piece is constructed, while at left the drawings are of a table-top pin and a doveled stretcher-post joint

### LIST OF MATERIALS


No. Pc.	Description	T.	W.	L.
4	Posts	1 3/4	2 3/4	23 3/4
2	Stretchers	1 3/4	1 3/4	16 3/4
2	Box ends	3/4	9 3/4	10 3/4
2	" sides	3/4	8 1/2	30
1	" lid	3/4	17	29 5/8
1	" floor (plywood)	3/8	14 1/2	30 3/4
2	Feet	1 3/4	2 3/4	21
1	Table top	3/4	30	51
2	Cleats	3/4	4	27
4	Pins turned 7" long from 1 1/2" stock			

Note All dimensions are given in inches.

responding holes in the posts. The position of these holes must be exact or the top will either rest at a bad angle when up or not set properly on the arms when down.


Finish the table settle to suit its intended use. If the wood you use has an interesting texture, a pleasing finish can be made to simulate old pine or maple with a water stain of light walnut color, brushed over when dry with shellac and thoroughly sanded to a satin smoothness. On the other hand, a note of strong color is pleasant for porch or terrace furnishings, and some decorators would be tempted to try strong red, blue, or yellow paint.

## Improvised Wedge Made of Washer Locks Hammer Head Firmly



A LOOSE hammer head can be fastened securely and permanently to its handle by the use of a wedge made from an ordinary washer. On an anvil or a block of metal, hammer the washer to a thin edge at one side as shown in the drawing at the left. Drive it into the handle as you would a wedge. The compressed wood tends to expand back into the hole of the washer, locking it firmly.—HARRY S. ALLEN.

# FOR THE BOYS IN THE SERVICE




Made from a solid piece of wood, this case will hold 10 cigarettes. Its pivoted lid is held on by a brad and, as a decorative touch, is shaped like an airplane propeller.


## CIGARETTE CASE

**H**AVE you a son or a friend in the Army Air Forces? Here is a simply made cigarette case that will be an acceptable gift. In fact, its airplane-propeller lid lends it a novelty that will make it appreciated by anyone in the services.

Gumwood, mahogany, walnut, or any close-grained wood is suitable for the case. Shape it roughly to the dimensions shown; then bore the ten cigarette holes—holding a half package of cigarettes—to the size in the drawing, which is just large enough to let a cigarette slip in or out. These holes are best made in the drill press, if one is available. Dress the case to shape, sand, and give it a rubbed-varnish finish. The insignia in the corner which decorates the case is taken from an inexpensive pin.—B. M.



## Trousers Hanger Clamps Small Glued Parts in Model Making



WHEN small strips of wood or other material are glued up, as in model making, an ordinary trousers hanger will serve to perfection as a clamp. The device works independently of a fixed axis and will clamp equally well whether the outer surfaces of



the pieces are parallel or tapered. These hangers are usually faced with felt, which will be a help in keeping tapered sides from slipping under pressure.—R. E.





# Craftwork

## ATTRACTIVE PHOTOGRAPH FRAME

Designed by ERNEST R. DEWALT

**EASEL PICTURE FRAME.** This interesting picture frame is made of  $\frac{1}{8}$ " hard, pressed composition board, as shown in the drawing. Heavy cardboard glued up could be substituted for the pressed board. The picture opening is cut in the front mat only, while the  $\frac{1}{2}$ " holes for the rings are drilled  $\frac{1}{16}$ " deep in the front of the mat and in the back of the backing. These holes are lined up to take the rings, which, when in place, hold the mat and backing together.


Make three parallel cuts on the mat on a circular saw for decoration. Cut the easel stand as dimensioned so it will open freely to the proper angle. Rub white paint into the saw cuts, and when it is dry, sand and wax the entire frame. The photo is taped in position on the backing, the mat is arranged over it, and the rings are snapped in place to hold the pieces together. Working time:  $3\frac{1}{4}$  hours.

## PIVOT CURTAIN BRACKETS OF WOOD.

Maple pivot hinges for curtains answer a common household problem in a decorative manner. A pair of brackets and poles swing on dowel pins having beads at top and bottom. The wall mounts are fastened with long screws. Saw out the opening in the mounts, and bore and countersink two screw holes as shown. Fit each bracket in its mount so that it won't bind when swung; then, using a  $\frac{1}{4}$ " auger, bore a hole for the dowel pin through both parts when they are lined up.



Bore a  $\frac{1}{2}$ " hole in the edge of each bracket for a dowel curtain pole. Round and shape the lower part of the bracket, and round the back of the bracket and the front of the wall mount to a  $\frac{7}{16}$ " radius. Turn and drill beads for each dowel pin and the finials for the ends of the curtain poles. The top bead is fixed on the dowel pin with a brad; the bottom bead is removable, but it is a tight fit. Cut the curtain dowel to a length suitable for the width of curtains and size of window. Stain or paint the dowels, finials, and beads any desired color, and varnish or shellac the hinges. Working time:  $3\frac{1}{2}$  hours each pair.

**DOUBLE WINDOW HANGER.** Use maple or some other hardwood for the bracket and circular key, because the joint that holds the weight must have strength. Lay out the




# Ideas for the Home

AND TWO WOOD BRACKETS AND RODS FOR CURTAINS AND DRAPES




brackets from a center line and make both of them at the same time. Cut out the circles in the base and bore the holes for the two dowel poles. Round the top into the slanting sides and sand smooth. Cut the parallel grooves on a circular saw. Each key is sanded to a slip fit in the curve of its bracket. Bore and countersink each key for a 2 3/4" wood screw. Cut both dowel poles to suit the window dimension. The finish should be such that it will harmonize with the color scheme of decorations in the room.

To install, screw the keys to the woodwork, and then slip the curtain hanger, already assembled, over the keys. The weight of window hangings will prevent slipping of the brackets on the keys. Working time: 3 1/2 hours each pair.







## Personal Scrapbook for Mementos from Your Own Hero

ANY family with a member in the service will appreciate a personal scrapbook in which to keep clippings and pictures that are being saved for his return. The covers of this one are made of  $\frac{1}{4}$ " plywood, as is also the frame for the cover picture. Saw through the front board 1" from the binding edge and join the two parts with small hinges set flush. Clamp the boards together for accurate alignment and drill two holes for binding posts, countersinking the back for nuts, which are glued in place.


Coat the outside of the back with glue and

stretch over it imitation leather, canvas, sailcloth, light corduroy, or other suitable material, allowing  $\frac{1}{4}$ " for folding over the edges. Finish the inside face with a piece of stiff paper glued on to cover the edges of the lap.

A different treatment is required for the front. Glue the covering material along one edge only, stretch it into position, and hold it with pins. Center the frame for the picture and draw a sharp knife around the inside of the opening; then remove the frame, the material cut out, and the pins. Next, center the picture in the opening,

cover it with a thin sheet of transparent cellulose film, and glue the covering material down. Fold the edges and finish the inside face as was done for the back.

Alternative designs are shown for the frame, which may be glued on or fastened with upholsterers' tacks. Red, white, and blue, olive drab, or Navy blue paint may be used for a finish if the material used for the cover is such that it will take paint readily.—JOHN J. GALLIVAN.




### Method of Assembly

Alternative frames for the scrapbook cover are shown at right. Use  $\frac{1}{4}$ " plywood except for the truck axle, which may be thinner. Any printing serves as a pattern for letters of  $1/16$ " stock

INNER RING STEP FANCY UPHOLSTERERS



Frame Suggestions for Sailors



Frame Suggestions for Soldiers


*from*  
**READERS'**  
**WORKSHOPS**

... ACTION MODELS  
 DISPLAY INGENUITY  
 OF HOME CRAFTSMEN


Capable of firing blank .32's, this deck gun has a 12" long barrel,  $\frac{3}{4}$ " recoil, 360-deg. traverse, 60-deg. elevation, and adjustable sights. It was built by Fred Jameson, Jr., of Omaha, and M. C. Gentry, of Detroit



Part of a collection of 50 models built by J. N. Holsted, of Omaha, over a period of 10 years, the two automobiles below depict a phase in the evolution of transportation. At the left is an 1898 Oldsmobile, at right, the same make dated 1903. Each is 9" long



Real oil is pumped by the miniature well above, which is modeled after an old-style, steam-driven rig. A 1/20-hp. motor in the base provides power for a continuous flow through  $\frac{1}{4}$ " pipe to a tank and return line. Joe D. Kitchen, of Caro, Mich., the designer, even included floodlights



Another model of historic value is this all-wood locomotive—a reproduction on a scale of  $\frac{3}{4}$ " to 1" of the C. P. Huntington, an engine built in 1864 and sent around Cape Horn on board ship. Alfred D. Slater, of Cleveland, mounts a motor behind a display case to drive the working parts





**DEHYDRATING IN ANY OVEN** is now simple with a new home food drier that can be used to advantage through the growing season and into late fall. Three galvanized-wire racks hold  $6\frac{1}{2}$  to 10 lb. of food at one time. The unit measures 11" by 14 $\frac{1}{2}$ " by 17 $\frac{1}{2}$ ", which is a convenient fit for most ovens of moderate size. Attached to it is a long, hooklike arm which can be adjusted to hold the oven door ajar for air circulation as drying goes on.



**THIS HANDY TOOL** is made strong enough to open wooden cases and tough corrugated cartons. Besides this, the blade end of it can be used to cut cord and rope. The carton opener, as it is called, is 14" long and 1 $\frac{3}{8}$ " wide and has a specially shaped slot in its flat handle which can be used for pulling out nails in wooden cases. The slot is also handy for hanging the opener up when not in use. The blade is of good steel and can be sharpened on an emery wheel or a whetstone.

HW 520

**GUMMED STICKERS** that take the place of metal paper fasteners in home or office are sold in convenient sheets bound in booklet form. Each booklet contains 500 gummed stickers. The sheets are perforated to tear apart easily and quickly. Being gummed on both sides, they can be used for attaching carbon copies to letters and for mounting photographs, clippings, and souvenirs in your scrapbook or on file cards, labels on bottles, and like purposes.



**DRYING SMALL ARTICLES** in the bathroom involves less trouble if the rack shown below is at hand. Hooked over the towel bar, it will still permit use of the latter while itself providing about four times as much additional space for hanging stockings, handkerchiefs, lingerie, and similar light laundry. Made entirely of wood, it can be put up or taken down in a moment, and holds securely in position without any other fastening.



**PACKAGED STRING TIES** have recently appeared on the market as substitutes for rubber bands. They consist of a stiff paper square with an extra heavy disk to which a length of strong string is fastened. The ties are boxed in the form of a coiled strip having perforations which make it easy to tear off individual ties as needed. Each coil contains 250 ties. Wrapped around papers, envelopes, and small packages, the ties hold securely. They can be saved after use and put into service again and again.




## AIDS TO WARTIME *Housekeeping*



**CARE OF YOUR TOASTER** is wise practice these days, for in most instances it will be impossible to replace it. Clean crumbs out of the inside frequently with a soft brush. If the toaster has a removable crumb tray, take it out often for cleaning. The chrome-plated outer housing can best be cleaned with a damp, soapy cloth, then rubbed briskly with a dry, soft cloth. Never put the toaster in water. Be extremely careful during all cleaning not to damage the heating elements. After using the appliance, allow it to cool off before you wind the cord loosely around it. This will lessen the risk of short circuits that might come from repeated coiling.




**RESLICING PRESLICED BREAD** is made easy with this wooden gadget designed and hinged like the cover of a book. A slice of bread is placed between the two covers and held upright while a knife is drawn down through it to make two thin slices. The covers permit holding the bread firmly without danger of cutting the hand. Any knife with a sharp blade is used. Besides making thin slices for Melba toast, canapés, and rolled sandwiches, the unit is a help with the last end of a roast or meat loaf.



**PERSONALIZED LABELS** are a new idea in identifying jars for families who raise and put up their foods. The labels are attractively colored and are printed with the name of the purchaser. They come gummed on one side and, measuring  $2\frac{3}{4}$ " by 4", will fit any jelly or canning container. There is a space in which to write the name of the contents and the date. These gay labels will add a bright touch to the fruits of your labor, and they will also be welcome presents for a friend who puts up food.





## MARINE RAILWAY

Makes It Easy to Haul Out Your Boat for Winter Storage

THE incline of this easily-built marine railway is made of two planks set on edge. They must reach out to water deep enough to float the boat, and the rise should not be over 4" to 1' of length. Space the planks roughly two thirds the beam of the boat apart, fastening them with crosspieces let into their lower edges and secured with lag screws.

Rollers can be made of pieces of 2" pipe turning on longer 1" pipes or heavy rods which are fixed in the planks about 3' apart. The shape of the bottom of the boat should be taken into consideration in locating the rollers, especially in fixing the distance from them to the top edges of the side planks. Medium-sized boats can lie over slightly until one bilge bears on the top of the adjacent side plank. There will be little pressure when the hull is still water-borne, but above the water the edges of the side planks should be rounded and padded with old hose or canvas, and well greased so as to minimize friction.

Cut notches 2 1/4" wide by 3" deep in the under edges of both side planks about 1' from the ends to be submerged. Fit a plank across two posts, as shown in the drawings, with one bolt only in each end. The posts should be 2' wider apart than the beam of the boat. Drive the posts far enough off shore so that the cross plank can be 2' below the draft of the boat. The single bolt in each end of the cross plank will prevent excessive strain

from developing while the posts are being alternately driven into position.



Float the assembled incline out over its location between the posts. Place rocks on it to submerge it so that the notches slip over the crosspiece, then fasten it there. The easiest way to do this is with strap-iron angles previously bolted on the two side planks just above the notches, each with a hole in its horizontal leg. Spikes can then be driven through these holes into the cross-wise plank and bent over to hold the incline down. If necessary, you can submerge in a bathing suit and strike a few blows at a time. This fastening is merely to offset flotation, and can easily be released for hauling the railway ashore after the boat is taken out at the end of the season.

The inshore end of the railway is held securely in place by short posts. Sections can be added to extend it as far as desired. The same incline can even be carried high enough so that a truck can be backed up to the end of it and the boat slid aboard and hauled away for winter storage elsewhere.

No great power is required for hauling because of the rollers, although a block and tackle may prove helpful. Fasten the hauling gear to a heavy line looped completely around the hull and held with lighter lines across the top of the boat. This distributes the strain evenly throughout the hull instead of applying the entire load to a single mooring bitt and cleat.



# BOAT HINTS




**ONE OUTBOARD MOTOR** used as shown above saves gas, carries twice as many passengers, and minimizes the danger of a spill in rough weather. The two canoes are held rigid with saplings lashed to the thwarts.

**A WARPED TRUNK** makes it hard to raise or lower the centerboard. To correct this condition, insert wedges at the center of the well as at the left before the boat is laid up for the winter, and leave them in until spring. Have a helper tap in one wedge while you drive in the other, being careful to expand the slot only slightly beyond its normal width.—H. S.

**SMALL-BOAT DRY DOCK.** Costing no more than a few dollars, this arrangement makes it easy to lift boats clear of the water for repairs or painting. Small boat yards and clubs, as well as individual boat owners, will find that it pays for itself quickly. The dimensions of the various parts will vary according to the size of the slip and the length of the boats to be accommodated. Those up to 30' in length can be raised in the dock shown at the right.

One man can readily lift a boat by means of the 10' long lever. This is hooked down to the dock at the end of its stroke so that the operator can then remove the pin which has been bearing the load in order to insert it in the new position. All four lifts should be raised to the same height before the first one is raised any further. The fork end of the lever is protected by covering it with sheet metal at the points where wear would otherwise occur.

If such a dock can be located high enough on tidewater, it is possible to make repairs to the bottom of a boat while standing on dry land. Away from tidewater, the top of the slip should be high enough above water level to give sufficient space for one to work conveniently on the bottom of a boat from a dinghy or wherry.—BRUCE MACINTOSH.





# MAINTAINING HOME DEFENSES



**A** FIRE extinguisher is a front-line weapon against fire. But, as with other weapons, its effectiveness depends on its ability to do the job for which it was designed, on its upkeep, and on the skill with which it is used.

Only three types are ordinarily found in residences. One, the soda-acid extinguisher, will combat fires fed by ordinary combustibles, such as wood, paper, and textiles, but not those involving inflammable liquids or electrical equipment. Another, the foam type, can smother a gasoline or oil fire, but must not be used on electrical apparatus.

The third—the familiar pump-gun vaporizing-liquid extinguisher—employs a carbon tetrachloride base instead of water and may be used on any kind of fire, but it is rarely made in very large sizes. On coming into contact with heat, the stream from this extinguisher breaks down into a vapor that displaces oxygen and thus smothers the fire. This vapor is a nonconductor, will not damage mechanical or electrical installations, and leaves no residue.

All of these units should be inspected at least once a year. The hose, gasket, nozzle, outer shell, and seams should be examined for signs of clogging, corrosion, denting, or tampering. If repairs are needed, they should be made by the manufacturer.

The soda-acid and foam extinguishers also require annual recharging, which can be done at home, preferably outdoors. Directions on the labels should be carefully followed, utensils should be dry and clean, and only refills recommended by the maker should be used. If you mark the date of maintenance on a tag attached to the handle,

it will serve as your reminder.

Despite its designation as a "chemical" extinguisher, the soda-acid unit uses only water to put out a fire. The chemicals provide pressure to throw the stream 30' to 40'. This pressure is supplied by carbon dioxide gas formed by the reaction of sulphuric acid with bicarbonate of soda when the extinguisher is inverted for use.

After the unit has been emptied to take its annual recharge, unscrew the ring-top handle and remove the acid bottle; then wash all interior parts thoroughly with clean water, draining the water through the hose. Dissolve the powdered chemical refill in warm, not hot, water, as directed on the label; pour the solution into the extinguisher to the point marked; and finally replace the acid bottle in its cage. When the cap is screwed back on the shell, make sure that at least four threads are engaged. A small amount of petroleum jelly rubbed on the threads will make this easier and facilitate removal for the next recharge.

The foam extinguisher looks like the soda-acid unit, and its parts are handled the same way when it is recharged. If you have any doubts about the kind you own, the Underwriters' rating on the label will identify it. The soda-acid type is rated *A* (for use on ordinary combustibles), while the foam is rated both *A* and *B* (the *B* meaning for use on inflammable liquids). Two chemical solutions must be replaced in the foam-type unit—one in the inner chamber and one in the outer. Directions on the label should be followed, and only the materials recommended should be used.

Vaporizing-liquid extinguishers are the easiest of all to service since they need recharging only after use, but the pump action should be tested annually by discharging a portion of the liquid into a clean dry con-

# AGAINST FIRE

## Extinguishers Must Be Ready for Instant Action . . . Here Is How and When to Service Them

By

**DELBERT JOHNSON**

Safety Research Institute

tainer. This test liquid can then be poured back through the filler opening. No lubricant should be used on the piston. Because ordinary commercial carbon tetrachloride may corrode and damage the extinguisher, use only the maker's processed refill.

Soda-acid and foam extinguishers located on a porch, in a garage, or in any exposed place should be housed in a tight cabinet that can be heated by a 50-watt bulb to keep the water from freezing—don't try to use an antifreeze chemical. A simple cabinet of  $\frac{3}{4}$ " stock will suffice unless you live in a section where temperatures go below zero, in which case double-wall construction is needed. For this, make the outer walls of  $\frac{1}{2}$ " stock, and arrange a lining of  $\frac{1}{8}$ " wallboard or similar material, leaving a  $\frac{1}{2}$ " air space between the two walls. The door should also be of double construction, closing into a rabbet and held shut with a spring latch.


Inside dimensions may be as small as practicable just so the extinguisher may be removed quickly. Four 4" iron rods, or similar brackets, set in the sides about 4" above the floor will hold the unit. Under them should be mounted a 3" conduit box and receptacle for the lamp, which will then throw its heat upward and thus keep the entire cabinet warm. During a protracted freeze, or in subzero weather, the lamp should be kept burning continuously.



Extinguishers of the soda-acid type must be recharged once a year. The chemical is dissolved in warm water and poured into the unit; then the acid is put back.




## Dainty Sprinklers Made from Oil Cans



WHEN plants are brought indoors for the winter, you will want one of these sprinklers made from regulation motor-oil cans. The larger one, built from an ordinary quart container with the top left on, holds enough water for several pots. For the opening in the top, score the metal deeply with dividers and tear out the unwanted part with pliers. Punch a hole  $\frac{1}{4}$ " from the bottom on the opposite side for soldering on the  $\frac{9}{16}$ " spout, which can be made from a discarded auto gas line, any  $\frac{1}{4}$ " tubing, or a strip of tin-can metal rolled up and soldered. Cut a strip of the metal 2" by 15" for the handle, bend it as shown, solder the seam, and solder it to the can in two places.

The smaller sprinkler is made similarly except that only half of a can is used and the top is soldered on. It will be found convenient for small pots or a miniature indoor garden.



## NOVEMBER CHECK LIST

[SHIPSHAPE HOME]

1. Inspect radiators for leaks and repair them with iron cement.
2. Drain a hot-water or steam system and refill with fresh water.
3. Scrape and cement joints in the fire pot of a hot-air furnace.
4. Repair or replace defective furnace grates.
5. Clean soot from the nozzle and burner unit of an oil-heating system.
6. Renew deteriorated smoke pipe from furnace to chimney.
7. Clean out scale and soot in boiler and tubes.
8. Insulate between chimney and wood framing with mineral wool.
9. Cut off water from all outdoor fixtures, such as sill cocks, and drain them.
10. Calk all cracks in the basement where air leaks in.

POPULAR SCIENCE MONTHLY SHOP DATA

**For Pocketknife Whittlers . . .**

# ROCKING-HORSE BLOTTER

**Is Fun to Carve**

By ELMA WALTNER

**M**EET Hector Hobbyblot, a wooden (but not Trojan) horse whose happiest moments are spent riding hobby-horse fashion on unblotted ink or in standing stanchly atop a stamp box. A jack-knife job, Hector is well within the capabilities of inexperienced carvers.



Use any kind of wood you prefer, so long as it's easily worked. Lay out the profile pattern on a piece of 2" stock, with the grain vertical to give sturdy legs. Then cut out the profile and drill two or three holes between the front and rear legs to help remove extra wood.

The carving is done entirely with a sharp knife. Don't try for fine detail, since the angles and planes add to the attractiveness of the piece as well as making the carving easier. To insure proper proportioning, turn the work often in your hands and rough out the entire figure before finishing any part. Use sandpaper sparingly to preserve planes.

Finish all but the teeth with shellac; they are a gleaming white, with markings added by pen and India ink. Hector's eyes are white map pins painted with black pupils. His crowning glory, his coal-black mane, is achieved by drilling a row of small holes in his neck and gluing in tufts of black yarn.

For a blotter base, cut one piece of stock

$\frac{1}{4}$ " by 2" by 4" and one  $\frac{3}{4}$ " by 2" by 4". Round off the ends of the thinner piece and mount the figure on it with four small countersunk screws running from the underside to each hoof. Drill the hoofs first to prevent splitting. Shape the lower section of the base to a curve of about 8" radius and attach with two small screws running down from the upper section of the base. Use strips of blotter cut 2" by 6". If you wish, Hector and the upper portion of the base may be mounted on a stamp box.








## Test Your Skill with This New Double-Deck Skip-Ball Game

**I**F YOU pull the shooter back just right and release it with a steady hand, your first count may be 200. But if your technique falters, your next count may be a lowly 5. The game is played by shooting balls against the hurdle with just the proper impetus to drop them between the high-scoring dowels. Your turn at play consists of five shots.

The dowel nearest the player, in the bottom row, is numbered 1. The next nine dowels are numbered, in order, 2, 3, 4, 5, 10, 20, 30, 40, 50. Each number refers to the space in which a ball may rest between it and the next dowel behind it. Dowel No. 50 is  $\frac{3}{4}$ " from the end of the box. The upper three dowels have two scoring spaces, the

forward one counting 200, and the rear space 100. Scoring here takes practice and skill. The five balls are wood,  $\frac{3}{8}$ " in diameter.

The model of the game shown in the photograph is attractively painted in five colors. The cardboard bottom and both removable backstops are blue. The sidepieces, the two backboards, and the hurdle are red. Bright yellow covers the guide tracks, front end-piece, shooter dowel, and 10 lower dowels in the scoring area. The top scoring dowels and the ram on the end of the shooting dowel are green. Scoring numbers are lettered in black on the upper surfaces of the scoring dowels.—MYRON FLEISHMAN.



# how to get Better Light from Your Home Lamps



**POOR**



**GOOD**

Poor lighting from a small lamp can be corrected very easily by adding an extension base and by replacing the shade. The extension shown above is made principally from a mailing tube

How raising the lamp and increasing the shade diameter give better light dispersal is illustrated at the right


MANY a small electric lamp looks attractive in the store, but when you sit down to read or work by one, you may find that it is better to look at than to see by. Often the lamp is too stubby and the shade too small for proper lighting. Instead of discarding the lamp or putting up with poor light, specialists at the General Electric lighting research laboratories advise, simply make an extension base and use a shade with better proportions. These two steps will result in a substantial increase in the circle of useful light.

The extension base shown in the lower photo is a heavy mailing tube fitted with a turned-wood footing and filled with pebbles for weight. It has a cover recessed about  $\frac{1}{2}$ " to hold the bottom of the lamp. A small notch in the lip permits the cord to come out. An attractive extension base may also be turned wholly of wood in a design harmonizing with the lamp and bored all the way through for a wire entering at the bottom.

Lighting experts say that a single-socket table lamp, with its recommended 100-watt bulb, should afford comfortable seeing within a 24" radius of the base. Whether or not this coverage is achieved, however, depends upon dimensions A, B, and C in the drawing. A squat, tightly shaded lamp has a relatively small useful light circle.


If B is lengthened to from 13" to 17" by an extension base and C is increased by a larger shade, the maximum useful dispersal can thereby be obtained. A should be as small as practicable, with the lower edge of the shade, viewed at eye level, covering at least part of the socket.

To obtain efficient reflection of light, use a shade that is lined with white. It is also desirable to select one that is fairly dense so as to reduce direct transmission of light to the eyes.





**DIRECT PAPER NEGATIVES MAKE ARTISTIC PRINTS...**



This original negative was made with paper in the camera instead of film. An extra-thin grade of single-weight paper was used here

# Filmless Photography

**SHOOTING NEGATIVES  
ON ENLARGING PAPER  
IS GOOD FUN AND WILL  
BRING REAL RESULTS**

**E**XPERT photographers desiring to produce highly artistic and dramatic photographs have long used the paper-negative process. This consists of making a positive print from a film and retouching it, and then making a negative paper print from the positive for further retouching, after which a finished photograph is finally secured by a print or

enlargement made from the paper negative.

Without going through all these steps, and without using film at all, you can get just as fine results. You can make your first negative on enlarging paper in your own camera, and work directly on that, printing your final positive from this lone negative. It is a simple process and is a lot of fun. Enlarging paper is much cheaper than film, and by using it instead of film, you eliminate expensive waste on questionable shots and can also make a lot of pictures you might otherwise pass up because of the cost.

And not to be overlooked is the opportunity to do really thorough and artistic jobs of retouching. Working on a paper negative, the camera enthusiast has a chance to try many effects, rubbing out those that prove least desirable, altering high lights and shadows, and finally bringing the nega-



Either contact prints or enlargements may be made from the paper negative, which may be retouched for special effects

By KONRAD CRAMER

## with Your Own Camera

tive to perfection, confident that erasures, pencil marks, and the like will not show up on the finished print.

Probably still more satisfying is the fact that you can know the results of your picture taking within a few minutes of snapping the shutter, for the whole photograph is unfolded for you as you develop the paper negative. As soon as it is dry, if the shot was a good one, you can begin retouching the paper negative to bring out desired effects, and then print your positive photograph from this negative.

To use this type of direct paper negative, cut the enlarging paper to fit in the back of your camera. Loading is similar to that of plate or film-pack cameras, but only one paper negative can be loaded at a time. If you have a roll-film camera, cut the paper for single negatives and load as you would

for the other types. It is not always necessary to do the loading in a darkroom, but a subdued red-orange light is essential.

For best results in taking these pictures, use single-weight, soft paper and expose it under strong light. The larger-size cameras, 3½" by 4½" and up, are ideal for this method. For my own purposes, I use lightweight paper in an 8" by 10" studio camera with which I can get a negative that requires no enlarging. Add to your equipment two or three photoflood lights, and you can make portraits of unusual quality if you can find a model who will hold still for 10 to 15 seconds. This exposure is usually necessary to get a good paper negative. If a comfortable pose is selected, most people can sit still that long with little trouble.


Still life is ideal material for direct paper negatives. Landscapes, with or without





Dramatic silhouettes with high lights and deep shadows for both figures and background, as shown in the photograph above, are created by retouching both sides of a paper negative before it is contact-printed or enlarged as desired

Portraiture of distinction is possible on paper negatives if the subject will hold a pose for as long as 13 seconds




figures in the foreground, are also good. Sometimes you will find that the negative itself has great pictorial charm. In such a case, there is nothing to hinder you from mounting and exhibiting a negative.

The paper negative can be retouched on both sides, using a ground glass and light when working on the back. Light tones, modulations, and additions may be added by building up the wanted values with any soft pencil or crayon and then shading with a stump. Large areas may be handled with a bit of chamols and powdered crayon. Dark tones and accents in the final print can be produced by lightening parts of the negative with local reducer or by carefully rubbing them down with powdered pumice. Major blemishes and faulty backgrounds can thus be corrected.

Some photographers using this process content themselves with only a slight softening of the image, caused by the printing light having to penetrate the paper instead of transparent film, plus a few slight retouching corrections. It seems best to go easy in the beginning so that most of the original character of a photograph is retained. Overworked paper negatives may take on the final appearance of a poor drawing, a result that is to be avoided.

Paper negatives can be enlarged or contact prints made from them. Extra-thin paper should be used in the smaller cameras as it gives a very pleasing texture effect when enlarged. The general effect of the enlargement is diffused, in contrast to the sharp definition of contact prints, yet the enlargement often has simplicity and distinction.

The writer made an 8" by 10" cardboard camera, using an ordinary magnifying glass as a lens, two cartons telescoping into each other, and a piece of ground glass which is interchangeable with a printing frame. If you make up such a camera for yourself, you'll be set for some inexpensive and distinctive photography, for paper negatives afford many ways in which to achieve a controlled artistic effect.




**NIGHT AND DAY** can be dramatically portrayed in the same picture by using a simple duplicator attachment. Build a box that can be secured to the front of your camera, fitting it with two vertical doors. Aim at a scene that will afford interesting day and night contrast and take, say, a day-

light picture with one door closed. Leave the camera untouched until nightfall; then open this door and close the other to make a second exposure on the same film. With a film-pack camera, just block off half the film with cardboard inside the camera, and reverse it between shots.—LOUIS HOCHMAN.


**PORTABLE FLOODLIGHTS.** Good indoor pictures require adequate lighting, particularly if color film is used. Shown at right is a compact case, only 8" by 11" by 16½", which holds six photofloods, complete with reflectors and extension cords. The case divides into two three-lamp banks of No. 1 photofloods which can be used separately on the floor or on tables or can be hung from picture molding.

As shown in the drawing, the cases are made from thin wood and the reflectors are ordinary white enameled oven pans, fastened to cleats inside each case. Sufficient air space should be allowed so that the cases won't get too hot. Air holes are cut behind the pans to provide ventilation.

In using the outfit, remember that six No. 1 photofloods will load a 15-amp. circuit to capacity. The 18-gauge extension cords should always be plugged into wall outlets, never into lamp sockets.—PAUL KOMROFF.







# DUMMY CAMERA

## Focuses Copying and Close-up Shots


**A**N INGENIOUS copying and close-up outfit, especially suitable for roll-film cameras which lack ground-glass focusing, may be built of wood scraps, a ground glass, and two lenses.

The principle is simple. A vertically sliding camera holder contains a supplementary lens, while a cardboard dummy camera has a lens of the same focal length as the camera lens. The dummy camera, which has ground glass instead of film, is used while adjusting the camera holder to sharp focus, after which the real camera is put in position and the picture snapped.

Design the camera holder so that the camera will always assume the same position when laid on it. The supplementary lens may be a regular copying or portrait attachment, or one of the chipped-edge lenses now available at low cost.


Make the dummy camera out of cardboard, proportioned so that its lens, when the dummy is in the camera holder, occupies precisely the position which the real camera lens would occupy. The lens in the dummy need not be of high optical quality, provided that its focal length approximates that of the camera lens. Mount a piece of ground glass in the dummy at the plane of sharp focus for objects more than 200' distant. The camera field may be located on the ground glass in this manner: Put a piece of ground glass (rough side down) on the film aperture of your camera, focus at infinity, and then put the camera in the stand. Adjust the height until a sheet of newspaper tacked to the easel is in sharp focus and note the area covered. Then put the dummy in place of the camera and mark the same field on the ground glass.

To take a picture, focus with the dummy camera and supplementary lens in the holder. Replace the dummy with the real camera, which should be focused for infinity and stopped down to  $f/16$  or  $f/32$ , and make the exposure.—ERVIN WALTERS.



The cardboard dummy camera, below left uses a lens with a focal length equal to that of the lens in the real camera. Note that the field limits are indicated on the ground glass. The other pictures below show how the supplementary lens and dummy are inserted in the holder. Different auxiliary lenses may be used






**LETTER ALBUMS** which combine space for six snapshots and two 4½" by 8" writing surfaces are now on the market. Excellent for sending photos to service men, the folded letters protect pictures in transit, and may be used on receipt as pocket albums.




**EXPERIMENTAL LENSES** of different focal lengths and diameters may be bought in sets priced so that a single lens costs but a few cents. Though ground and polished, they are inexpensive because small chips on the edges make them commercially unacceptable. They may be used as supplementary lenses for close-up or telephoto work and for making ground-glass or enlarging focus magnifiers, color-film viewers, and telescopes. Instructions come with the sets.



**PORTABLE DARKROOM** equipment, compactly arranged in an easily carried case, is now being made for the armed forces. Similar models are planned for postwar civilian use. Besides chemicals, paper, trays, and a daylight developing tank, the case holds a timer, safelight, thermometer, easel, and an enlarger that can be powered by a car battery. It also has space for a camera, flash synchronizer, and filters.

**HOT-WEATHER DEVELOPMENT** of films is said to be easier and safer with certain new chemical solutions. Films can be processed in temperatures that range up to 100 deg. F. without risk of softened emulsion or reticulation. The temperature-resistant solutions include developers, hardeners, and fixers. Photographers working in hot weather in temperate zones, those in the tropics, or those using make-shift field darkrooms will find the chemicals of special value.







**H**OMEMADE attachments and jigs will greatly extend the uses to which a small bandsaw can be put. They make possible accurate cutting of tenons, automatic sawing of irregular curves, thinning of stock for bending around forms, and other types of jobs.

*What is a setup for cutting tenons?* First cut the cheeks, or sides, of the tenons. To guide the work, clamp a piece of straight square stock to the table for a fence parallel to the line of sawing. This fence must be high enough to support the work accurately with the face side in a vertical plane. The distance from the fence to the saw blade is such that the kerf will be made in waste wood with its far side forming the tenon cheek. This distance should be established by making trial cuts in scrap wood. Clamp a block to the fence where it will stop the forward motion of the work when the cheek is cut to length.

With this setting, saw one cheek of all like tenons, sliding the face side against the fence. If the pieces have parallel edges, they may be turned end for end, with the face sides kept against the fence. The position of the stop block is shifted if the tenons differ in length.

If the pieces are equal in thickness, their opposite sides may be put against the fence when the other cheeks are sawed, but if the thickness of the stock varies, such reversal will make the tenons either too thick or too thin. In this case, the fence should be reset to keep the face sides of the pieces against it. Shifting of the fence can be avoided if it is first set to cut the cheek opposite the face side. Then a shim of proper thickness may be inserted between the fence and work for sawing the face cheeks.

To cut the shoulders, as shown in one photo and in the sketch, clamp a stop block to the table at right angles to the blade. Also clamp on a length block to locate the tenon ends. Rest the piece to be cut on edge, rock the upper edge toward the stop block, and slide the lower edge forward until the blade severs the waste. As

Special Jigs and Attachments  
ADAPT  
**Your Bandsaw**  
TO MANY USES  
By EDWIN M. LOVE

before, use test cuts when setting the blocks, and make allowances for variations in stock thicknesses.

These methods apply only to comparatively short stock cut to exact length. Trim the tenons to width with similar setups, but with the face sides lying on the table. Trim the shoulders freehand or use the miter gauge.


When through tenons are made, cut the pieces roughly to length and use shoulder stops to locate the shoulder cuts for the second tenons after the first ends are cut. This assures accurate shoulder-to-shoulder measurements and correct frame dimensions after assembly. It is a good method to use even when the stock is precut to length. If the bandsaw is equipped with a metal fence, screw a larger auxiliary fence to it so as to give a firm support when wide work is handled.

*Of what use is a trough jig?* This is a jig in which a piece of square stock can be supported cornerwise with the diagonals vertical and horizontal. The construction is shown in the drawing. Make a center kerf

at one end and notch one side. A typical use of this jig is in scoring the ends of a turning square to give bite for the live center of the lathe. Clamp the jig to the table with the blade in the end kerf and feed the turning square against the saw, cutting about 1/16" deep. Turn up the other diagonal and repeat.

With the same jig clamped to the table so that the blade enters the wider side notch, it is possible to trim off the corners of built-up table legs. This saves turning time in roughing down the bulbs on post-blocked turnings and the like.

*How is part of a rail sawed thin?* Clamp the work to a heavy squared piece. Notch the inner face where the bend is to begin and make a kerf at the end. The slot can be made with several bandsaw cuts and a sideward motion to break out the waste. The blade is then entered to rip out the required portion. Cut the thin section an extra 1/2" long to allow wedges to be driven in for tightening. This method of clamping the piece to a heavy squared piece of stock is useful on many jobs since it gives ade-







A rail being thinned to allow bending is clamped to a 3" by 4" piece permitting freehand guiding




Accurate shoulder cutting is assured with stop and length blocks to control the depths of tenon cuts

quate support when freehand cutting is done.

What can be done to correct saw-blade lead? If the blade doesn't lead true, it can often be improved by holding an oilstone lightly against the side to which it leads while the saw is running, thus reducing slightly the set of the teeth on that side. A little lead is of no consequence in freehand

work, and the fence can be quickly adjusted for ripping to make it parallel to the line of cut, but when a miter gauge is used, difficulties due to wedging may be encountered. Sometimes this can be corrected by loosening the table mounting screws sufficiently to allow the table to be swiveled by light mallet taps on one corner.

How are self-guiding jigs made? The drawings illustrate a basic type. The size depends upon the design to be cut. The lower, or fixed member, has cleats beneath it to locate it on the saw table, and it has a saw kerf to allow entry of the blade. Set a guiding peg in the fixed member in front of the blade, and if the curve to be cut allows, add another peg behind the blade. The




At the left is a sketch of a jig for sawing several layers of plywood at one time. Before cutting, make sure all pieces are up against the stops. A sliding pin guides the work as it is sawed, thus eliminating layout and producing accurate work at the same time




upper member of the jig is a sliding form with one or more guide slots cut in it. These must be accurately made, with no more than free sliding clearance on the pegs, and they must be long enough for the blade to run free in front of and behind the parts to

be cut. Screw on stop blocks, as detailed, and also hardwood bridging strips to stiffen the slit ends of the jig members. Place the stock to be cut against the back and side stops of the sliding member and push forward until stopped by the peg.

## Stop Rod Prevents Creeping of Miter Cuts on Circular Saw




MAKE a  $\frac{3}{4}$ " hardwood block as long and as high as the face of the miter protractor. Set two countersunk bolts in one side of the block, with nuts set flush on the other side. Let the bolts extend  $\frac{3}{4}$ " to go through holes in the miter gauge, where they are attached with two extra nuts. Cut a groove in the bottom of the block for the stop rod. A vertical hole takes a bolt having a hole drilled through its lower end to let the rod slip through. When the wing nut on the upper end of the bolt is tightened, the sliding rod, with a right-angle bend at the end, is locked and holds the work from creeping. If you make rods of various lengths, you can handle many sizes of work.—B. B.



## BRACES AND COMMON RAFTERS

[ SHIPSHAPE HOME ]



The plumb and level cuts of a common rafter are determined by the rise and run of the roof pitch. The rise is the vertical distance between the plate and a point on the plumb cut which is located by extending a line along the rafter, parallel to its edge, at the depth of the plate notch. The run is the distance from the center to the outside of the plate. This is usually expressed in terms of inches rise per 12" of run. The sketch illustrates 8" in 12".

Lay the square on the stock with the figures coinciding with the crowned edge. A line drawn along the tongue is the guide for the plumb cut, and a line drawn along the blade is a guide for the level or heel cut.

The plate notch is usually cut 1" deep on the plumb for 2" by 4" stock. On wider rafters, cut deep enough to provide a 2" or greater bearing of the heel on the plate.

The same principle applies to cutting butted braces.

POPULAR SCIENCE MONTHLY SHOP DATA



# Modern Cabinet Conceals



**1** Wood extensions are attached at the sides and back of the machine top with the help of cleats


## NEW DRESS PROMOTES IT

By Charles and Bertram Brownold

**D**USTED off and rehabilitated, many old-fashioned sewing machines are doing yeoman work to help the family budget. With a new dress to hide ugly Victorian lines, yours may be brought out into the open where it will be easier to get at when there is mending to be done or new clothes to be made. The simple wooden cabinet shown can be made for any drop-head model



**2** Use of a plumb line shows the back projects beyond the ironwork



**3** Drawer cabinets of plywood attached to rectangular frames are screwed to the sidepieces and wooden parts of the machine



**4** Corner blocks lock matching ones on a front panel, while others hold the cabinet to the frame



**5** Sliding bolts made of hardwood dowels lock the top of this detachable panel to the cabinet

# Old Sewing Machine

## FROM ATTIC TO PARLOR

and will double as a living-room chest or desk, a dining-room sideboard, or a bedroom dressing table.

Discard the old drawers and attach a 2" by 3" piece to each end of the table, as in Fig. 1, rabbeting the inner edge to fit the routed edge of the top. Set the upper surfaces and ends flush and fasten on the underside with thin hardwood cleats, such as those shown in Figs. 1 and 2. The backs of the top drawers that will be installed later



6 These dowel bolts are screwed to the handles through slots in the panel that permit sliding



7 With its new dress completed, the old-fashioned machine becomes an attractive piece of furniture



Top and front panel removed and its dropped head lifted, the old machine does a good job of sewing

are cut down about  $\frac{1}{2}$ " to allow them to slide past these cleats.

It may be necessary to attach similar extensions to the front and back if the metal frame projects beyond a plumb line held from the table edges (Fig. 2). On the machine used here, an extension was needed only at the back since all parts at the front were within the plumb line.

For each of the side drawer cabinets shown in Fig. 3, you need two  $\frac{1}{4}$ " plywood panels and four rectangular frames. These frames, of  $\frac{3}{4}$ " by  $1\frac{1}{2}$ " stock, must be the same size and accurately squared. They have lap joints glued up under pressure. The plywood panels are attached to them






Above the machine serves as a dressing table when not used for sewing, and at right as a desk. Some details that will aid in construction are shown in drawings at the upper right

with countersunk screws driven in from the outside

The inner panel of each cabinet is held tightly against the iron frame by fitted hardwood blocks at the bottom, as illustrated in Fig. 4, and at top it is fastened by screws to the woodwork of the machine.

Openings should be cut in the plywood to accommodate any projecting parts of the ironwork. The outer panels are about 1" longer than the inner, and their upper ends are fastened with screws to the table-top extensions. One piece of plywood is fastened across the entire back of the machine.

Stock 1" thick is used for the drawer fronts, the sides of which are rounded off as shown in the photographs. The deep bottom drawers—spacious enough to hold both materials and work—have fronts made of two pieces so that when closed each appears to be two drawers. All the fronts are deeper than the drawers themselves, covering the frames upon which the drawers slide, and are wide enough to be flush with the cabinet sides. The bottoms are plywood glued into rabbets  $\frac{1}{4}$ " from the lower edges of the fronts, sides, and backs. Draw-



er pulls 3" long are made of 1" hardwood dowels flattened on one side and fastened with screws from the inside.

When the machine is not in use, the top is covered by a lid having pegs that fit into holes bored in the table-top extensions. The lid is made of  $\frac{1}{4}$ " plywood and quarter-round molding held together by  $\frac{3}{4}$ " strips, as shown in a drawing, and on the front is a 1" plywood strip concealing that part of the sewing-machine top between the two drawer cabinets.

The treadle and driving wheel are kept from view by a plywood panel (Fig. 5) that is removable. Hardwood blocks near each lower corner of the panel and on the lower corners of the drawer cabinets hold this removable piece at the bottom (Fig. 4), while sliding hardwood bolts fasten it at the top. These bolts (Fig. 6) are made of 5" lengths of 1" hardwood dowels and are attached to handles on the outside with wood screws extending through slots. The bolts slide into holes bored in the drawer cabinet walls.



Either paint or stain may be used as a finish. Before painting, fill all exposed countersunk screws in the side panels with a hard-drying filler. If a stain is used, it will be necessary to glue a thin veneer panel over each side panel to cover the screw heads. The drawer fronts should be made wide enough to allow for this.

## Model Maker's Turning Tools Are Ground from Small Files





FOUR excellent wood-turning tools, especially suited for model making and other small-scale lathe work, can be ground from two worn-out 6" round files. Break the files in a vise so that the pieces are of about equal length (Fig. 1) and grind them until they are rectangular in shape as shown in Fig. 2. The pointed ends need only be rough-ground (Fig. 3) since they will fit within the handles, but the exposed portions should have all file marks removed. Be sure that the surfaces which will bear on the lathe rest are ground smooth.

The cutting points should be shaped with particular care to secure the angles shown in Fig. 4; use a grinding jig if one is available. Handles can be made from  $\frac{5}{8}$ " birch or maple dowel. Ferrules are not necessary if the handles are drilled out sufficiently before the tools are forced in. Finish the cutting edges on an oilstone to razor keenness. If you wish to make a set of larger tools, pillar files will need less grinding than larger round files.—C. W. BERTSCH.



## Discarded Razor Transformed into Keen Whittling Knife

A WHITTLING knife that will hold an exceptionally keen edge can be made from an old straight razor. Since the original shaving edge is too thin for its new role, it should be ground back about  $\frac{1}{4}$ ". Do not remove more than is necessary to thicken the edge slightly, because many razors are tempered only part way back from the edge. Take care not to "burn" the steel. Grind the entire blade to the shape shown in the drawing at the right, reducing the thickness at the back if desired. Use hardwood or a piece of  $\frac{3}{4}$ " birch dowel for the handle and attach a ferrule of seamless brass or copper tubing. If such tubing is unavailable, a discarded kitchen fork or spoon will probably yield a ferrule. Restore the knife edge to razor sharpness on an oilstone and make a leather or wooden sheath to fit the blade, as shown in the photograph.—C. W. B.





# KEEPING THE HOME



Most people prefer to have a furnace-regulating thermostat installed in a spot where it will not be noticeable and yet will serve efficiently. This often means that insufficient light will fall on the dial for accurate setting. Squinting in a dark corner and guesswork regulation of your heat can be avoided, however, by having a small notch filed in the dial face at the temperature or temperatures most frequently desired so that the exact setting can be made by touch alone. A small triangular notch like the one shown above can be made quickly with a three-cornered file.


When loose ration points are received in change, a good precaution against their loss is to place them in an envelope pasted on the inside of the ration-book cover—a convenient, safe receptacle



Furniture casters won't stick to a floor and mar its sheen in very hot weather if a thin coating of floor wax is applied to the wheels. In damp weather a little wax put in the sockets of the casters will keep them rust-free and free-turning.




If you need to lubricate machine parts so placed that they are hard to reach, and an oil can with a long spout is not available, try using a soda straw on the end of the spout for an extension.



Screw one leg of a spring-type clothespin to the inside of a drawer for keeping letters, b.l.s., and receipts where they can be found when wanted.

One way to get a broken key out of a lock is with a piece of jigsaw blade. Push the blade into the lock with the teeth pointing outward, twist it so they will be at right angles to the key and pull




# SHIPSHAPE



If members of your family or office staff absent-mindedly pocket a key that should be left for others to use, put the key on a ring that is too big to go into a pocket




In an emergency, a very satisfactory washer can be made for a faucet by removing the metal from the center of a round typewriter eraser. The hole will fit the screw, and the rubber can then be pared to proper size




Milk bottles can't be kicked over and broken if they are held in this sturdy wall bracket. Make enough holes for your needs, and slant the back edges of the ends if your house is of clapboard

Friction tape is likely to dry out and lose most of its adhesiveness when removed from an original wrapper. Use an empty shoe-polish can as a handy, airtight container in which tape will keep fresh




Service-worn clothes wringers can be given many a day of extra life if the rust and discoloration that come in time from their iron roller cores are eliminated. These stains result from water that has seeped into the cores through the frayed and loosened rubber at the ends. A repair may be effected by removing the rollers from the wringer and fastening paper collars around the worn ends. The rollers can then be sealed against water and secured against rust if melted paraffin is poured into the collars. Gears and bearings should be cleaned with gasoline and coated with light grease

Bolts may be made to hold in concrete by winding the threads with wire, inserting them in drilled holes, and filling the space left with cement. They are withdrawn and reinserted with a wrench









Made entirely of hardwood with the exception of screws, this drop-type latch is designed for use on a home-built cabinet or cupboard. Its pivoted moving part is cut out as shown in the drawing.

The sliding bolt shown below, also of wood, is another distinctive latch. The bolt itself is a piece of hardwood dowel, while the remainder of the latch is made up from a block of grained stock. Care should be taken that the grain of the two halves match or form a pleasing contrast.



# Wooden Hardware Gives Cabinets


## LATCHES AND HINGES MADE FROM NICELY GRAINED STOCK

By FRANK WHELOCK


**B**EAUTIFUL latches and hinges that blend so closely with the grain of your home-built cabinets and cupboards that they seem to grow out of the wood can be made from small bits of matching hardwood. Others that will have as interesting an effect and add to the distinction of a piece may be turned out by the craftsman from contrasting woods. Many designs are possible, from the simplest lines to highly ornamental carvings, and any will be pleasing so long as the fittings are in keeping with the piece on which they are used.

Illustrated are two latches and two hinges for a cabinet door. The dimensions are suitable for many pieces, but the plans are intended primarily to give an idea of what can be done with hardwoods and to form a basis for designs of your own creation.

Care should be taken to have a pleasing flow of grain in adjoining parts, or else the grain of two pieces should be turned so that the contrast will be arresting. The two parts of each of the latches shown may be cut from the same piece of stock to obtain a flowing grain, or a small block can be sawed down the center with the grain for



With a length of dowel used as a pin, this wood hinge is strong enough for a cupboard



Another design for a hinge suitable for a door that has greater width than height

# New Character

## FOR HOME-BUILT PROJECTS

a perfect match. In the latter case, the inside faces are exposed, and the abutting ends are placed to let the grain coincide.

One of the latches illustrated is of the drop type with the moving part pivoted inside one of the halves. This part may be of dowel, shaped at the top as shown in the drawing. It is raised to unlatch the door and dropped into a slot in the corresponding half to hold it shut. The other latch has a sliding bolt cut from a hardwood dowel, while pieces of hardwood dowel also form the pins of the hinges.

Finishing will depend for the most part on the finish of the piece on which the fit-

tings are used and also on the kind of hardwood from which they are made. In many instances, the finish desired will probably be one that will emphasize the wood grain. It should be put on in any case after a trial fit and before final assembly so that no unfinished corners will show in the exposed moving parts. Before the pieces are permanently assembled, all moving parts and contacting surfaces should be waxed and rubbed well. Parts of this kind that do not show, such as the hinge dowels, will need no finish except a thorough waxing. If it should be decided to use paint, don't paint parts between which there is friction.






## CUTTING GEARS on the MILLING MACHINE

ONE of the oldest and most common methods of cutting gears is on the milling machine, which is still extensively used despite the fact that other machines designed specifically for gear cutting can do the job faster. Gear hobbers, shapers, and planers, for instance, can be set up for mass production of various types of gears, such as spur, helical, bevel, spiral, and herringbone gears.


Before using any of these machines, the operator should have a knowledge of the fundamentals and nomenclature of gear-tooth design. Reference to a good handbook will enable him to set the machine to the correct speed and feed for the type of gear to be cut and for the kind of metal of which the gear blank is made. It will also allow him to check on the blueprint to be sure that none of the dimensions are contradictory. In addition, he should check the cutter to be used to make the gear with both the specifications given in the blueprint and the data in the handbook.

Actual setting up of the milling machine for gear cutting and its operation, along with important points in gear design, have been made the subject of one of the series of motion pictures used by the U. S. Office of Education for training machine-tool operators. Frames from this film, which is distributed for the Government by Castle Films, appear on the succeeding pages.


In setting up the milling machine, be sure to place the outer-arbor support as close to the cutter as possible without danger of the gear blank striking the cutter. If the distance between this support and the machine column is too great, the cutter arbor will spring upward under pressure of the cut and result in teeth of uneven depth. For the same reason, a table jack is used to support the gear blank for the fairly heavy roughing cuts. Just how important it is to keep the cutter arbor and the gear-blank mandrel steady can easily be seen when one considers that the clearance of an 8-pitch gear of 36 teeth is only .0195".




**1** On gears, the pitch circle cuts the working center of the teeth, addendum and dedendum are equal, and clearance is added to give full depth of tooth. Diametral pitch is used in calculations



**2** Here is the job. Cut 36 teeth in a gear blank machined to dimensions in the blueprint. The center hole is drilled and reamed so the face will run true when the gear is mounted on the mandrel





**3** Since the shape of the teeth is to be involute, refer to the involute-system table of cutters in a handbook. A No. 3 cutter will provide this shape when the number of teeth is from 35 to 54



**4** Specifications are stamped on the cutter. Here the diametral pitch (8), the number of teeth (35-54), and the full depth of tooth ( $D+f=0.270$ ) meet the requirements of the blueprint for the job

**5** The blank below has been set up and notched for 36 teeth following a trial setting of the dividing head (see P.S.M., Oct., p. HW 481). A table jack keeps the mandrel steady during cutting

**6** One roughing cut and a finishing cut of  $1/16$ " will be sufficient for teeth of this size. To determine the depth of the roughing cut, subtract  $1/16$ " from the full depth of tooth (continued)








**7** As the first step in setting the machine for the depth of the roughing cut, the cutter is slowly rotated while the table is raised by hand until the cutter barely scrapes the gear blank



**8** At this point, the index dial on the handwheel that moves the table vertically must be set at zero. Each division on the dial represents .001" and a complete revolution raises the table .100"



**9** Run the table forward so the gear blank will clear the cutter; then raise it .207" for the roughing cut. This is accomplished by two full revolutions plus seven divisions on the index dial




**10** Cutter speed is next calculated. Since the gear is cold-rolled steel, a speed of 90' per minute is required at the cutter teeth. Dividing this by the cutter circumference gives 115 r.p.m.

**11** On most milling machines, the cutter or arbor speed can be set by a speed selector. Below, the speed dial is set at 116 r.p.m., the nearest speed of this machine to that required for the job

**12** Feed, the speed of the table movement, is now determined. The 12 teeth of the cutter will remove 12 chips .002" thick in one revolution, so the feed should be 116 r.p.m. multiplied by .024"





**13** This gives a feed of approximately  $2\frac{3}{4}$ " per minute, at which point the feed-selector dial is set. It represents the distance in inches per minute the gear blank will be fed into the cutter



**14** With the depth of cut, cutter speed, and feed set, take the first roughing cut, being sure to use an ample supply of cutting fluid; then stop the machine when the cutter just clears the blank



**15** Set the table stop dogs to limit its travel at the point where the cutter clears the work. This keeps the cutter from traveling far enough to damage the dividing head and also speeds the job



**16** Stop the table at the end of each reverse stroke and index the blank for the next tooth according to the dividing-head setup. Due to backlash, indexing must be continuous in one direction

**17** When all 36 teeth are rough-cut, raise the table  $1/16$ " and make a finish cut; then index one space to finish the second face. Check width at the pitch line with gear-tooth vernier calipers


**18** Cutting depth is adjusted, if necessary, to correct the pitch-line width. Indexing then proceeds forward for the rest of the gear. Cuts are light, and the table jock is no longer needed





## New SHOP IDEAS

**BLUEPRINTS** remain cleaner and last longer if they are kept off workbenches and left uncreased. One foreman lengthens the life of shop drawings by stapling two shipping tags behind the top edge of each as shown below. The blueprints can then be hung on two screw hooks over the workbench or machine where they are needed. A large number can be stored on two long curtain-rod hooks. If staples are not available, the tags can be attached with glue.—RONALD EYRICH.



**AIR PRESSURE** speeds air power to smash the Axis. In the Fisher Body Division of General Motors, an ingenious trick suggested by Russell Dudley, an employee, has cut by 17 percent the time required to install electric wires in horizontal stabilizers. This was formerly done by first pushing through piano wire, which frequently caught at sharp bends in the conduit. Dudley's method is to tie the electric wire to a piece of string, blow the latter through with compressed air as shown below, and then pull the wire through.





**IN SOLDERING**, a hot iron put down hastily or carelessly may char the bench or table top. If a spring-type paper clip is previously put on the tool just behind the head, such damage will be avoided. Spread the grips of the clamp slightly to afford a broader support.—W. SWALLOW.



Courtesy Grift and Grinds, a Norton Company publication.

**WORN PIPE WRENCHES** can be restored to service by regrinding the teeth on the jaws. This can be done by hand on any bench grinder equipped with a 100 or 120-grit, medium-grade wheel running at 5,000 surface feet per minute. The wheel face should have one sharp and one rounded corner, the sharp one to grind to the root of the teeth and the rounded one to provide clearance when teeth are being ground close to the shank of the jaw. It is usually the teeth on the movable jaw that require sharpening. The angle between teeth is generally 100 deg., and this should be preserved as closely as possible in regrinding. A dull wrench can usually be reconditioned in this way in a few minutes. Teeth can be re-sharpened several times if care is used, the depth of hardness and the amount of metal removed on each occasion being the only limitations on the life of a wrench so reconditioned. A simple file test will show whether the teeth are still hard; a triangular testing file should just bite enough not to slide over the teeth.



## Shop Marking Gauge Has Replaceable Scriber

By C. W. WOODSON

**F**ITTED with a phonograph needle as a scriber, the gauge shown above will be found useful in making extremely accurate layouts on metal. Continued fineness of lines is assured since the needle can be changed when it becomes dull. The gauge is particularly suited to shops where aluminum sheet or steel plate is worked, but it will be a handy accessory also for many operations in home workshops.


Chucked as in Fig. 1, a short piece of 2½" shafting was turned to make the base. A center hole was then drilled in the end for tailstock support, and the handgrip was knurled as shown in Fig. 2. During this operation, the tool should be kept flooded with oil, and the knurls should be sunk deeply enough into the work to make a perfect diamond pattern.

With the knurling complete, and the work still in the chuck, a hole was drilled through and reamed to the diameter of the spindle (Fig. 3). Then a hole for a thumbscrew was drilled and tapped 10-32 in the side of the gauge, and the thumbscrew was turned and threaded on the end of a ¾" rod. The head was knurled, and the complete screw was finally cut off. An 8" length of drill rod forming the spindle was faced square at each end and drilled to receive the scribing point and a setscrew to hold it securely,

Detailed specifications for the metal-marking gauge







## SMALL ELECTRIC

# Resistance Furnace

## HAS MANY SHOP USES

By Walter E. Burton

**T**EMPERING small tools, bluing metal parts, melting lead, and baking enameled pieces are just a few of the uses to which this efficient little furnace can be put in the small shop or laboratory.

A resistance coil of the kind used in electric heaters and toasters forms the heating element. Such an element can be purchased at an electrical supply house or salvaged from a discarded appliance. The furnace shown, designed to reach temperatures up to 1,000 deg. F., has one that draws 520 watts. Higher temperatures can be obtained by using a 1,000-watt element, or by making the heating chamber smaller.

Two concrete-asbestos shingles  $\frac{1}{2}$ " by  $9\frac{1}{2}$ " by 24", either smooth or textured, are needed for the furnace chamber. With a hacksaw, on a jigsaw, or by scoring the material with an awl and breaking it over an


edge, cut six rectangles measuring  $1\frac{1}{4}$ " by 6". Cut also a hexagonal bottom measuring  $1\frac{1}{4}$ " on each side.

A jig such as that shown in Fig. 1 will speed the work of drilling a  $1/16$ " hole  $\frac{1}{2}$ " from the end and  $\frac{1}{4}$ " from the edge at each corner of these pieces. Center a similar hole  $\frac{1}{2}$ " from one end of each to receive an S-shaped hook for holding the resistance wire. If you intend to use a crucible in the furnace, particularly a metal one, drill a hole in the center of each piece to take a 6-32 screw. Left long enough to project about  $\frac{3}{8}$ " and secured with nuts, these screws will prevent the crucible from touching the element.

Link the rectangles together with small wire loops as shown in Fig. 2, with all the centered holes on the same side.

The coil hooks can be made of iron, copper, or nichrome wire. Insert the lower ones in the holes drilled for them and the upper ones through the links holding the pieces together. Drill a hole near the upper corner of each end rectangle to secure the two ends of the resistance wire. Measure the distance the wire will have to stretch, pull it out to slightly less than this length, and mount it as in Fig. 3.

With the element in position, fasten the two end rectangles together and insert the hexagonal bottom, securing this with some



black furnace cement. Wrap a strip of asbestos paper around the outside of the unit as shown in Fig. 4. Tie this with wire.

Expanded mica, rock wool, or similar fire-proof insulation material is used to line the furnace body, which may be a 2-gal. crockery jar or a metal can or bucket 8½" in diameter and as deep. Pour enough of the insulating material over the bottom to bring the heating chamber even with the top of the housing as in Fig. 5; then pour more insulation around the sides, tamping it firmly.

The connecting wires should be of the asbestos-covered type, but may be bare for the last 2" inside the crock if well separated. Secure them outside with a grooved wood or fiber block and a wire as shown in Fig. 6.

From the same asbestos abingle material, cut a disk to fit the crock with a hexagonal opening to accommodate the top of the heating chamber, as in Figs. 7 and 8. Add insulating material to within ¼" of the top and fit this cover in place. A 7" disk of the same material fitted with a metal ring or knob serves as a lid for the furnace.

Work should rest on a platform of fire clay, firebrick, or metal about halfway between top and bottom. Some pieces may be suspended on wires from a rod laid across the top. For accurate temperature control a pyrometer should be used. The finished furnace ready for use is shown at the right.







Photo courtesy of Westinghouse

# How the Vacuum-Tube Grid

By JOHN W. CAMPBELL, JR.

**U**SEFUL though the diode is in its various applications, it was not until Lee De Forest in 1907 inserted that simple third element—the grid—between the cathode and plate that the vacuum tube came into its heritage. That controlling grid has made it the indispensable tool not only of electronics, but also of physics, chemistry, medicine, metallurgy, and astronomy. It has rendered the electron the servant of industry instead of a plaything of the laboratory.

A diode passes current whenever the plate is positive with respect to its electron-emitting cathode. That plate-circuit current can be increased or decreased in just two ways: by controlling the emission of electrons (which in a thermionic-cathode tube can be done by varying the cathode temperature) or by altering the positive potential on the plate. Either method requires comparatively large current changes, such as we can bring about by the use of variable resistors,

as in Fig. 1 in the drawings on page HW 558.

Suppose, however, that we inserted a miniature Venetian blind between the cathode and the plate, along with a microscopic motor that could open or close its slats. If the slats were closed, electrons from the cathode would be unable to reach the plate; no current would pass. With the blind open, only a few electrons would strike the slats; the majority would pass through, and a plate current would flow.

If we could build so tiny a Venetian blind, and a small enough motor to control it, we would be able to control a fairly powerful plate current by means of a small current—the current needed to energize the motor. But although mechanically possible, the method is complicated and impracticable. Instead, the triode tube makes use of an electrostatic equivalent of our Venetian blind—a grid. Its slats are not metal, but electric fields, and they can open and shut smoothly 10,000,000,000 times a second.

The grid is simply a lattice of fine wires



Electrical nerve centers of glass and metal speed the messages of modern warfare. These high-power transmitting tubes, destined for the U. S. Navy, will help to maintain ship-to-shore communication

between cathode and plate, or, in some tubes, an open helix of wire surrounding the cathode. If connected to the cathode and therefore at the same potential, a grid presents to electrons emanating from the cathode the same appearance of an open network as it does to the eye (Fig. 2 on page HW 558) and the full plate current passes.

Suppose, however, that the grid is made more negative than the cathode by applying to it an additional negative potential of, say, -1 volt. Nothing will appear changed to us, but electrons, "seeing" electrically, will behold something like the grid shown in Fig. 3. The wires have been electrically "inflated" to many times their original size, and the space between them through which electrons can pass has been diminished. The electrons on the grid constituting that charge of -1 volt will repel some electrons that would have passed before. Furthermore, a grid negative in respect to the cathode tends to block the strong positive attraction of the plate. Fewer electrons reach the plate, and the plate current is smaller.


If we increase the negative potential on the grid to -2 volts by crowding additional

control another current powerful enough to fill an auditorium with sound through a loud-speaker, open doors, control heavy machinery, or do other useful work.

A potential as small as .001 volt is detectable in a standard amplifier. A vacuum tube such as the 6F5-G will react to a current of one one-hundred-billionth amp. In a special two-tube circuit, a current of less than one ten-billionth amp. controls a current of 1 amp., which in turn can control 1,000 amp. or more. Special tubes can detect a current consisting of only 30 electrons per second—a flow so infinitesimal as to be meaningless when expressed in amperes.

The reason such sensitivity is possible is that individual electrons fed onto the grid have a cumulative effect. As the grid cannot emit electrons, they cannot escape. Because the grid is already negative, electrons emitted by the cathode are repelled by it and cannot affect it. As the tube is evacuated, there are no gas ions to be attracted by the grid and discharge it. In a theoretically perfect tube, having a perfect vacuum and a fully insulated grid, a current of one electron per hour on the grid would eventually mount to a potential that would block the plate current completely.

But the triode has, in addition to its amazing sensitivity to minute electrical potentials, another important characteristic. It reacts



## Controls Electrons

electrons on it, the wires will be inflated still more, as in Fig. 4, and even fewer electrons will reach the plate. Finally, if a sufficient negative potential is applied, the electrostatic fields around the grid wires will completely overlap as in Fig. 5—the "slats" of our electrostatic Venetian blind will be closed—and no current whatever will flow across the tube.

When grid wires are closely spaced, even a charge of a few volts will block the plate current completely. If they are widely spaced, a higher negative potential is necessary.

In the triode, or three-element tube, we thus have a method of controlling the plate current that the diode did not afford. The vastly important advantage of this grid control is that a mere charge—a potential, not a current—will affect the plate circuit. The triode is an ultrasensitive relay, in which an infinitesimal current can con-

The 8012, shown full size at right, is a transmitter tube that delivers 35 watts at 500,000,000 cycles. Below is a slightly larger 300-watt tube







Fig. 1



CATHODE GRID PLATE




Fig. 2




Fig. 3




Fig. 4





Fig. 5



This setup shows how grid changes affect the plate current. With a 275-volt power supply, 250 volts can be impressed on the plate and 25 on the grid. A few volts difference on the grid affects the lamp as much as a 100-volt change on the plate, the ratio indicating the amplification. Try varying the potentiometers and also reversing battery polarity. A glow spreads or diminishes on one plate of the neon lamp as the plate current increases or lessens.



to changes in grid potential at almost the speed of light. Electrons have very little mass, hence very little inertia. They can be moved at tremendous velocities. Electrons can be impressed upon the grid of a vacuum-tube amplifier in a ten-billionth of a second and drained off as quickly. The plate current will respond to such changes in the grid potential faithfully, even though it may take more than a ten-billionth of a second for the electrons comprising that plate current to travel from the cathode to the plate. The plate-current variations would arrive a trifle later than the grid impulses, but all in correct order and properly spaced.

However, to charge and discharge a grid periodically, we must move electrons quickly and in great numbers. Small though their inertia is, pumping them into and out of a grid at high frequencies requires considerable power. The reason for this is that a grid constitutes one plate of a tiny condenser,

which in most small amplifier tubes has a capacity of only a few micromicrofarads. Now a certain number of electrons impressed upon a .001-mfd. condenser will produce a charge of, say, 10 volts. But the same number of electrons on a .01-mfd. condenser will charge it to only 1 volt. Therefore, the bigger the grid (that is, the greater its capacity) the more energy is required to pump electrons into and out of it.

A 1-mmfd. condenser will be charged to a

potential of 1 volt by a current of 1 micro-microampere flowing for 1 second. To charge this same condenser to the same potential in a millionth of a second takes 1 microampere—a million times the current.

Radio amateurs working with short-wave equipment at frequencies up to 750 megacycles use very small "acorn" tubes in special circuits. At such frequencies, the capacitance even of a straight piece of hook-up wire becomes something to reckon with.

## Triode Oscillator Generates Wide Range of Frequencies

WITH the homemade oscillator shown below, you can generate audio frequencies ranging from the lowest to the highest audible to the human ear. The addition of a telegraph key makes the oscillator a useful code-practice set.


By impressing upon the grid of a triode the oscillating current of a resonant circuit,

we obtain in the plate circuit a current of the same frequency. Since this same plate current flows in the cathode circuit, which includes the lower half of the inductance  $L$ , the varying magnetic field there created will induce a like oscillating current in the remainder of the inductance, thus maintaining the energy in the resonant grid circuit. With the proper values of capacity, inductance, and resistance, any desired frequency can be generated. When the resistance  $R$  is adjusted to zero, the circuit oscillates at a frequency given by the formula



$$F = \frac{160}{\sqrt{LC}}$$

where  $F$  is the frequency,  $L$  the inductance in microhenries, and  $C$  the capacitance in microfarads.

With a center-tapped filter choke and a .001 to 1-mfd. condenser, a 1,000,000-ohm potentiometer tunes the circuit to various frequencies. If you have no center-tapped choke, you can use an audio transformer by joining a primary and a secondary lead so that current flows through both in the same direction. The juncture acts as a center tap, and the speaker-lead resistor can be omitted.



Mounted on an old radio chassis, the oscillator is powered by a high-voltage supply shown at the right of it. Below, the underside of the chassis






# Servicing Your Radio




**NOISY VOLUME CONTROLS** of either the wire-wound or carbon type often can be repaired simply by removing them from the chassis and cleaning them thoroughly. Soak a piece of clean linen in ordinary noninflammable cleaning fluid and rub the windings and contact arm of a wire-wound control until they are clean. A little more care is necessary with a carbon control. Roll a small piece of absorbent cotton tightly around the end of a toothpick, dip it in the cleaning fluid, and wipe carefully, with a little pressure, along the carbon strip. Be sure also to clean the contact springs on the rotating arm.



**SLIPPING IN THE TURNTABLE** of a phonograph may cause difficulties that are sometimes incorrectly attributed to the motor. Look first at the rubber washer between the turntable and the motor spindle—the cone-shaped piece marked with an arrow in the photograph at left—for it may be to blame for the turntable failure. Frequently this washer becomes soaked with oil from the motor, and when this is the case, the washer surface is made so slippery that it cannot establish a firm contact with the turntable. Cleaning is rarely effective, and it is much more satisfactory to replace the old washer with a new one.



**YOUR HANDS USED ALONE** sometimes will serve to locate trouble in a balky receiver. For instance, if reception is weak, touching the grid cap of the converter tube—a tube such as the 6A8 or 2A7—with one finger and chassis with another, as indicated in the photograph, may make it come in louder. This will mean that the secondary of the antenna coil is open or that a corroded connection on the coil is causing an extremely high resistance in the circuit. Even persons shy of electricity need have no fear in making this test, for no shock will be experienced if directions are followed. Don't touch parts below the chassis.




**WAVEBAND SWITCHES** and other switches in a receiver circuit may be replaced when they break down by using a four to six-prong tube socket and an insulated banana plug, as shown in the photograph at the far left. The socket may be mounted on the back of the chassis, following the directions detailed in the drawing. Two sleeves placed under it will raise it slightly from the chassis so that there will be room for insertion of the plug.

# radio ideas

**FM POLICE RADIO EQUIPMENT** now incorporates "iron-core" or inductive tuning among other new features. The closely controlled movement of an iron core in and out of a small form-wound coil permits easier and more accurate tuning, and reduces the effects of car vibration on tuning adjustments. Likewise new is a "workbench" support which proves convenient when the chassis is inverted for inspection or repair. Test jacks permit direct, simultaneous readings of several functions at one time. All tube sockets and tuning controls are stenciled on the top of the chassis.

**A MIDGET RECTIFIER** for energizing any electrodynamic speaker having a high-resistance field coil can be made as shown in the accompanying diagram. This will permit substitution of such a speaker in a circuit originally calling for a permanent-magnet speaker. One of the advantages of the midget rectifier is that it is small enough to fit any radio chassis and therefore can be used in a wide range of circuits in which such a speaker is to be supplanted. It will provide the current necessary to operate an electrodynamic speaker if it is equipped with a rectifier tube capable of carrying at least 150 milliamperes, and is a handy expedient when a permanent-magnet speaker is not available.



## RESISTOR AND CONDENSER CODES

[ELECTRICAL]

Small carbon resistors and small mica condensers required in a modern radio set are too small for convenient labeling with numerals so the Radio Manufacturers Association has adopted a standard code-marking system, a color code. Digits are represented by colors as follows:


0 Black	5 Green
1 Brown	6 Blue
2 Red	7 Violet
3 Orange	8 Gray
4 Yellow	9 White

Two types of markings are used on resistors. The straight-end, tubular-type resistor, with leads coming straight out of the end, is marked with color bands. The band at one end represents the first digit, the next band gives the second digit, and the third band gives the number of

zeros. That is, if the bands are brown-green-orange they are read 1-5-three zeros, or 15,000 ohms. This straight-end type sometimes carries a fourth band, either gold or silver. This band indicates the accuracy of value, gold being the highest.

The second type of resistor with leads coming out at right angles—uses the body color for the first digit, tip color for the second and a dot or band at the center for the number of zeros. Thus brown body, green tip, orange band should be interpreted as 1-5-000 or 15,000 ohms.

Condensers use the same type of color coding but the readings are in micromicrofarads, and the color is applied in small dots with an arrow indicating the order in which they are to be read.



POPULAR SCIENCE MONTHLY SHOP DATA




## Dissolved Oxygen Reduces Power Needs and Increases Life of Electron Tubes

THE recent solution of a long-standing electronic mystery promises new radio tubes which will have both longer operating lives and reduced power requirements. Similar improvements are foreseen for other electron tubes.

It is the purpose of a vacuum-tube cathode, of course, to discharge a volley of electrons to the plate. For 40 years scientists have known that an oxide-coated cathode emits electrons more readily than a pure metal one, but they haven't known why. Now Dr. Harvey C. Rentschler, Westinghouse research expert, has an answer.

Atoms of oxygen, he finds, apparently distort the crystal-lattice structure of the cathode and thus enable the electrons to be shot off more easily. Moreover, a method has been discovered by which oxygen can be dissolved within the metal of the cathode, much as salt can be dissolved in water. In previous practice, certain types of cathodes have been made by forming oxides of various metals into a paste and baking the paste on tungsten supports. The procedure developed by Dr. Rentschler consists of heating cathodes of zirconium, titanium, thorium, or caesium in oxygen until a "solid solution" of oxygen is uniformly distributed throughout the metal.

High-voltage vacuum tubes offer a special application of this new technique. Hitherto the cathode of a high-voltage tube has had to be made without an oxide coating because the strong electric field would rip the coating from its support. Oxygen dissolved in the cathode, however, is an integral part of it and can't be pulled off.



Within the glass tube is a strip of zirconium which Dr. Rentschler is treating with oxygen to improve its electron-emitting characteristics


Below, a photoelectric cell having one of the new cathodes is tested by a spectroscope. Electron emission is caused by both light and heat



# How Airplane Wings Get Their Lift

**W**HAT gives an airplane its lift? Near the beginning of the eighteenth century, a Swiss mathematician, Daniel Bernoulli, discovered a physical principle which accounts for the greater part of the answer. In the course of experimenting with fluids, both liquids and gases, he found that pressure decreases as velocity increases.

The Bernoulli principle explains the increased draft of a chimney when wind blows across its top, the bursting of a house near the path of a tornado, the curve of a ball that is spun as it is thrown. It is also one of the most vital factors in aerodynamics, ac-



**MAKE THIS AIRFOIL** by covering a cardboard-and-dowel frame with paper. Holes are needed in the paper to enable the airfoil to move freely along the guide wires as pictured in the photographs above. Stops on the wires cause the airfoil to rest normally just a little below the center of the slip stream from the fan. To show that the airfoil gets more lift from the partial vacuum above the wing than from the air stream under it, hold a strip of cardboard under the leading edge so that only the under surface is exposed to the breeze of the fan. The airfoil will rise a little. Then make a second test by holding the cardboard in such a way that the fan blows only above the airfoil, which now rises much higher.

home

## EXPERIMENTS



**AN AIR STREAM** directed in the space between two freely suspended oranges will result in lowered air pressure in this area. The outside air pressure will thereupon force the two oranges together. Suspend the oranges so that they are about 1 1/2" apart when hanging at rest.





**A MANOMETER**, a device used for measuring gas pressure, can be made by partly filling a bent glass tube with colored water. The level in both sides is normally the same, but when you blow through another tube squarely across one open end of the manometer, the water rises in that leg, showing that the air pressure on that side is reduced. As you blow harder, increasing the speed of the air flow, the water rises higher. Similar manometers are used in determining pressures on the various parts of airplane wing surfaces and on the wings of test models. Atomizers work on the same principle.



counting for nearly 75 percent of the total lift exerted by an airplane wing. Air passing rapidly over the curved upper surface of a wing reduces pressure there, causing a partial vacuum. The relatively greater pressure beneath the wing then buoys it up. This may sound mysterious, for the idea that lift comes from a partial vacuum above a wing is not the most obvious explanation. But by performing the accompanying simple experiments, you can prove to yourself how the Bernoulli principle plays a part in modern aerodynamics.



**CUT TWO DISKS** of cardboard about 4" in diameter. Make a small hole in the center of one and seal the end of a drinking straw over the hole with sealing wax. Push a pin through the center of the other disk. Hold the first disk about  $\frac{1}{2}$ " over the other with the pin sticking up into the straw. Blow hard through the straw, and the lower disk will jump up to the other. The harder you blow, the more firmly the disks stick together, since the air rushing between them reduces internal pressure while external pressure remains the same.

**A TABLE-TENNIS BALL** bounces up and down if supported on an air stream, but it won't fall to one side. As it tends to do so, the air stream creates a low-pressure area on the opposite side, and atmospheric pressure moves it back.

# Magical Tricks

## WORKED WITH CHEMISTRY

Simple Home Demonstrations To Mystify Your Friends

By KENNETH M. SWEZEY

**A**LTHOUGH it may be a far cry from the ancient alchemist's den to the modern laboratory, chemistry is still a science of amazement and seeming magic. Everyone who professes to be a chemist, amateur or otherwise, is expected by his lay friends to be able to conjure up wonders at the slightest notice.

For personal pleasure, and to gratify these friends, every home chemist ought to develop a little "curiosity shop"—a collection of exhibits and fascinating stunts with which he can entertain visitors. Items for this shop can be both permanent displays and tricks that can be performed with the minimum of preparation. A few suggestions follow, but every installment of this home chemistry series contains at least one stunt that could

well be included in your repertory of wonders.


A "silver tree" that can either be "grown" before the spectator's eyes or be set up as a semipermanent exhibit will make a beautiful and instructive feature. Merely dissolve 3 grams silver nitrate in 60 ml. distilled water and pour it into a 2-oz. bottle. Carefully clean and scrape a roll of tin foil about  $1\frac{1}{2}$ " long and  $\frac{1}{4}$ " in diameter, and suspend it from the stopper of the bottle. In a few minutes glittering crystals of pure silver will be deposited over the surface of the tin foil. Being chemically more active than silver, tin drives the silver out of the silver nitrate and replaces it. The crystals of silver keep growing until all the silver in the solution has been replaced. They will remain on the tin-foil core until jarring dislodges them.

A miniature flag that responds as a humidity indicator, and may be changed



Here is a puzzler guaranteed to make spectators gape. A beaker or thin glass containing crystals of ammonium nitrate is set on a damp block of wood. Simply by adding water and stirring vigorously, the beaker can be made to stick tight. As the crystals are dissolved the beaker becomes intensely cold and the drops under it freeze solid





Colored in a solution of cobalt chloride, this little flag is a bright blue when it is perfectly dry. Blow on it, however, and it turns pink as it absorbs the moisture from your breath. Its ability to register quickly a slight change of moisture in the air makes a flag of this kind an excellent indicator of humidity.

coating of oil smeared inside the beaker above the solution will allow the water to evaporate eventually of its own accord and keep the chemical from creeping over the top of the beaker. When the crystals are dry, the stunt may be repeated.

You probably know the dinner-table stunt of boiling water on a visiting card with turned-up edges. The

from bright blue to pale pink merely by blowing on it, is another stock exhibit that may be made in a few minutes and will always arouse interest. Soak a piece of white cotton goods in a solution of cobalt chloride. While this cloth remains wet, or is even moist from humidity, it will be pink, but as it dries, its color changes to light blue and then to deeper and deeper shades of blue. Mount the cloth on a little flagstaff. Before demonstrating the trick, warm the flag slightly in order to make it the deepest blue. By blowing on it for a minute or so, you can turn it pink as the crystals of cobalt chloride absorb moisture from the breath.

Strips of white paper can be made to turn pink or red when held in what appears to be an empty glass, and then to turn white again when removed. Prepare a supply by soaking strips of blotting or filter paper in phenolphthalein solution and allow them to dry. To work the stunt, moisten a strip in plain water and hold it in a glass that has just been rinsed with household ammonia. In the presence of the ammonia, the phenolphthalein gives its usual reaction to a base, turning pink or red, but returned to fresh air, it loses its color.

A beaker or thin glass containing 60 grams ammonium nitrate will enable you to perform a feat that will get a sure-fire response. Put a dozen drops of water on a wood block and place your beaker in the center of the puddle. Now stir in 60 ml. of water (as cold as you can get it), attempting to dissolve the chemical as quickly as possible. During this process the beaker will become extremely cold and in a minute or two will freeze fast to the block. A thin

match or candle flame used does not burn the card because the water keeps the latter below the temperature of combustion. With care, tinfoil and lead foil may be melted similarly on a card.

The safety lamp, invented by Sir Humphrey Davy to prevent the explosion of free gas in coal mines, makes use of the same principle. In this case a screen of fine wire gauze surrounding the flame prevents igniting of outside gas by limiting the heat that gets through. A model of a safety lamp can be made from metal netting soldered or sewn to form a tube 6" long and 2" in diameter. Fasten on a top of the same material. If copper gauze of 30 or 40 mesh is used, only one layer will be required. Coarser netting, such as ordinary window screen, may require three or four layers. A jar cover forms the base, and a birthday-cake candle the light. Direct a stream of illuminating gas from a small tube toward your safety lamp. The gas will not ignite outside the screening, though it may catch fire within the lamp.

A little ball of steel wool that floats and sinks apparently without rhyme or reason is another good puzzler. Fill a tall tumbler or glass cylinder with a water-clear solution made up of 1 part sulphuric acid and 6 parts water. Compress a little wad of fine steel wool to the size of a marble and drop it into the solution. First it will float because of air trapped in it; then it will sink as the solution penetrates. Suddenly, however, it will rise again, then fall, and go through unpredictable gyrations.

To the chemist, the cause of the rising and sinking is obvious. The iron liberates


As a finale for your home exhibition of chemical magic, put a little potassium thiocyanate in the bottom of a tumbler, some silver nitrate in another, a few drops of potassium ferrocyanide in a third, and ferric chloride and water in a pitcher. Pour this last into the glasses. The first will become red, the second milky white, and the third blue



hydrogen from the dilute acid. This clings to the ball and buoys it up, but as some of the gas is lost, the ball drops again. If the ball doesn't rise, fluff out the steel wool; if it doesn't sink, compress it further.

For an astonishing—and patriotic—finale, prepare four little dropper-top bottles, each containing a solution of potassium thiocyanate, silver nitrate, and potassium ferrocyanide, and ferric chloride, dissolving 10 grams of each chemical in 60 ml. water. Into the first of three tumblers put 10 drops of potassium thiocyanate; into the second, 10 drops of silver nitrate; into the third, eight drops of potassium ferrocyanide. These solutions are clear and will not be noticed at the bottoms of the glasses. The ferric chloride solution, however, is yellowish, so about 15 drops of it are put into a tinted or opaque pitcher, together with three glassfuls of plain water

Pour the solution from the pitcher into the first glass, and it instantly becomes red; pour it into the second, and it becomes white; pour it into the third, and it becomes blue!



Made of ordinary wire gauze or screening, the little lamp above will demonstrate the effectiveness of the miner's safety lamp invented by Sir Humphrey Davy. A jet of illuminating gas directed toward the flame will cause it to flutter, but will not ignite outside the lamp. The wire gauze cuts down the intensity of the heat passing through to prevent combustion


Literally made to grow before the eyes of your friends, the little "silver tree" at right presents a pretty sight. It is a small roll of tin foil in a solution of silver nitrate. Tin is more chemically active than silver, and suspended in the solution it replaces the silver, which is deposited on the roll in glittering crystals as it is freed. This continues until all the silver is used up







**GARDEN TOOL SHEDS** prefabricated of insulating wallboard for quick assembly are waterproof, fire resistant, and vermin-proof. They consist of seven parts, including four walls, a floor, and a two-part roof. There are three sizes, from 4' by 6' to 10' by 12', and they can be used on the beach as cabanas or as back-yard playhouses for children.




## HOME OWNERS

**NEW SHOWER CABINETS** are made of noncritical materials for quick assembly on the job. The cabinet has less than one pound of metal in it. All walls are made of hard pressed wallboard covered with baked enamel resistant to high temperatures. The receptor is made of green plastic. Complete equipment is included with the cabinets, even to the curtain.




**COOKING ON GLASS** proves quite practical with this portable grate and grill. It is made of glass that has been fired black, powdered to a fine dust, then molded into the grill and basket grate. A folding frame made of wood is coated with fire-resistant glass to render it safe from flame. The grill surface measures 12" by 19". Any kind of fuel may be used, although charcoal is, of course, ideal for the purpose.



**HOME HEATING** may be revolutionized by a new furnace recently invented by Corporal Harry Giffords of the Army Air Forces. The automatic unit furnishes hot water the year around, heats and circulates air in cold weather, provides circulation of outside air during hot days, and filters the air at all times. One of the unusual features of the operation of this unit is that it imparts heat from heated air to water, and

**PRESERVING METAL** that is about to rust through and become useless, such as gutters on a house or water buckets, is a simple matter with a new solution. The metal is cleaned of rust and dirt to begin with; then the solution is painted on, leaving a thick coat. This liquid is noninflammable and can be used indoors or outside. Objects treated with the solution should be allowed a week to dry, after which they may, if desired, be painted with any good-quality oil paint.



uses the water so heated to furnish the domestic hot-water supply.

In summer the unit heats air that in turn heats water for storage or for immediate use without interfering with the circulation of cool outside air. An artificial cooling unit can be added if desired. The furnace is said to be economical to operate. Its principle has been suggested for possible use on large postwar air liners.



**COMBINATION LADDER.** A compact ladder that folds small enough to go into the luggage compartment of a car can be used as a long extension ladder, a small or a large stepladder, or as a support for a scaffold. In the photo above one such ladder is shown extended and another in use as a stepladder. The rails and rungs are of hardwood. Rigidity in all positions is assured by a patented double-lock design.



Dear Workshop Editor

We have a sturdy one-year-old who is about ready for a baby walker, but they're just not to be had in our town. Could you publish plans for a walker that I could build in my home shop?

J. R. Hullman, Rockford, Ill

J. R. Williams, Rockford, Ill.



This walker, by Franklin H. Gottshall, can easily be altered to suit makers' tastes. Thus if it's used as a stroller, a detachable floor might be devised to keep the child's feet off the ground. Be sure that the grain of each wheel disk is 120 deg. from that of the other two disks. Don't finish with white lead paint, since it might be poisonous for teething children.

# "HARD WORK NEVER HURT ANYBODY"

The  
Story of  
Harry A. Winne

A BOY waving at the trains passing in and out of his world—enchanted by the mystery of their engines and machinery—that was Harry A. Winne.

He just *had* to know what made their wheels go round, and he was about knee-high to a brakeman when he started to learn. He'd hurry home from school to run the steam engine in his father's laundry. Soon he tore a small magneto apart and from it built an electric motor.

He knew he was going into the electrical business somehow; he thought maybe he'd become a lineman for an electric power company. So he and a blacksmith made metal climbers, and he learned to climb the telephone poles outside the grocery store where he was clerking.

But the teachers in the upstate New York town urged him to go to Syracuse University to study engineering. So Harry Winne started working harder. Summers he worked in a creamery; at other times he delivered the college newspaper and was Sunday watchman at Woolworth's. Studying as hard as he worked, he was graduated at the head of his engineering class in 1910.

At once he joined General Electric as a student engineer in the testing department, Schenectady. There he could watch some of the biggest wheels in the world go round, and

in two years he was made assistant general night foreman.

"There are things higher up for you, Harry," his boss said before long. "You've got everything you can get here. You're destined for higher things."

And up Harry Winne went—through various engineering departments, to head of the steel mill section in G.E.'s industrial engineering department, to manager of sales of the combined mining and steel mill section—and then finally, a couple of years ago, to vice president in charge of design engineering!

Harry Winne'd tell you he got up there by hard work and luck. Today he's working harder than ever—at G.E. supervising the design of electric equipment for the army and Navy, at home in a big Victory garden beside his made-over farm house on a dirt road outside Schenectady.

But then—"hard work never hurt anybody!" *General Electric, Schenectady, N. Y.*

Hear the General Electric radio programs: "The Hour of Charm" Sunday 10 p.m. EWT, NBC—"The World Today" news, every weekday 6:45 p.m. EWT, CBS.

The best investment in the world is in this country's future BUY WAR BONDS.

## GENERAL ELECTRIC

664-742-711

Buy War Saving Bonds and Stamps regularly.

HW 571



## Easily Made Rope Ladder Is Useful Emergency Equipment




Wrapping an arm and a leg around a rope ladder gives support to the body in climbing. At right are shown details in the construction of a ladder

WHEN an emergency strikes, rope ladders are often highly desirable equipment, since they may be quickly put in position and are not hard to use. A feature which makes them especially convenient is that they can be rolled up for compact storage. They are also handy for access to a loft or attic where room does not permit installing a stairway.

These ladders are easily made from strong rope, 18" lengths of oak  $1\frac{1}{4}$ " in diameter, and twine. The rope may be used in two pieces or doubled. Unlay the strands at equally spaced intervals 12" to 18" apart, insert the rungs, allowing 1" to protrude, and hold them fast with staples. Bind twine above and below the rungs.

Whip the rope ends by forming a circle of a 15" length of twine, with ends overlapping 2". Hold it against the rope so that one end projects a little beyond the rope end. Wrap the side of the loop which extends beyond the rope back around the rope. When the loop has diminished, hold as shown and pull on the projecting end of twine. Then cut off the loose ends.—WILLIAM H. DAVIS.



## Perky Halloween Hobgoblins Are Created from Black Walnuts

CAPTIVATING little hobgoblins for Halloween decorations may be made from a few black walnuts and pipe cleaners. Cut off a portion of the tapered end of the walnut so that you may use the exposed cross section for the face. The simplest way to do this is to hold the nut in a vise and cut it with a coping saw. Dig the meat from the two natural eye holes and fill the cavities with wood putty. After the putty has hardened, paint a little pupil on a part of each eye. The natural formation of a black walnut will give the illusion of a nose and mouth. Saw out the hobgoblin's big feet from  $\frac{1}{2}$ " stock and drill holes in the head, body, and feet. Attach the head and feet to the body with pipe cleaners and glue, allow-




ing the glue to set before painting all but the face with mahogany oil stain. The little fellows will serve to hold nut cups and place cards if their pipe-cleaner arms are bent properly. They may also be placed around the room as Halloween decorations.—E. W.


# BLITZED IN A GREENHOUSE!




(The exciting experience of Margaret Bridges, of the London Auxiliary Ambulance Service, during one of London's heaviest raids. Pretty, attractive 30-year-old Miss Bridges is part English, part American. She volunteered for the ambulance service, reporting for duty just three days before war was declared.)



① "We had about 40 ambulances and other cars stored in a building with a great glass roof—a virtual greenhouse—when Jerry's bombers arrived. When they began finding our section of London we started getting the cars out ...



② "Naturally, the transparent roof taboo'd ordinary lights. Yet we hadn't a moment to lose; with every sickening crash we expected the roof to splinter into a million heavy daggers. I got out my flashlight. In about ten minutes I had guided all the cars to safety ...



③ "I was working alone in my office when the roof finally did cave in. Only my flashlight could have helped me find a way through that deadly, glittering sea of broken glass ... You begin to see why ambulance drivers must always carry flashlights with fresh batteries!"



Your dealer may have no "Eveready" flashlight batteries. If so, please don't blame him—almost the entire supply is currently going to the armed forces and those war industries with the highest priority ratings.

Send for "You and the War," official O.C.D. guidebook to all vitally important war posts available to civilians. This free booklet tells exactly what there is to do and how to do it. Write National Carbon Company, Dept. D.P. 30 E. 42nd St., New York 17, N. Y.

NATIONAL CARBON COMPANY, INC.  
30 East 42nd Street, New York  
Unit of Union Carbide and Carbon Corporation

UCC

The word "Eveready" is a registered trademark of National Carbon Company, Inc.





## Homemade Brooder Uses Infrared Lamps as Source of Heat


WITH factory-made brooders hard to get, poultrymen may need homemade equipment to increase chick production. Shown below is a simply built brooder of 250-chick capacity which will let you raise "spring" broilers at any season, and which costs only \$3 to \$7 for materials. It was designed by Professor John E. Nichols, of Pennsylvania State College.

The brooder is made of  $\frac{3}{4}$ " by 10" stock, with legs 2" by 2" by 14". Set the inside cleats 11" from the ground, and nail on them a flooring of 10" stock, 4' long. You will then have two shallow compartments, the lower one giving about 4" ground clearance. Fill the upper compartment with floor litter to serve as insulation, and tack a cloth skirt to the sides. Slat s can be nailed across the top so that the brooder may later serve as a roost for older chickens.

On facing inner sides of the lower compartment set two porcelain lamp sockets, and


bore a  $\frac{3}{8}$ " hole for the cord. A strip of wood under the upper edge of each socket base will give the lamps a desirable downward tilt. Be sure to use heavy-duty wire in connecting the sockets. The lamps are 150-watt reflector-flood types or 250-watt reflector-drying types, with rated lives of 1,000 and 5,000 hours respectively. These lamps, which project infrared heat rays as well as light, are especially suitable, although ordinary incandescent bulbs can be used if reflector types are unavailable. A thermostat is not needed with the former, since the chicks can find the right heat for their needs, but is desirable with ordinary bulbs.

An even simpler brooder for 200 chicks or less can be built by forming an uncovered enclosure of wood or light sheet metal and suspending one or two reflector bulbs over the area. Start with a lamp about 12" above the brood and raise it with the handy wire shortener as the chicks grow.




## Wood Supports Keep Chickens from Upsetting Water Pan

CHICKENS perching on the side of a water pan will frequently upset it, particularly when the water level is low. A simple and practical method of preventing this is to use three notched supports as shown in the drawing to the right. Saw kerfs in the tops of three wooden stakes, sharpen the opposite ends, and drive them into the ground in the proper position. It may be necessary to bend the lip of the pan somewhat so that it fits the notches snugly.—JOHN K. KARLOVIC.



# BRILLIANCE WITH A PURPOSE

Like mirrors and jewels is the sparkle of polished metal parts in an Allison—but the eye cannot begin to see the perfection this brilliance reflects. ★ For one of the challenges in making aircraft engines is this . . . ★ To preserve — by exquisite accuracy of manufacture and finish — all of the inherent strength and endurance in every ounce of material used. ★ This need for perfection is nothing new to Allison. For years it has been our special province to handle metals with precision and lapidarian skill. ★ In today's tasks we are advantaged by all that General Motors has to offer in production techniques. ★ The result is a liquid-cooled aircraft engine which in performance can speak for itself—and an engine which we are resolved to make the finest in the world.



KEEP AMERICA STRONG  
BUY MORE BONDS

POWERED BY  
ALLISON

P-38—Lightning  
P-39—Airacobra  
P-40—Warhawk  
P-51—Mustang

LIQUID-COOLED AIRCRAFT ENGINES

*Allison*


DIVISION OF



Buy War Saving Bonds and Stamps regularly.

HW 575






Motor and compressor are mounted on one chassis. A homemade check valve is shown in the sketch to the left; at the upper right, a pressure control

## HEAVY-DUTY AIR COMPRESSOR



The throttle of this motor is controlled by a rod from a pressure unit that was made by bolting together two conduit boxes over a rubber diaphragm

On the compressor, below, the throttle control rod is moved by a vacuum overdrive unit, but the type used with the engine would have been satisfactory. The radiator is needed to keep the compressor cool




AIR compressors can't be bought readily today, so when a mining company needed one, Henry Lawrence, of Santa Fe, N. M., built it from two wrecked cars. A motor from one is used to drive a compressor made from the other motor.

To convert the motor to a compressor, Lawrence removed the valve lifters and installed light springs on the valves. This enables both the intake and exhaust valves to feed air to the cylinders, and makes each upward stroke a compression stroke. To filter all the air through the carburetor air cleaner, the exhaust manifold was closed off and an inner wall broken through to the intake manifold.

Studs were screwed into the firing chambers in the cylinder head and lead was poured around them to increase compression. Homemade check valves were screwed into the spark-plug holes. Each was made of a pipe tee, the valve proper consisting of a concave expansion plug such as is used to safeguard engine blocks against freezing. A check valve in the air manifold also keeps air from feeding back.

Two homemade control units govern the machine. The air chambers in the control units are connected with a hot-water tank relief valve set on the air tank. When pressure reaches the point for which this valve is set, the control diaphragms move rods attached to each carburetor. This reduces the engine speed to idling and also cuts off the compressor air intake so that it "coasts." A pinhole in the air line to the control units allows the pressure to bleed out slowly. Then both throttles open and pumping continues.—EUGENE S. HARRIS.



## "FIRE BOMBS FALLING ... Rush the Pumpers!"

It's a forward base for the big push . . . and the Japs know it. They're trying to burn us out. For a while it seems we have more fires than we can handle . . . that is, till the fire pumpers arrive. They're hauled by anything that will pull! They unlimber and go into action like artillery. Fire just hasn't a chance with them around!

Nearly anybody can operate a Chrysler War Emergency Fire Pumper . . . Originally developed to meet an acute shortage of fire equipment in areas vulnerable to air raids, they had to be simple and easy to use. Thousands of them now augment our regular fire departments in all parts of the country. They've proved so compact and

mobile that many more have been sent into service at our advanced bases overseas.

The Fire Pumper is built around the same sturdy, dependable engine used to power thousands of cars manufactured by Chrysler. The engine with its moving parts Super-finished mirror-smooth—some to one-millionth of an inch, for quietness, economy and longer life.

Such Chrysler wartime developments demonstrate the pioneering leadership of Chrysler Division.

BACK THE ATTACK—  
WITH WAR BONDS

# CHRYSLER

DIVISION OF CHRYSLER CORPORATION

### WAR PRODUCTS OF CHRYSLER DIVISION

Industrial Engines • Marine Engines • Marine Tractors • Navy Pontons • Harbor Tugs • Anti-Aircraft Cannon Parts • Tank Engine Assemblies • Airplane Wing Panels • Tank Parts • Fire Fighting Equipment • Air Raid Bells • Gun Boxes • Navy Searchlight Reflectors.

THE NATION WIDE CHRYSLER DEALER ORGANIZATION  
OFFERS OWNERS SERVICE FACILITIES TO MEET  
THEIR WARTIME TRANSPORTATION NEEDS

NOVEMBER, 1943

Buy War Savings Bonds and Stamps regularly.



# "Double Your Money Back"

## IF YOU DON'T GET BETTER AND SMOOTHER MOTOR PERFORMANCE WITH CASITE

● If your motor has lost its pep and punch, get the quick, speedy relief that CASITE gives and guarantees!

CASITE restores performance—makes any motor run better and smoother, because it cleans out and keeps out power-destroying sludge, retards the formation of engine varnish, and frees up gummy, sticky valves and rings.

Join the thousands who are using CASITE to keep their war-weary motors at top performance. Get a CASITE tune-up today, from your car dealer, garage, or service station.

THE CASITE CORPORATION  
HASTINGS, MICHIGAN



HERE'S CASITE'S  
SENSATIONAL  
GUARANTEE

### Guarantee

#### YOU ARE THE JUDGE—

Add Casite to crankcase and run through carburetor according to instructions, then drive your car 100 miles or for 60 days, whichever is first. If not convinced that Casite gives you better and smoother performance, you get double your money back by filling out guarantee certificate and mailing it to The Casite Corporation, Hastings, Michigan. Maximum refund is \$1.30 per pint, which is twice the nationally advertised price of Casite.

CLEANS OUT MOTORS • KEEPS MOTORS CLEAN

## New Theory of Air Power

(Continued from page 52)

equipment. An Air Support Party—sometimes a single liaison officer—is attached to a field unit, such as a regimental combat team.

These men funnel the inflowing mass of information, strain out what is important, pass on what the ground commander should know, and expedite requests for air support at specific places and times. Their work must be cool, unhurried, yet rapid and precise. The plans they draw up and the orders they give tell the story.

The complexity of air support, the fluid brilliance with which it functions in battle, is almost impossible to visualize without seeing it in action—and few civilians ever can have the chance to see it. Even the war correspondents who get behind the scenes of military operations are barred by security regulations from describing the technical workings of the machine.

To give a clear, dramatic picture of air support, POPULAR SCIENCE, with the co-operation of Army Intelligence sources, has arranged an account of one day's air-ground operations on a divisional front. It is accurate in every detail, although the description is sufficiently generalized that no information can be revealed to the enemy.

The opposing forces are facing each other along a line lying roughly between the town of X and Unknown River. Our forces are attacking to the north, while the enemy, giving ground slowly, is attempting to hold south of the river. At dark our troops have been stalled by stubborn resistance. The division commander has decided that he must lean heavily on air support in the next day's fighting.

The battle plan is set up at a conference in the tent of the chief of staff. Attack is to be resumed in the morning, with Combat Team X making the main effort on the left. Team Y will hold the right flank and Team Z will be held in reserve. The first need is for thorough air reconnaissance far behind the enemy line. The second is for heavy air support, as most of the artillery will have to be concentrated on a relatively narrow front in support of Combat Team X.

Air Commander recommends continued pressure to keep the enemy air force pinned down, plus a heavy bombardment of key rail lines. As for the direct support of the attack, that is a matter of careful timing. The infantry push is scheduled for 0615, preceded by a 10-minute artillery barrage of maximum violence, beginning at 0600.

(Continued on page 204)



**You may  
worry about  
feeding  
your pets**

**but you won't worry about your car  
with **Marfak Chassis Lubrication****

With Marfak Lubrication you have a sweeter, smoother-running car. For Marfak, you see, is one of the finest, most thorough and efficient chassis lubrication services ever devised.

Your dealer works with a scientific Marfak chart. He checks every vital point on your car, from battery and tires to differential and rear-end gears. No guesswork here—the job is *accurate*, to protect irreplaceable engine and chassis parts.

Insist on genuine Marfak Lubrication today—to keep your car in "top" condition. At Texaco and other good dealers everywhere.




Tune in the TEXACO STAR THEATRE every Sunday night. See your local newspaper for time and station.

*You're Welcome at* **TEXACO DEALERS**



# "A HOME-STUDY COURSE" for a postage stamp



**Are you a shop foreman, mechanic or mechanical "trainee" who appreciates the importance of sound fundamental knowledge of the proper use, proper care and proper selection of tools?**

Start with files and filing—one of the most basic and widely applicable subjects in the mechanical curriculum. If you are in or definitely aiming toward a mechanical career, a postage stamp will bring us your request for

## "FILE PHILOSOPHY"


—the most authoritative book of its kind. Widely used in school-shops and shop-schools, "File Philosophy" takes you through the history of files; the way files are designed and manufactured; the kinds, sizes and cuts of files, the purposes and characteristics of many special files. Tells how to use files expertly—on various metals, in sharpening saws and other tools; how to take care of files.

**IT'S FREE**—this valuable "text-book" of 48 interesting, informative, profusely illustrated pages—a Nicholson contribution to the advancement of American industry and the vast army of trained men who are its back-bone.

**NICHOLSON FILE CO., 19 Acorn St., Providence 1, R. I., U. S. A.**  
(Also Canadian Plant, Port Hope, Ont.)

Manufacturers of Nicholson and Black Diamond quality files—sold through hardware and mail-supply houses.

**NICHOLSON**  
**FILES** FOR EVERY  
PURPOSE



# New Theory of Air Power

(Continued from page 202)

Air support is to strike at precisely the interval, hitting at 0610 with a low-level attack by six A-36 Mustang fighter-bombers. Two minutes later the pounding will be taken up by another flight of six A-24 dive bombers.

As an indication of the precision with which air and ground operations are integrated, the artillery barrage will end with the firing of smoke shells to mark the objective for the diving planes; the last dive bomber gives the infantry the signal to go ahead by wagging its wings. Our own front lines will be marked with colored smoke to obviate any danger of an error in bombing objectives.

The chief of staff okays these arrangements and orders the necessary reconnaissance and photographic air missions to be worked out with the G-2 (intelligence) officer. Next comes a conference in the Air Support Control office, usually located near the divisional command post. The G-3 (operations) officer explains the plans for ground operations, while the Air Commander outlines his operations to the liaison officers of the various air groups—reconnaissance, dive bombers, medium bombers, and fighter planes.

The complex process of mounting a co-ordinated air-ground operation moves along as the air support and divisional signal officers go into a huddle of their own, check over their wire and radio communications, shift some of the radio frequency bands which are jamming up against powerful enemy transmitters, and arrange a code of visual smoke and panel signals. Finally, the Air Commander is ready to issue his attack and operations orders, which are teletyped to the airdromes over the A-2 wire net.

At dawn the attack begins, with a thundering artillery barrage pouring down on the hill which is the enemy's chief point of resistance. With split-second timing, at 0610, the artillery fires its smoke shells, the infantrymen set off red smoke to mark our advanced lines, and out of the low-hanging mists roar the A-36 Mustangs, to strike with their bombs, then vanish. Immediately the Douglas Dauntless A-24 dive bombers arrive, peel off one by one, and smash at the target. As the last plane gives the signal by rocking its wings, the infantry attack is launched.

While the ground fighting grows in intensity, the planned air operations go ahead with attacks on enemy air fields and supply

(Continued on page 208)



# CHAMPION SPARK PLUGS

## *ON ACTIVE DUTY ON THE HOME FRONT!*

Here at home, Champion Spark Plugs "Back The Attack" in buses, cars, trucks, tractors, planes, stationary and marine engines of every type, delivering manpower and horsepower to tasks vital to Victory. In engines of every size and type, Champions are maintaining their long established reputation for better performance, greater dependability.



The air transport lines are one of our most important means of transportation. Dependable Champion Spark Plugs are enjoying rapidly-growing favor with leading air line companies.



Short of manpower, and with the imperative need for unprecedented food production, the farmer knows he can depend on Champion-equipped power-driven equipment.



Champion-equipped engines furnish dependable emergency power in "stand-by" plants in thousands of industries and utilities.



The nation depends on truck transportation as never before. Here again dependable Champion Spark Plugs excel and are preferred.



**IN CIVILIAN TRANSPORTATION.** War workers depend on their own cars in driving groups to get them to and from work, and everyone knows Champions are a dependable source of efficiency and economy.



**ON CONSTRUCTION JOBS.** Champion Spark Plugs are the source of dependable performance in thousands of heavy duty industrial engines like the one that powers these pneumatic hammers.

## BACK THE ATTACK — WITH WAR BONDS





*There's been  
a  
big change*

● Sentiment about the old things is an admirable American trait. But even the most sentimental of us must admit that change frequently is for the best.

An outstanding example of progressive, beneficial change is that which Tyson has made in tapered roller bearings. Tyson improved the old-time conventional bearing by adding an average of

30% more load-carrying rollers. Result: Tyson users enjoy greatly increased load capacity—almost doubled bearing life!

\* \* \*

These users often tell us that the Tyson "All-Rolls" Bearing is the greatest improvement in tapered roller bearings in forty years. *The big name in bearings today is—TYSON!*

 TYSON BEARING CORPORATION, MASSILLON, OHIO

COUNT THE ROLLS • THE ROLLS COUNT

**Tyson**  
TODAY'S HEAVY-DUTY BEARING



★ BACK THE ATTACK — WITH WAR BONDS ★



# 750 Ton Flapjack!

**H**ISTORY was made when the destroyer escort, U.S.S. *Bunch*, was "rolled over" successfully at the Defoe Shipbuilding yards at Bay City, Michigan. For this was the first time a steel-welded ship more than 300 feet long and weighing over 700 tons had been built upside down.

The same engineering feat that made it possible to build the U.S.S. *Bunch* in record time is producing an ever increasing fleet of sister ships—many of which are already in service with the Navy on the high seas.

Defoe's unique "flapjack trick" with ocean-going warships does away with conventional ship scaffolding and allows workers to stand over their job at all times. Defoe con-

struction methods deliver *twice the production per man hour* resulting in *double the number of ships built at half the labor cost per vessel.*

Resourcefulness in developing new methods and shortcuts to speed delivery of ships to the Navy is typical of Defoe engineering tradition. And when our fighting men and their allies have dealt a knockout to the Axis, the same competi-

tive spirit, skilled workmanship and "know how" that are now setting records in producing for Victory, will be reflected in even greater values of Defoe products to serve peacetime America.

★ ★ ★

**BACK THE ATTACK—BUY WAR BONDS**  
Defoe workers take more than 10% of their pay in War Bonds

*"Next to our immediate task of building warships faster and faster, the first responsibility of Defoe is to plan for post-war operations that will provide the maximum of gainful employment."*

HARRY J. DEFOE  
Founder Defoe Shipbuilding Co.

DEFOE SHIPBUILDING COMPANY, BAY CITY, MICHIGAN

**Defoe**



*Two White Star Federal Citations now decorate the Navy "E" Award won by Defoe workers.*

**Ships for Victory  
Servants for Peace**



If you can imagine measurements to a fraction of the thickness of this sheet of paper, you can visualize tolerances allowed in Stevens production of military rifles. Measurements as fine as this are made thousands of times each day with gauges that measure to one ten-thousandth of an inch.



## PRECISION ... to a FRACTION of the thickness of this sheet of paper!

The production of military rifles of infinitely precise and dependable mechanism, and in huge volume, is the kind of job with which Stevens has long been familiar.

Before the war, Stevens produced sporting arms in great quantities. Yet the technical skill and facilities employed called for the most painstaking and precise methods of gun-making and assured a high degree of accuracy, safety and reliability in all Stevens-built rifles and shotguns.

Stevens long offered exceptional values from the standpoint of basic gun quality and comparatively low price. When the war is won, Stevens will repeat this performance, with the greatest rifle and shotgun values in our history.

J. STEVENS ARMS COMPANY  
Division of Savage Arms Corporation  
Chicopee Falls, Mass.

# STEVENS



## New Theory of Air Power

(Continued from page 204)

lines. About 10 a.m. full reconnaissance reports and air photographs from 30,000 feet reveal an alarming development. A heavy enemy striking force, including 100 tanks and additional armored and supply vehicles, is moving up on the rear roads, clearly heading for the point of our main attack.

Meanwhile the infantry advance has run into terrific opposition at the contested hill, and has been stopped dead in the woods at the foot of the slope by heavy fire from mortars, machine guns, and 77-mm. field guns. The infantry commander has learned that he cannot get any additional artillery support, and has sent a hurry call for help to his accompanying Air Support Party officer, who radios Air Control to ask what missions might be assigned or diverted to help pull the situation out.

Here air command has two new and pressing problems. The enemy-held hill needs our attention; so do the approaching tanks. But ground-force headquarters must determine the relative priorities involved, and the division chief of staff unhesitatingly puts the tank column first. A reserve squadron of B-25's (North American Mitchell medium bombers) is ready, and is ordered into action through the flexible system of control.

Photo maps and latest reconnaissance data are hastily assembled, and the crews file into their field headquarters for briefing—an informal but deadly serious process. The youthful squadron leader explains casually that "our doughfoots are in a jam, and it's up to us to deliver a low-level attack that will stop a column of enemy tanks. They're getting too close to a spot that's already too hot."

He shows them the map point where they will take formation, echeloned to the right. The attack will be pressed home at extreme low altitude, with intervals of 2,000 feet. "Give 'em your forward guns on the way in, and release all bombs in train." Fighter escort is arranged with a near-by field. The combat crews pile into jeeps and trucks and roll out to their planes, scattered around the dispersal area.

The tank column, rolling south at 20 miles an hour, is attacked at "zero-plus altitude." The first B-25 sweeps in over the trees, its guns blazing, and cuts loose with its bombs, which have delayed-action fuses set for the planned attacking interval so that they will explode just after the plane is out of the way and before the next attacker slashes by.

(Continued on page 210)

# Without batteries...war machines are useless!



1. Bomber 2. Destroyer 3. Submarine 4. Landing Barges 5. Troop Transport Trucks 6. Supply Trucks  
7. Self-propelled 155 mm. Gun 8. Tanks 9. Jeep 10. "Walkie-talkie" communications

EXIDE BATTERIES ARE USED IN MORE THAN 100 APPLICATIONS BY OUR ARMED FORCES

Modern mechanized warfare demands a dependable source of electric power, which, under most conditions, only a storage battery can supply. Without such a source of power, our mightiest weapons would be useless, idle, dead.

Supplying dependable storage batteries to the armed forces is Exide's most important present day job, and you as a civilian motorist can help us provide America's fighters with more and more of them. You can do this by giving your present battery the very best of care. Let your Exide Dealer check your bat-

tery every two weeks. Trust him, and his dependable Exide Sure-Start Service, to prolong its useful life.

Remember, when you take care of things you own, you're really making important savings. Invest your savings in War Bonds.

Back the attack—with War Bonds!



## WHEN IT'S AN EXIDE YOU START

THE ELECTRIC STORAGE BATTERY COMPANY, Philadelphia • Exide Batteries of Canada, Limited, Toronto



# Avoid those "Icicle evenings"



## PROTECT HOME COMFORT WITH BALSAM-WOOL ATTIC INSULATION



Tooth-chattering "evenings at home" aren't fun! But there's no need to endure chilly, uncomfortable rooms. At low cost, you can make your home far more comfortable—and save up to 25% in fuel at the same time—by applying Balsam-Wool Insulation in your attic.

Applying Balsam-Wool is as easy as laying a carpet! That's because Balsam-Wool is a finished insulation—tailored for quick application. Wind-proof, moisture-proofed and fire-resistant, it is scientifically designed for lasting efficiency—and sold under a money-back guarantee of satisfaction.

Make this lasting investment in comfort and fuel saving. See your lumber dealer about applying Balsam-Wool in your attic—or mail the coupon for full information.

# Balsam-Wool

SEALED INSULATION

WOOD CONVERSION COMPANY  
Dept. 211-11, First National Bank Bldg  
St. Paul, Minnesota

Gentlemen: I want to know more about Balsam-Wool Double Value Attic Insulation.

To assist us in giving you special information, please check. I am a home owner ☐ renter ☐ architect ☐ student ☐ contractor ☐

Name \_\_\_\_\_

Address \_\_\_\_\_

City \_\_\_\_\_

State \_\_\_\_\_



## New Theory of Air Power

(Continued from page 208)

The formidable armored column disintegrates into a wild, scrambling mass of vehicles and men. Within 10 minutes the road is strewn with burned and blackened equipment, and the pummeled remnants of the enemy force are withdrawing in total confusion.

Meanwhile, air support is working on the problem of the enemy hill. No other reserve flight is available, so bombers must be diverted from a planned operation to take up this emergency job. By means of radio equipment and a secret technique, the air support command "vectors" a squadron of bombers on their way to blast enemy railroad yards behind the battle, and steers them to the new target. They wing in, drop a blanket of destruction on the enemy strong points and artillery emplacements, and clear the way for the combat team to push ahead, carry its objective, and then drive on to the river crossing against steadily deteriorating resistance in the late after-

noon. For air operations the day ends with the return of the planes and systematic interrogation of the crews to determine the results of their attacks. This is done at the air fields, where the airmen gather at the squadron intelligence officer's office, make themselves comfortable with coffee and cigarettes, and then answer the long routine of questions on what targets they hit, what effect the bombs had, what air opposition or ground fire they encountered, what the weather was like, and so on and on.


But the day ends only in the sense that this information is summarized and reported on to the higher command, which starts at once to plan the air support for the next operation—only a few hours away. This, in capsule form, is how air support works. And what it means to the ground forces was best summed up by the Allied field commander in Tunisia, General Sir Harold Alexander, in this message to the African Tactical Air Command:

"Without your support this drive would just not have been possible."

## NOTICE TO SUBSCRIBERS

Subscribers in the armed services who notify us of change of address are requested to give us the key symbols appearing on the wrapper in which the magazine is received.

# Harley-Davidsons are Really *Standing Up!*



On all war fronts, the men who ride and service Harley-Davidsons are learning what "dependable performance" really means. You can't beat tough war action for proving that Harley-Davidsons can "take it and dish it out."

One fighter wrote from (CENSORED): "We're in an ordnance maintenance outfit and I'm overhauling trucks, cars and small engines. Harley-Davidsons are really standing up. They get twice the mileage and abuse other vehicles get before they need attention. I intend to get a new 74-OHV Harley-Davidson when I get back to the good old U. S. A."

*Hundreds of these letters continue to pour in—and the story is always the same. Put your fighting dollars in War Bonds — and join the riders who are going to own newer, better Harley-Davidsons after the war!*



## HARLEY-DAVIDSON MOTORCYCLES

HARLEY DAVIDSON MOTOR CO.  
Dept. P5, Milwaukee 1, Wisconsin

Please send at once free copy of 24-page  
"Enthusiast" Magazine, filled with motor-  
cycle action pictures and thrilling stories.

Address \_\_\_\_\_

City \_\_\_\_\_

State \_\_\_\_\_

SEND COUPON  
**NOW**

**FREE!**





## Know How to Sharpen Plane Irons or Chisels


Unnecessary grinding of chisels and plane irons wears them out prematurely. If they have simply become dull in use, whetting will restore the sharp, keen edge desired.

### GRIND THEM ONLY WHEN

1. The cutting edge is nicked.
2. The bevel has become blunt due to whetting at the wrong angle.
3. The bevel has been rounded by careless whetting.

Tools are vital to Victory. Care for them and use them properly—to make them last for the duration—to avoid waste of scarce metals.

Complete instructions for grinding and whetting edge tools are included in the **STANLEY TOOL GUIDE**, a 32-page handbook for the home craftsman. Simple explanations, thoroughly illustrated, tell how to use and conserve all types of tools.



**A Big Value  
for only 25¢**

Write for your copy today.

# STANLEY TOOLS

DIVISION OF THE STANLEY WORKS

106 ELM STREET

New Britain, Conn.

## Props for Our Warplanes


(Continued from page 187)

charged engines. If the propeller were, however, able to vary its blade pitch gradually from zero-angle low pitch up to 90 degrees high pitch, it would be flexible enough to absorb the engine's full horsepower at all altitudes. The constant-speed propeller is such a type. The prop and engine act as checks and balances against each other under all conditions of flight.

For emergency operation in the case of multimotored airplanes, this business of changing blade pitch has been carried a step farther to permit the "feathering" of the prop. The blades are turned in their hub through highest pitch until they are edge-on into the wind. The propeller is, of course, useless for thrusting in this position, but feathering is an expedient for flying with one or more engines out of operation, either by design or accident. Four-engined transports frequently cruise on only two of their engines, but this would not be considered good flying practice if full-feathering propellers were not available. Should an engine go dead in an emergency, the prop is feathered into the wind immediately; the prop in this position acts as a brake on the dead engine. In normal operating pitch, the prop would be subjected to "pinwheeling," just as the toy pinwheel spins when held to the wind, and this might result in a damaged engine. All the feathered propeller does is create a drag. A windmilling prop, however, would create more than 20 times this drag. The feathered propeller adds about 1,500 feet to the service ceiling of a twin-engined Douglas C-47 cargo transport flying on one engine and makes the plane much easier to handle. Even a single-engined airplane is at an advantage when fitted with a feathering prop because, in emergency, the plane's gliding range is half again as great with this type as it would be with a windmilling, unfeathered prop.

Carrying the pitch angle beyond the 90-degree feathered position into reverse pitch was a logical step in propeller development made first by Curtiss-Wright. The reversible-pitch prop, which delivers negative thrust, is extremely useful as an air brake. In some instances, it may be used to slow the landing run of planes, but its most practical application is found on multiengined flying boats. Maneuvering a flying boat in the water is, at best, a tricky operation. The reversible prop facilitates maneuvering in general and turning in particular. By reversing the two inboard propellers and

(Continued on page 216)



## GREASE for GEARS but NOT for SHAVING

Grease is great for machines, but men hate to put it on their faces. That is why so many men are switching from ordinary brushless to the new Mennen Brushless Shave — it's a cream, not a grease! Get it in either jar or tube.







## A Lift from the Front at Guadalcanal

**F**OR all its grimness, modern war is merciful to our wounded. The life-giving miracle of blood plasma\*...the swift, efficient treatment behind the lines...plus speedy transport to finely-equipped base hospitals...result in an incredibly high proportion of recoveries among even desperately stricken men.

*Speedy Transport!* It may be by giant transport plane, by ambulance or nimble-footed Jeep...or at jungle fronts in the South Pacific, by outboard-driven small craft threading narrow rivers, saving priceless hours between front lines and the base.

Evinrudes are busy at innumerable tasks for the Army and Navy, Marine Corps and

Coast Guard...driving swift assault boats...propelling pontons, lighters, ferries...powering huge rubber rafts, wherries, small craft of every type. *After Victory* there will be peacetime Evinrudes worthy of the traditions of their fighting forebears!

EVINRUDE MOTORS, Milwaukee, Wisconsin  
Evinrude Motors of Canada, Peterboro, Canada

**EVINRUDE**  
OUTBOARD MOTORS

*\*A pint of your blood can save the life of a wounded soldier or sailor. The need is constant, pressing. Call your local Red Cross Chapter for an appointment.*

# "Sonia Guns"

NINETY pounds of *fire-power*,—that's the .50 caliber Browning machine gun that AC builds by the thousands, night and day

Manufacturing these guns demands the highest order of split hair accuracy. Yet, the Army knows that good manufacturing is not enough to keep those guns in trim. So, they are cleaned, oiled and adjusted in strict accordance with rigid Army requirements.

## A Special Message for You


AC has been producing another kind of *fire-power* since 1908. It's the precision-built AC Spark Plug.

The chances are good that you drive with AC's. But, whether you do or not, your spark plugs need to be cleaned and adjusted,—to make them last longer, save gasoline, and improve starting ease.

Your automotive service man can do this for

you. He can also give Conservation Service, outlined in the panel below, on the right of our AC products

Make regular use of this Conservation Service. When replacement is necessary, select AC—for complete satisfaction

 Awarded to AC on September 2, 1942, and renewed June 19, 1943, for outstanding achievement in producing for Victory

AC SPARK PLUG DIVISION  
GENERAL MOTORS CORPORATION

BACK THE ATTACK—WITH WAR BONDS!

## SPARK PLUGS

**SPARK PLUGS**—Dirty or worn plugs waste up to 10% on gas. They also cause hard starting, weaken your battery. Have your plugs cleaned and adjusted every few months.

**FUEL PUMPS**—Practically trouble free. But, if yours has been in use thirty or forty thousand miles, a check-up may be due.



Spark Plugs



Air Cleaners



Fuel Pumps



Oil Filters



Driving Instruments

**AIR CLEANERS**—A dirty air cleaner chokes down the flow of air into the carburetor. Your air cleaner should be rinsed whenever your car is lubricated.

**DRIVING INSTRUMENTS**—Speedometer, gasoline gauge, oil pressure gauge, ammeter, and temperature gauge seldom need service.

But, if they give trouble, have them cared for *at once*.

**OIL FILTERS**—Slow driving accelerates formation of soot and carbon in engine oil. This dirt will clog piston rings, cause increased consumption of oil and gas. Replace your oil filter element whenever your dealer's AC Oil Test Pad shows that your oil is dirty.



# KEEP THOSE TOOLS SHARP!



**W**ITH sharp tools you can turn out better work—and do it faster! Not only that but sharp tools last longer. And that's important today when your present tools have to do until the war's over.

The easiest way to have sharp tools is to keep them that way—with Carborundum Brand Silicon Carbide Combination Sharpening Stones. They are made with one side coarse and one side very fine grit. Use the coarse side to sharpen very dull tools and the fine side for giving that smooth, keen edge that makes work fun. Ask your dealer for Carborundum Brand Silicon Carbide Combination Stone No. 109.



**P.S.** And be sure to write for your copy of "Short Cuts to Better Work For The Home Craftsman". It's free for the asking. 100

pages full of practical suggestions and how-to-do-it pictures on how to sharpen tools.

**CARBORUNDUM**

**MAKING TOOLS SHARP**

Dept. S-113

**THE CARBORUNDUM COMPANY**

REG. U. S. PAT. OFF.

**Niagara Falls, N. Y.**

(Carborundum is a registered trade-mark of and includes manufacture by The Carborundum Company)

## Props for Our Warplanes

*(Continued from page 212)*

leaving the outboard props in normal pitch, the pilot of a four-engined flying boat can "come about" in one-fourth the turning radius of a similar craft with conventional propellers.


Under the most favorable conditions, the prop is capable of translating 86 percent of the engine's horsepower into useful thrust, and props have a specific weight of between .22 and .38 pounds per horsepower. (There are only three or four aircraft engines in the world that are known to have a weight-horsepower ratio of less than one pound per horsepower.) It is because there is so little room for improvement that propeller engineers are burning up much midnight oil and energy in their quest for increased power-plant performance.

It has been mentioned that the adaptation of the laminar-flow airfoil section—which holds the stream of passing air close to the surface and cuts down turbulence and drag—to prop blades increased their efficiency, and that engineers have sought to increase the blade area to gain more thrust and absorb the output of higher-horsepower engines. The compressibility phenomenon of the shock wave makes the engineers hesitate to increase blade diameter. Bigger props could be used only if they were geared down to turn slowly enough that the tips would not reach the speed of sound. When an airfoil attempts to exceed this speed, the pressure wave created at its leading edge cannot move ahead of the airfoil. The compressibility cannot get out of the way of the wing or propeller and must be carried along with it, just as the bow wave of a steamer is cast upward instead of outward along the surface when high speed is attained. Unlike the much denser water, the air has nowhere to go and must be dragged along, coating the propeller with tightly packed, turbulent air that does nothing but create such drag that the airfoil loses much of its thrusting ability.

Hamilton Standard engineers increased their blade area without extending the diameter by making the blade paddle-shaped from the shank outward. The paddle blade is wider, with a more rounded tip, and is still structurally strong enough at the shank to withstand the many stresses. There is, however, a limit to the width of the blade. The ability to absorb the engine's power increases directly in proportion to the width of the blade, but, unfortunately, the weight increases with the square of the width.

*(Continued on page 218)*

For Men Who  
Really Know Pipes

Royalton 



Royalton  
COMMANDER



Royalton  
TRAVELER

Royalton Silver Crown — *Choice Grains* — \$5

It's "that little more" that brings success in life. So with pipes. A Royalton adds that extra something to make a good tobacco taste better. Because this greater satisfaction brings enduring pleasure, a knowing smoker and his Royalton are seldom parted.



WHEREVER BETTER PIPES ARE SOLD





**Dear Jim:**

**You ought to see**

the interest in motorcycles around here. When our outfit comes in from maneuvers the fellows all crowd around asking questions and begging rides. Believe me, our Club is going to have plenty of new riders after the war.

These military Indians are honeys! They take punishment like regular champs -- and they're easy to handle and safe, just as Indians have always been. Wish I could tell you about the new Indian improvements, but military secrecy won't let me. Regards to all the Club members.

INDIAN MOTORCYCLE COMPANY, SPRINGFIELD, MASS.



**BUY WAR BONDS NOW**

★ ★ TO BUY AN INDIAN LATER ★ ★

## Props for Our Warplanes

*(Continued from page 216)*

When the blade is made thicker, it displaces more air and builds up compressibility more readily.

There are still other more involved limitations. One of these was the problem of cooling the radial-type engines, since the slip stream, or backwash of air from the prop, is hollow in the middle because of the blades' shape. This was overcome by fitting the blades with cuffs that continue the airfoil shape right down to the hub. This additional surface provides larger thrust area and also brings the hole in the center of the slip stream down almost to nothing. Part of the backwash is then able to enter the engine cowl and contribute to cooling.

The next obvious step in gaining thrusting area was the use of more blades. When planes began to use the bigger engines, the demand for more than three blades forced engineers to solve the vibration problems introduced by four- and six-bladed props. Four-bladed propellers of wood were used in World War I, and were reintroduced by Curtiss in hollow steel form in 1939. Planes that use four-bladed props include the Martin Marauder, Republic Thunderbolt, North American Mustang, and Britain's Spitfire IX (with a British Rotol prop).

The ultimate in props today is the four- or six-bladed dual-rotation job, which consists of two units mounted on coaxial shafts which turn in opposite directions. Even these have been fitted with constant-speed, feathering hub mechanisms by Curtiss, Hamilton Standard, and General Motors, and by Rotol and De Havilland in Britain. They are, literally, two propellers and naturally are heavier than a single prop. But because they can be of smaller diameter and blade width, the weight is not actually doubled but is only about one third greater. The dual-rotation props are worth their weight in performance. First of all, they do away with the evils of torque, or swinging action in flight, since the torque of one set of blades cancels out that of the other unit. Shorter landing gears can be used because of the smaller blades, and this results in a great saving of weight and improved landing behavior of the plane. At speeds around 400 miles per hour, the contra prop increases aerodynamic efficiency more than five percent. The rear prop picks up the whirling slip stream of the forward set of blades and converts it into useful thrust.

The engineers are hard at work on still newer ideas, but the dual-rotation prop will be with us for many years to come.



STYLED BY MASTER CRAFTSMEN



IT'S THE LITTLE THINGS THAT COUNT  
and cutting shoes out of skins is our process that calls for skill and perfect vision. The cutter must get the most possible "cuts" out of each piece of leather—always still scrupulously avoiding any flaws.

## STYLED for GOOD LOOKS

It takes 8 full days—and over 130 separate hand and machine operations—to make a single pair of W. L. Douglas Shoes. It takes accuracy and skill, too, and more patience than you'd think possible. For the experts who make W. L. Douglas Shoes take pride in perfect work—and they aren't satisfied with less.

That's why, today, men everywhere are buying W. L. Douglas Shoes with their ration coupons. That's why you should see our new Fall shoes today. They're styled for good looks . . . and priced for honest value.

**W. L. Douglas Shoes**  
W. L. DOUGLAS SHOE CO., BROCKTON, MASS.  
Stores in Principal Cities—Good Dealers Everywhere

at "Save for War Bond Prices"



### The Commander

A favorite of service men and civilians is this tan pair of military oxford. Rugged leather sole for all-weather comfort. No 4563. In Black, No 4635.


**\$6.50 \$8.50**

Other styles at \$5.50

### The Wingtip

Handsome mocassin style oxford in rich brown leather—with Douglas Flex soles for longer wear, greater comfort. No 4516.

Douglas Down to the Bottom construction assures you better




Construction of W. L. Douglas Shoes

BUY WAR BONDS AND STAMPS FOR VICTORY



## HOW TO GRIND CUTTERS FOR WILLIAMS' TOOL HOLDERS



## FREE! WILLIAMS' TOOL DATA SHEETS

These two Williams' Tool Data Sheets graphically explain how to grind cutters—give correct included angles, clearances and rakes. Also instructions for set-up and use. Other Data Sheets are listed below. Circle the number of those desired on coupon and mail today. They're punched for 3-ring binder.

- |  |  |
|--|--|
| 1. Characteristics of Williams' "Superior" Wrenches. | 9. Having Time with Williams' "Superoscopes"   |
| 2. Data on Williams' Boring Tools.                   | 10. Data on "Vulcan" Eye Bolts.                |
| 3. Data on "Vulcan" Chain Pipe Tongs.                | 11. Data on Williams' "C" Clamps.              |
| 4. Data on Williams' "Hopscocket" Wrenches.          | 12. Use of Williams' Cutting-Off Tool Holders. |
| 5. Data on "Vulcan" Lathe Dogs.                      | 13. Use of Williams' Knurling Tool Holders.    |
| 6. Data on "Vulcan" Chain Pipe Vises.                | 14. Use of Williams' Threading Tool Holders.   |
| 7. Data on Williams' Turning Tools.                  | 15. Internal Threading with Williams' Tools.   |
| 8. Data on Williams' "Superior" Wrenches.            | 16. How to grind Tool Holder Cutters, Sheet A. |
| 17. How to grind Tool Holder Cutters, Sheet B.       |  |

## MAIL THIS COUPON

J. H. Williams & Co., Dept. S-1143, Buffalo 7, N. Y.  
Please send Data Sheets circled below:

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17

Name \_\_\_\_\_

Address \_\_\_\_\_

City \_\_\_\_\_ State \_\_\_\_\_



## "Seeing" the Weather

(Continued from page 95)

Because of the help they might afford the enemy, official weather reports are out for the duration. But there's no reason why you can't learn to be your own weather man. Here are a few simple "hows":

If a summer sky has small cumulus clouds which don't tend to grow larger by noon, you can bank on clear weather.

If you see a bank of cumulus clouds that is growing and building up to a summit, look for rain, hail, and lightning.

If there is a cloud layer over the horizon, and it begins to form turretlike shapes at its top, you are in for squalls.

If you see high bands of clouds extending east and west and moving fast, it means that there is a cold snap on the way.

If clouds clot into thick masses and blot out the sun, duck for cover.

## Brain-Teasers in Uniform

(Answers to problems on page 89)

- His weekly pay is \$99.98.
- 295 bombs.
- Here is one of the possible solutions:



- Boat D enters P. Boats A, B, and C pass P. Boat D goes on its way. Boats A, B, and C return to the other side of P and same operation is repeated for E and for F.
- The two hands are together at  
12:00 Noon  
1:05  $\frac{1}{2}$  A.M. and P.M.  
2 11 " " "  
3 16  $\frac{1}{2}$  " " "  
4 22 " " "  
5 27  $\frac{1}{4}$  " " "  
6 33 " " "  
7 38 " " "  
8 43  $\frac{1}{2}$  " " "  
9 49 " " "  
10 54  $\frac{1}{2}$  " " "  
12:00 Midnight  
134 sentries stand watch.
- Outfit A, which receives \$144. Outfit B receives only \$72.
- A man could; but a ship might not be able to. The wire would be about 16 feet above the surface of the earth.



## "Maybe next year, Queenie!"

"Mallards! Gosh, don't they remind me of some swell times!

"Gets you kind of excited too, Queenie, doesn't it? I understand. My dog was a lot like you, and I know how he loved hunting.

"There'd be cold, gray autumn mornings when the wind almost blew our ears off. Just the right weather for ducks. I'd paddle us out to our favorite hunting place in the marsh. Pretty soon our wooden decoys would be hobbin' away, natural as life, and a big flight of mallards would start down to get chummy. Then—*whammo!*

"No matter how far away the ducks dropped, that dog of mine

used to retrieve 'em every time. I'll bet you did too. And boy, what wouldn't we both give to do some duck hunting this season!

"But there's a war on now, Queenie. We're in the Coast Guard, and we've got a job to do. Maybe next year . . ."

\* \* \*

Remington's job right now is to supply a lot of military arms and ammunition fast—to help speed, among other things, the return of hunters and hunting dogs to their favorite marshes. Here is what we are doing . . .

1. *Every working day, Remington pro-*

*duces thirty million rounds of military small arms ammunition.*

2. *And, every working day, Remington produces more than enough military rifles to equip an entire infantry regiment at full fighting strength.*

After the war is won, we will again be serving our sportsmen friends with Remington shotguns and rifles, Nitro Express shells, Kleanbore Hi-Speed .22's, and Core-Lokt big game bullets. *Remington Arms Company, Inc., Bridgeport, Conn.*

"Nitro Express," "Kleanbore," "Hi-Speed," "Sportsman," "Rev U S 1st Off," "Core-Lokt" is a trade mark of Remington Arms Co., Inc.

**HELP YOURSELF LATER BY HELPING YOUR COUNTRY NOW. BUY WAR BONDS!**



Remington Sportsman 2-shot auto-loading shotgun and Nitro Express shot shells

# Remington





*"Good Pictures"  
bring you  
together*



Send your soldier "Good Pictures"... of the old familiar scenes... the home place, the best girl, the old fishin' hole, sister Mary's new baby, the puppy now a dog, the cabin up the river... all the happy scenes of home sweet home. That's what counts a thousand miles from nowhere.

Make the most of your present camera! Take good care of it, and conserve vital film by making each picture a good picture. After Victory Argus will make new cameras... employing the new techniques and extensive experience acquired in War Production.

FINE AMERICAN CAMERAS  
PRECISION OPTICAL INSTRUMENTS  
AVIATION RADIO EQUIPMENT  
BUY WAR BONDS



AWARDED TO PLANT 2  
OF THE DIVISION

*"Good Pictures"*

Make the best use of your present equipment — learn more about lenses — films, filters and composition. Send 25c today for this 56-page booklet



# Men with Mechanical Ability Needed in Vital Shipyards

Here's a chance for men who know how to use tools and operate machinery to get into a vital war job—just about the most important job a civilian can do. Thousands of men and women are needed *now*—to build and repair ships.

If you are not now engaged in war work, get a job in one of the repair or shipbuilding plants of the Todd Shipyards Corporation.

You will be well paid while you take a fighting crack at the enemy. Mail the

coupon today and be sure to indicate the city in which you prefer to work. We will advise you of the proper U. S. Employment Service office through which you may discuss employment.

No placement fee. Persons in essential activities cannot be considered without statement of availability.

***If inexperienced you are  
paid while learning.***

Todd Shipyards are located in:

BROOKLYN, N. Y.	HOUSTON, TEXAS
HOBOKEN, N. J.	SEATTLE, WASH.
S. PORTLAND, MAINE	TACOMA, WASH.
GALVESTON, TEXAS	NEW ORLEANS, LA



"I'm in a shipyard to help get my two boys home safe. That's what we're working for—to help our fighting men finish the job fast. We need your help. How about clipping that coupon right now?"

*C. L. ERICKSON, Todd Foreman*

Mail to

TODD SHIPYARDS CORP., Employment Dept.  
One Broadway, New York 4, N.Y.

My occupation is \_\_\_\_\_

Draft status \_\_\_\_\_

Also know \_\_\_\_\_

Prefer to work in (name of city) \_\_\_\_\_

Name \_\_\_\_\_

Street \_\_\_\_\_

City \_\_\_\_\_ State \_\_\_\_\_

## Todd Shipyards Corporation

ONE BROADWAY  
NEW YORK


*for more than a quarter of a century, builders and repairers of fighting ships for the U. S. Navy . . . merchant ships for all the world*







# Atlas MILLING MACHINE



## ON EVERY FRONT WHERE PRECISION COUNTS

Millions of dazed Germans fleeing devastation from the air . . . captured Nazi supermen cowed and begging to see our "automatic cannon" . . . Jap warships sunk in pitch black night, out of sight but not out of reach — such military miracles are tributes to the American ingenuity and the production ability of American industry.

We're proud that in thousands of war plants, and in the mobile machine shops of our armed forces, compact modern Atlas machine tools are picked for the precision work that helps make such victories possible.

Typical of Atlas development for war production is the Milling Machine — shown above — first low cost bench milling machine. It handles the full range of milling on small parts, relieves larger machines of such work, and maintains precision production day after day. It's a good tool to remember for your post-victory shop.



### ATLAS PRESS COMPANY


1155 NORTH PITCHER STREET, KALAMAZOO 13D, MICHIGAN

NOVEMBER, 1943

Buy War Savings Bonds and Stamps regularly.



LATHES



SHAPERS



DRILL PRESSES

★ BUY WAR BONDS NOW ★

FOR A NEW *Atlas* SHOP AFTER THE WAR



# HOW TO CHOOSE A GLUE

Don't think that there is any one glue that does all gluing jobs. Here are two simple rules to follow.

## RULE 1

**USE CASEIN GLUE:** For all interior or protected construction—furniture, cabinets, toys, laminated trusses and beams, interior wall panels and all types of "odd jobs".

**REASON:** Casein Glue (CASCO) is easier, more fool-proof to use than resin. CASCO is "self-bonding," needs only moderate, not extreme pressure. Has "filling action" on poorly fitted joints. Highly water-resistant, withstands any interior conditions except extreme dampness or mold. Used at any temperature (above freezing).

## RULE 2

**USE RESIN GLUE:** Where a water-proof, moldproof or stainfree glue is required—boats, outdoor furniture, screens, in damp basements, on thin veneers, etc.

**REASON:** Resin Glue (CASCAMITE) is completely waterproof, moldproof, stainfree. (Resin glue requires well-fitted joints, smooth wood surfaces, positive clamp pressure and workroom temperature of at least 70° F.)



**CASCO Powdered Casein Glue**  
Meets Army, Navy and Federal casein glue specifications. Highly water-resistant. Cold water mix. 10¢ to 65¢ at hardware stores.



**CASCAMITE Powdered Resin Glue**  
The same type of glue used for Army and Navy life floats, truck bodies, other field equipment. Mixes instantly in cold water. 10¢ to 85¢ at hardware stores.

## FREE GLUING GUIDE AND PROJECT BOOKLETS

**CASEIN COMPANY OF AMERICA** Dept. PS-11  
350 Madison Avenue, New York 17, N. Y.

- Send me the literature checked.
- ☐ "GLUING GUIDE". Complete directions for both glues. Over 80 home workshop jobs.
  - ☐ "CASCO PROJECTS". Describes 24 furniture projects by famous American designers. How to get free plans.
  - ☐ "CASCAMITE WATER PROJECTS". Describes 12 new boat and water projects by Wm. F. Crosby. How to get free plans.

NAME \_\_\_\_\_

ADDRESS \_\_\_\_\_

-----Save 2¢—Stick coupon on penny postcard-----

Buy War Savings Bonds and Stamps regularly.

# FREE! LATEST, MOST COMPLETE RADIO PARTS CATALOG



**EVERYTHING in RADIO and  
ELECTRONICS for War Train-  
ing, Maintenance or Repair**

It's the most complete, up-to-date BUYING GUIDE available! It contains latest "supply data" on radio and electronic parts available without priority for repair and replacement—plus everything in war training kits, books and equipment! Whatever you need—you'll save time by getting in touch with ALLIED first. Send for this big free catalog today.



## RADIO'S FINEST BOOK VALUES

Specially prepared to aid radio training in schools and industry. Full of valuable data. Send for all six!


- Radio Formulas and Data Book No. 37-732. 10c
- Dictionary of Radio Terms No. 37-731. 10c
- Radio Circuit Handbook No. 37-733. 10c
- Radio Builders' Handbook No. 37-730. 10c
- Simplified Radio Servicing No. 37-735. 10c
- Radio Data Handbook No. 37-734. 25c
- All Six Books No. 37-799. 75c

**ALLIED RADIO CORP.**

632 W. Jackson, Dept. 7-L-3, Chicago

# ALLIED RADIO


## POWERFUL VISION — LONG RANGE



### 6-POWER TELESCOPE \$2.49

Perfect for spotting ships, planes, watching sporting events, people, birds, etc. Genuine black life-size picture. Scope has 6x magnifying lens. 33 mm. lens. Objects 600 yards away appear as 40 yds. distant. Sample to focus on both day and night. Only objects 15 DAYS FREE TRIAL. If not fully satisfied, return for refund. SEND NO MONEY. Just pay postage \$2.49 plus few cents postage on delivery. Cash order sent postpaid. Limit one purchase of telescopes may be carried as it has been on liberal terms. Vorse Telescope Co., 7155 S. Halsted, Dept. B-408, Chicago.


## OTTAWA LOG SAW



### Write for FREE BOOK

PUT THIS OTTAWA to work for you.  
MAKE MONEY! Wood is valuable.  
10 men easily  
cut trees—and saw  
Use 5-hp. engine for  
work.  
OTTAWA MFG. CO.  
1101 Wood St. Ottawa, Kans.

## MASTER DRAFTING MACHINE



● Biggest time-saver for dimensioned sketches, lettering and layouts ever sold at—This Low Price—While they last. Limited Supply, only

**\$3.95**

ORDER TODAY

**RANDOLPH RADIO** 611 West Randolph St. CHICAGO-ILLINOIS





Here's how you can plan now for

*More Fun and  
more Profit-with*

# DELTA POWER TOOLS

*..in your after-the-war home workshop*

Get ready for exciting adventures in homecraft with the great new tools that are coming!

You can start today to lay the ground-work for a shop that any home craftsman might envy. A shop where you can do things you hardly thought possible — using the new Delta Power Tools that are on the way — finer, faster, safer, better-looking than any pre-war tools.

As we make thousands of Delta Tools for vital war work, we add to the "know-how" that has already established Delta Tools as the finest in the field. You get the benefits, as you create objects that are more beautiful and more saleable, and do it with greater ease, greater safety, and greater pride than ever before.

HM 4

## 3 things to do NOW . . .

Though Delta's entire output today is needed for war work, there are three steps you can take now to assure the maximum of enjoyment, healthful recreation, and earnings from your post-war workshop.

**1. Get Delta's help in planning**  
Now you see "How to Plan a Home Workshop," a 56-page book to help you in laying out and equipping an efficient, attractive home workshop. It's packed with practical ideas. It gives you how to information on dozens of subjects, from Shop Layout to Tool Racks.

Let this book help you save time and money, avoid waste of effort and materials. Use the coupon below and send for it today.

**2. Build cabinets, accessories**  
Get ready for the day of "full production." Tool racks, cabinets, storage racks and other equipment can be prepared. Use ideas from the book below.

**3. Buy War Bonds with a goal**  
Decide on the power tools you want. Then "ear-mark" your War Bond purchases and make your dollars work two ways for future happiness.

**Only 25¢** "How to plan a Home Workshop" — 56 pages of practical, tested ideas and helps — pictures of typical shops — plans, designs, layouts. Fill out coupon below and send it with 25¢ in stamps, check, or money order.

Tear out and mail coupon today



THE DELTA MANUFACTURING CO.  
652M E. Victoria Ave., Milwaukee 1, Wis.

I am enclosing 25¢ for my copy of "How to Plan a Home Workshop."

Name \_\_\_\_\_

Address \_\_\_\_\_

City \_\_\_\_\_ State \_\_\_\_\_





## TOOLS FOR MACHINISTS AT WAR



The manufacturing might of all America is concentrated on producing for victory. In the front rank of this vast industrial army are the machinists—and their weapons are tools!

In plants everywhere throughout the nation machinists are busy at every phase of their craft—helping to turn out more, faster, with tools by Disston. Some of the machinist's tools supplied to industry by Disston are the files used every day in general machine shop work, Superfine Swiss pattern files for precision work, file cards, hack saws, hack saw blades, metal cutting hand saws, metal cutting band saws, solid and inserted tooth metal cutting circular saws, metal cutting sabre blades, tool bits, machinist's chisels and others.

● If you need a hand saw for essential war work, see your Hardware Dealer about

### DISSTON D-7



Lightweight Straight-back pattern. Universally popular, moderately priced, Disston quality. Made in 26-inch 7, 8, 10 and 11 points cross-cut, 5½ points rip.

**KEEP TOOLS WORKING** with the help of the Disston Saw, Tool and File Manual—FREE from your Hardware Dealer . . . or write for a copy.

**HENRY DISSTON & SONS, INC.**  
1110 Tacony, Philadelphia 35, Pa., U.S.A.

## MOVIE MAKERS

**\$1500.00 FOR**

IDEAS

IDEAS

IDEAS

## 8MM CAMERA AND PROJECTOR COMPETITION

You who know what YOU want in the next motion picture camera you buy—what YOU think will simplify and perfect the operation of your postwar motion picture projector—this is YOUR OPPORTUNITY to share \$1500.00 in U. S. War Bonds (maturity value) that DeVry Corporation will award the best and most practical ideas for TOMORROW'S 8MM MOTION PICTURE CAMERA & PROJECTOR. Submit IDEAS in rough or finished drawing—with brief comments if you desire . . . the IDEA is what counts. Write today for details—award amounts—Official Entry Blank. There's no obligation. Competition closes midnight Dec. 31, 1943. DEVRY CORPORATION, Dept. 8-PS, 1111 Armitage Avenue, Chicago, 14, Illinois.



**DEVRY**



AN OUTSTANDING NAME IN THE CINEMATIC WORLD

## 3 in 1 RADIO TUNER Only \$1.00 Postpaid



1. Aerial Eliminator
2. Antenna Tuner
3. Wave Trap

Eliminates hums, clicks caused by static rain wind etc. Replaces old inefficient out-couplers. Works at any frequency anywhere. The 3 in 1 improves the reception of weak stations, separates interfering stations, gives you greater volume and distance. Uses no power, lasts life of radio. Also works on battery radios. Takes no time to connect. 15 DAY FREE TRIAL. SEND NO MONEY. Simply pay Postman \$1.00 plus few cents postage or we will send postage for one dollar bill. Vague Eliminator Co., 7759 S. Halsted, Dept. E-754, Chicago.

## SYNCRO

## Torpedoes the Axis!

Synco Electric Jig Saws are busy torpedoing the Axis in the shape of SYNCRO-machined parts for submarines, bombers, tanks, guns, etc. Meanwhile Synco research guarantees better Synco Saws for you after Victory!

**SYNCRO SAWS**



**SYNCRO DEVICES, INC.**  
3285 Bermuda Ave.  
Dept. PS 113  
Pawtucket 20, Michigan



*What kind of "window blinds" do you want for your home after the war?*

# TELL US...YOU MAY WIN \$200.00\* IN WAR BONDS OR ONE OF THE 41 OTHER PRIZES, TOTALING \$500.00

## WHAT HAS BEEN DONE



Many years ago, window drapes and shutters were used to regulate light and give privacy.

About 1864, the spring roller for cloth shades was perfected. Since then there have been few changes in this roller, or in cloth shades.



Fifteen years ago, CLOPAY perfected and introduced cellulose fiber window shades which looked like expensive cloth shades, but cost about 1/3 as much.



Then women asked: "Why can't you make a shade to attach to our old rollers so we can afford to put up fresh, clean window shades every year?" So CLOPAY invented the gummed strip which makes it easy to attach a new CLOPAY shade to an old roller—without tacks or tools. These "refill" shades still sell for 18c, 15c—with lovely washable ones for only 29c.





Next, Venetian Blinds for all. CLOPAY developed Venetians with sturdy curved fiber slats that look like the smartest steel and wood Venetians. They cost about half as much—\$1.69 to \$2.19.

What's your pet window shade peeve? How would you remedy it? What gets your goat about Venetian Blinds? How would you improve them? Have you a brand-new, bright idea about window blinds?


## WHAT MIGHT BE DONE

For instance, you may have an idea for a window shade that pulls from side to side. Such a shade could be made.



Or, perhaps you'd like a Venetian Blind with slats of glass or some other material. Maybe you have an idea for an entirely new kind of slatted shade.

How about an accordion-type blind—one that lets down from the top, or pulls up from the bottom?



Let's have your ideas and suggestions for the window blind. CLOPAY is planning for the brighter homes of tomorrow. And even the simplest thought may win one of the 42 prizes. It may be a suggestion for a new pattern, color or material...an idea for improving wearability...a new way of hanging, pulling or adjusting. Read the easy rules and get busy this very minute.

Your idea or suggestion may be the very one to win that \$200.00 in War Bonds\* or one of the other valuable prizes. You'll find it fun to try your hand at postwar window shade planning. And wouldn't it be grand to win? Sit down, write your letter, now.

## CLOPAY CONTEST RULES


1st Prize \$200 in War Bonds\*  
2nd Prize \$100 in War Bonds\*  
Next 40 Prizes Each, \$5 in War Stamps

1. Write a letter telling us what you think is wrong with window shades or Venetian Blinds, what changes you would like after the war. Suggest if you can how these improvements might be made. Or briefly explain any brand new idea you have for window blinds. Write plainly on one side of paper only.
2. Mail your entry to CLOPAY Corporation, 1278 CLOPAY Square, Cincinnati 14, Ohio. All entries must be mailed no later than midnight, December 31, 1943.
3. Entries will be judged on the basis of originality of idea, maturity value.
4. No entries will be returned. All entries, ideas and contents thereof become the property of the CLOPAY Corporation.
5. This contest is open to any resident of the United States or Canada, except employees of the CLOPAY Corporation or its advertising agency and their families, and is subject to all Federal, state and local laws and regulations.

# CLOPAY WINDOW SHADES

On sale at 5-2-10c and neighborhood stores everywhere.





WHAT YOU CAN  
JACOBS CHUCK

DO WITH YOUR  
and a WIRE BRUSH

Hard surface deposits that defy ordinary removal methods quickly give way under the harsh, scratching action of the stiff wire end brush. These brushes, held by the JACOBS Chuck in a drill press or lathe, remove rust, baked-on grease, scale, and paint.

In the photo above a small casting is being burnished. Note how the wire brush gives finish to a dull casting. With a softer brush brass, copper, and other non-ferrous metals are given a soft satiny finish.

**If You Have A Drill Press or Lathe,  
or Are Planning on  
Getting One, You Will Want This Book**

The operation outlined briefly here is one of nineteen covered in detail in our new booklet just off the press. It gives practical, helpful information on unusual and varied uses for drill presses and lathes. Printed in color and containing 49 illustrations, it shows how the set-ups are made, illustrates the tools used, and in some instances tells you how to make the tools themselves. If you have a workshop you will want the valuable ideas this booklet contains. If you are planning on having a shop of your own after the war, you will want the booklet now to help you plan.

10¢

19  
UNUSUAL USES

DRILL PRESS  
OR LATHE

**Jacobs Chucks**  
WORLD'S LARGEST PRODUCERS OF DRILL CHUCKS

Jacobs Mfg. Co.  
2113 Jacobs Road, Hartford Conn.  
Please send me the booklet immediately  
I am enclosing 10¢ to cover handling and  
mailing costs.

**THE THIN  
GLUE-LINE  
THAT  
WON'T CHILL**

EVERY DROP WORKS

Spread Franklin Liquid Hide Glue thinly. Its extra strength makes the thin glue-line possible with no chilled joints. FRANKLIN is ready to use; no mixing, no heating.

**FRANKLIN**  
*Liquid Hide* **GLUE**  
AT YOUR  
HARDWARE DEALER

IF YOUR HARDWARE DEALER CANNOT  
SUPPLY YOU send 25¢ for 1/4-pint to  
The Franklin Glue Co., Columbus 3, Ohio.



**ONAN**  
ELECTRIC PLANTS

**Electricity for Any Job—Anywhere**

ONAN GASOLINE DRIVEN ELECTRIC PLANTS provide electricity in locations where it is not otherwise available, and for emergency and standby service. Thousands doing a winning job in the war.



Sizes from 350 to 35,000 watts, A.C. 50 to 800 cycles, 110 to 660 volts D.C. & to 4000 volts. Also dual A.C. and D.C. output models. Air or water cooled. Details gladly furnished.

**D.W. ONAN & SONS**  
1809 Royalton Ave., Minneapolis, Minn.

LUBRICATES • CLEANS • POLISHES • PREVENTS RUST

**3-IN-ONE**  
*Heavy Body*  
**OIL**

**PROTECTS  
LIGHT  
MOTORS**




At Hdwe., Drug,  
Grocery and  
10¢ Stores



*Ah-h-h!...that  
wonderful BRIGGS!*

The short cut to a long education in pipe-tobacco is—a package of Briggs right now. You'll see right off that Briggs is the grand prize of pipedom, from the first fragrant, tantalizing sniff to the lingering delight of its luxurious, caressing taste. Because Briggs is cask-mellowed for years—longer than many costly blends—and you harvest all its full-ripe richness! So go to it, man—try a package of Briggs today.



**BRIGGS**

The Smoke with  
a Smile



PRODUCT OF P. LORILLARD COMPANY

## New "TRIG" 10" Slide Rule

S&T Scales Added



**\$1**

### SPECIAL OFFERS

28-page instruction book and slide rule carrying case included in all offers.

No. 1—New "TRIG" 10" Slide Rule with S, L, and T scales; Gun-metal Finish Indicator. \$1.00 postpaid.

No. 2—Standard 10" Slide Rule (A, B, C, D, CI and K Scales only). 50c postpaid.

No. 3—New "TRIG" 10" Slide Rule, Pocket Calculator for adding and subtracting up to 999,999. 6" Transparent Protractor and Graph Rule graduated in centimeters and inches. \$1.50 postpaid.

No. 4—Standard 10" Slide Rule, Pocket Calculator, Transparent Protractor and Graph Rule. \$1.00 postpaid.

FOREIGN—add 10c to each price.

To insure getting Yours Promptly—**Mail Coupon NOW**

Standard 10" slide rule with A, B, C, D, CI and K scales on face plus S, L, and T scales (SINE, LOG, TANGENT) on reversible slide for problems in trigonometry.

Enables you to make difficult calculations instantly without paper or pencil—in multiplication, division, proportion, squares and cubes, square and cube roots, logarithms, and trigonometrical problems.

Guaranteed or money refunded. (See Special Offers)

NEWIG CO., Box R-143, Grand Central Annex, New York, N. Y.

Enclosed is remittance covering Special Offer checked below

SPECIAL OFFER

(PLEASE PRINT)

Name

Address

☐ No. 1

☐ No. 2

☐ No. 3

☐ No. 4



# ATKINS

**FINE SAWS**  
*deserve*  
**FINE CARE**



Atkins "2000" Hand-saw—one of a wide range of types, sizes and styles of quality saws.

● A fine saw is something to be proud of—a tool deserving of special care, particularly in these days when tools are such important weapons on the home front. If your saws are Atkins, you can expect plenty from them in the way of easy handling, accurate work and edge-holding qualities. That's all the more reason to treat them well—to guard them against unnecessary rough handling or neglect.

Send Only 10c for Useful  
"How To Do It" Book

**E. C. ATKINS AND COMPANY**  
428 South Illinois St., Indianapolis 9, Ind.



Buy War Savings Bonds and Stamps regularly.

## INTRODUCING-New Victory Model HANDIWELD · ELECTRIC ARC WELDER

FULLY  
GUARANTEED

RETAILS  
ONLY  
**\$1.95**




### PLUGS INTO LIGHT SOCKET

Victory Model Handiweld Arc Welder operates from 110 volts, A.C. or D.C. current same as other arc welders higher priced generates tremendous heat to weld all metals. Not a toy welder that uses carbons but actually uses standard coated rods—sizes 1/16" and 3/32". However, due to Priorities a generous supply of 1/16" rods only are supplied with the welder. Guaranteed not to burn out. Repairs fenders, auto bodies, radiators, etc. Take it home or use it anywhere. Operate right from light socket. You find a

thousand uses for this welder. Your home garage, repair shops, tin shops, farmers, etc. etc. now **MAKE NO MONEY**. You need helmet, operating instructions and necessary parts with the exception of a large jar and a small piece of extension cord. These most everyone has. Pay postman only \$1.95 plus a few cents postage. If not delighted return Victory Model Handiweld in 3 days from receipt and money paid for it will be refunded promptly. Rush your order now.

**KUMFY PRODUCTS INC., Dept. W-205, Cincinnati, Ohio**

### 110-VOLTS AC from DIRECT CURRENT



**KATO ENGINEERING CO.,**  
207 Elm St., Mankato, Minn., USA



Clean out car radiators thoroughly  
before adding anti-freeze. Use

**Sani-Flush** 10c and 25c sizes  
Directions on can



### TRAILER BUILDERS' PARTS CATALOG


Will save you money on everything. Largest  
catalog of trailer parts. **NATIONAL TRAILER EQUIPMENT CO.**  
219 N. Seventh St. Milwaukee 3, Wis.

## QUICK REPAIRS!

Holes and cracks in  
floors or baseboard  
can be quickly re-  
paired with Plastic  
Wood. Handles like  
putty, hardens like  
wood. At Paint, Hard-  
ware and 10¢ Stores.



**PLASTIC WOOD**



THERE IS NO SUBSTITUTE  
FOR EXPERIENCE



## FIRST COUSIN TO A PURSUIT SHIP



The Sea-Horse outboard motor, being a little fellow, doesn't roar. It purrs. But its purr results from the same characteristics that distinguish airplane motors—sheer quality, high relation of power to pounds, and smooth, **DEPENDABLE** operation.

Fact is, Johnson used aluminum to revolutionize small motor design way back in the days when intrepid fliers were barnstorming in crates. Stainless steel, chrome, molybdenum and nickel alloys and other fine metals followed—until Sea-Horses were composed almost entirely of the materials *most urgently* needed in the Nation's present program of war plane construction.

Today's Sea-Horses are all for the armed services. Tomorrow's Sea-Horses, built out of twenty years' experience, will be revelations in performance. • Johnson Motors, Waukegan, Illinois.

DO YOUR DUTY — BUY WAR BONDS

# JOHNSON SEA-HORSES

for **DEPENDABILITY**

## The Machine of 1000 Uses New DURO HAND GRINDER



only  
**\$15.95**



**T**HE ideal hand grinder for craftsman and model makers. The DURO Heavy Duty Grinder eliminates tedious hand filing, carving, buffing, polishing and scratch brushing. Does delicate, accurate work in fraction of time. Packs plenty of power and speed—24,000 R P M. Powered with fully universal G. E. motor. Of streamline design—only 6½" in length. Has approved Underwriters' cord. Collet chuck with capacity up to ½". 110-V A.C. or D.C. current, 60 cycles or less. Has many special features including New Departure ball bearings, shock proof motor case, adequate cooling fan, push-button switch. Also available in lighter "Streamline" model at \$9.95 and in complete Heavy Duty Grinder Kit at \$22.95.

Send for  
Complete  
Circular

giving full details, specifications and prices on DURO Hand Grinders—also for catalog of complete line of DURO Machine Tools.

# DURO TOOLS

MACHINE TOOL DIVISION

ALSO MAKERS OF DURO HAND TOOLS

Duro Metal Products Company  
2453 N. Kildare Ave., Chicago, Ill.

Gentlemen: Send me complete circular on DURO Hand Grinders—also FREE copy of latest DURO Catalog.

Name \_\_\_\_\_

Address \_\_\_\_\_

City \_\_\_\_\_

State \_\_\_\_\_



# A PROTRACTOR-RULE

## and a REPAIR HANDBOOK



**SMOOTH-ON  
CEMENTS**



Motor Car and Boat  
Home, Factory and  
Power Plant

*both sent*  
**FREE**

*if you mail the coupon*

Here are TWO handy helps every householder and handy man should have, and which are available without charge to the readers of this magazine.

1—A durable protractor, with black letters on a white background for greatest legibility, with angles reading in both directions, and with an inch scale on the straight side.

2—The 40-page Smooth-On Handbook, with simple instructions for time-saving, labor-saving and money-saving repairs to household and auto equipment, etc. Illustrated by 170 diagrams.

The instructions in this handbook are based on the experience of thousands of mechanics and repair men, and include much information not to be found in any other publication. Some of the subjects covered:

How to seal cracks in boilers, stoves, water heaters, radiators, pipes, auto engine water jackets, gear cases, etc.

How to stop leaks at seams, bolts, rivets, threaded or flanged joints, etc.

How to tighten loose parts of furniture, apparatus, fixtures, utensils, tools, etc.

How to waterproof concrete, brick or stone floors, walls, cisterns, pools, etc.

Get Smooth-On No. 1 in 1½-lb., 7-oz. 1-lb. or 5-lb. container from your dealer, or if necessary from us. For your protection, insist on SMOOTH-ON used by mechanics and repair men since 1895.

Send the coupon TODAY to be sure to receive the free protractor and repair handbook before the supply is exhausted.

SMOOTH-ON MFG. CO., Dept. 5B  
574 Communipaw Ave., Jersey City 4, N.J.  
Please send the Protractor and the Smooth-On Repair Book.

Name.....  
Address.....  
11-43.....



*Do it with* **SMOOTH-ON**

# Mortite UTILITY TAPE

## BETWEEN YOU AND THE COLD

New pliable plastic stops leaks, saves fuel. Weatherstrips windows, doors, baseboards — caulks casements; makes packing, gaskets.

### EASY TO APPLY

Unrolls like ribbon. Just press into place and it stays put. Does not crack, chip, dry out or shrink.

About 80 ft. to box. At Hardware, Plumbing, Mill Supply Dealers or \$1.25 prepaid (\$1.40 west of Rockies).


Send for Circular



## STOPS THAT DRIP

A sure cure for condensation drip from tanks, pipes, walls, ceilings, etc. Apply with brush, trowel or spray. At stores or \$1.90 for 1 gal. prepaid (\$2.10 west of Rockies). Free Circular.

**J. W. MORTELL CO.** 534 Burch St. KANKAKEE, ILL.



**BUILD THIS MODEL**  
An accurate 13" scale model of the famous PT Complete kit includes all fittings — Only \$8.

**GET THIS BOOK** — the only one of its kind Full of detailed drawings and photographs with instructions for building and rigging ship models.

**SHIP MODELS ILLUSTRATED** postpaid for only \$2.

**MARINE MODEL CO., Dept. P, 28 W. 15th St., N.Y.C.**



## SELL ELECTRIC FENCE

The New HIBALL FENCE KIT is the best yet. Sell dealers or direct. Salesmen make up to \$188.44 per year. Good territory open. 2 Samples, \$3.00.

**LEJAY MFG. CO.** 2823 Lejay Bldg., Minneapolis, Minn.



## OTTAWA TRACTOR SAW

### Falls Tree—Cuts Log

Uses Power Take-off any tractor. Direct drive. Long stroke. Saws fast. Easy on fuel. Thousands of satisfied users. Big labor saver. Low in Price.

**OTTAWA MFG. CO., D1101 Forest Ave., OTTAWA, KANSAS**


Write for FREE Book and Prices



## WINN'S NEW IDEA HOME LABORATORY — CHEMICAL KITS

For High School & College Students. Send for Free Literature and Retail Supply Catalog. **J. H. WINN MFG. CO., Dept. 111 124 W. 23 St., New York 11, N.Y.**





# FILES TO MEET ALL YOUR WARTIME NEEDS

**W**ITH all the repairing and overhauling that's necessary... all the worn out parts, tools and broken down equipment that have to be rebuilt and made to serve for the duration... you'll be filing angles, corners, keyways and slots one day, enlarging concave openings another day, finishing flat surfaces, and so on. At one time you will be filing very hard metals such as stainless and alloy steels. Then, again, soft metals such as lead, aluminum and brass. Or non-metallic materials as fiber, leather, plastics, slate and wood.

There are NUCUT Machinists' Files for general machine shop work. NUCUT Saw and Mill Files for sharpening saws and for finishing. NUCUT Swiss Patterns for delicate filing with a high degree of precision. Also NUCUT Rasps for wood and similar soft materials.

These files are of all lengths... in bastard cut, second cut and smooth cut... and of varying shapes or cross-sections to best meet the specific job in hand. Your nearest dealer will be glad to suggest a practical assortment that will meet your individual needs.

**HELLER BROTHERS COMPANY** • Newark, New Jersey, Newcomerstown, Ohio  
America's Oldest File Manufacturers—Good Tools Since 1836

## FREE MANUAL on files and filing

This handbook is yours for the asking. Within its 64 pages, you can find the information you need for selecting a file of the right length, shape and cut for practically every filing need.



# PROPER HARDNESS IN STEEL MEANS EXTRA SHAVING COMFORT AND LONGER LASTING

## BLADES


Guaranteed by  
**GLIDER BLADE COMPANY**  
Newark New Jersey

**FIVE  
BLADES  
for  
25c**

**Professional  
BLADES**  
FREE SHARPENING • TEST RESISTANCE

INSTRUMENT  
FOR TESTING  
THE HARDNESS  
OF STEEL





## WARTIME TRAFFIC CALLS ON BURD EXPERIENCE

Burd's generation of experience gained in designing and manufacturing piston rings for every conceivable kind of internal combustion engine has been drafted to war service. In addition to producing piston rings to keep our fighting men in the home front, Burd is being called on to make special rings for our military machines. The very primary feature of this feature which pertains to the nature of the machine is the fact that the rings are fitted on the shop floor and are guaranteed against any sticking or breaking by a system of mechanical inspection. This feature is the result of the fact that thousands of mechanics need for the full length of the story and free books (one cent).

**BURD PISTON RING CO., Dept. PS, Rockford, Ill.**

### COUPON BRINGS HAND BOOK FREE

**BURD PISTON RING CO., Dept. PS**  
Rockford, Illinois

Send me, please, a Handy Handbook and your pocket car or money saving book as well as information of Great Piston Rings.

Name \_\_\_\_\_

Address \_\_\_\_\_

City \_\_\_\_\_ State \_\_\_\_\_



## GS TOOL CHESTS

GS Tool Chests are used by thousands of mechanics to safeguard their precision tools. Illustrated is the Chest 20"x30"x13 1/2" with 7 drawers and TWO LOCKS for complete safety. Price \$13.50 plus shipping charges. QUICK DELIVERY to workers in war plants. Extra discounts on quantity orders. **INQUIRE WHEN YOUR ORDER IN TODAY**

Write for four page folder.


**GEO. SCHERR CO.**

1289 S. LAFAYETTE ST. • NEW YORK 13

To safeguard and preserve the American way of life—buy Defense Savings Bonds and Stamps



## SOLDIERS, SAILORS & WAR WORKERS



Your Watch with a Broken Crystal Is Useless  
Exposed to Damage from Glass and Dust.

**PROTECT YOUR WATCH**—Avoid costly repairs. Go to any jeweler—ask for a **G-S FLEXTO CRYSTAL 100% BREAK-PROOF**—Any size. Any shape. Can be fitted while you wait.

Mfgs. of military water-proof watches, gauges, instruments now use **G-S FLEXTO** made of **GOV'T APPROVED PLASTICS**. Same materials are used for all **G-S FLEXTO CRYSTALS**.

**GERMANOW-SIMON MACHINE COMPANY, Rochester, N. Y.**

## BUILD ARC WELDER FROM OLD GENERATOR

For Light or Heavy Work 30-200 amperes. Complete **PLANS 35c**. Send today and we will include **FREE** our **BIG Catalog** of **LEJAY MFG. Co., 1223 Lejay Bldg., Minneapolis, Minn.**



## HIGH BLOOD PRESSURE

### A DANGER SIGNAL

Often associated with Hardening of the Arteries, a Stroke, Paralysis, Heart Trouble, Kidney Disease, and other grave complications. Resultful treating methods of the **BALL CLINIC** have proven dependable for nearly a quarter of a century. Send for **FREE Blood Pressure Book** today. No obligation.


**BALL CLINIC, Dept. 5160, Excelsior Springs, Mo.**



**SAVE**

## RUBBER

Save in its cuts, heels, worn spots in tires. Will also mend shoes, raincoats, boots—any thing that needs rubber.



**MEND the HOLE for 1¢**

**SPREAD ON like butter**. Dries tough overnight. Flexible. Non-slip. Waterproof. Won't come off—guaranteed.

**So-Lo** **BY MAIL** **1¢**



## NOW a DYNAMIC HEAVY DUTY INDUSTRIAL WELDER

### AMAZINGLY SIMPLE & EASY TO OPERATE

This portable Dynamic Welder—easily carried right to the job—plugs into any convenient, properly wired 110 volt light circuit—works on Iron, Steel, Brass, Bronze and other metals. Has all the features and controls of a high grade electric arc work you would think only possible with a larger, more expensive machine.

### DESIGNED TO DO HIGH GRADE WELDING INEXPENSIVELY

Maintenance Men, Farmers, Mechanics, Machine Shops, Foundries, Auto Rental Repair and Job Welding Men, using the Dynamic find it so indispensable and useful that they cannot afford to be without it. If inexperienced, you can easily learn to do a variety of high grade welding jobs by following the practical, simplified operating and welding instructions furnished.

**DYNAMIC WELDER CO., 2226-N Silverton Road, Chicago 16, Ill.**

for Only **\$23.50**

**COMPLETE**

**Saves VALUABLE TIME and MONEY!**

Once you see a Dynamic in operation you won't be without it. Its simplicity will amaze you. In a year the Dynamic only costs you about 6¢ a day.

Comes complete with helmet, rods, cables, electrode holder and operating instructions, etc.

Write today for free priority assistance and particulars on how to qualify for one of these amazingly low-priced welders. Act now while there are still available. Get details on our 10-day trial offer.





# SAVE Valuable Paint Brushes!

After every use a DIC-A-DOO PAINT BRUSH BATH keeps bristles flexible, useful, new! DIC-A-DOO Brush Bath will soften and cleanse discarded, hardened brushes—right down to the heel. DIC-A-DOO restores an luster to bristles—does not leave them limp or flabby. 5¢ pkg. cleans several brushes. At paint, hardware and 5 & 10¢ stores. Patent Ceram Corporation, Geneva, N. Y.—makers of the famous DIC-A-DOO PAINT CLEANERS.

**DIC-A-DOO  
PAINT BRUSH  
BATH**



## USE YOUR BENCH SAW

With our six in. tool steel cutters. Make moldings, casings, drop and tables, grooves, beading & cutting 1" wide \$1.50 1 1/2" \$1.75. Free paid State also hole. List & folder free. John A. Sandstrom, Box 517, Stew, N. Y.


Land or Water, "DUCKS" Know Their Way



HULL MFG. CO., P. O. Box 246-E11, Warren, O.

## WITTE DIESELECTRIC PLANTS

A. C.  
and  
D. C.



For 73 years the WITTE plant has been serving America and the World. Today WITTE is producing only for the War Effort. After Victory these improved WITTE plants will be available to all.


Remember us then.

**WITTE ENGINE WORKS**  
LARGEST BUILDER OF SMALL DIESELS  
KANSAS CITY, MO., U. S. A.

# A NAME WORTH LOOKING FOR when you need quality tools



THE NORMAL Millers Falls line includes hack saw frames in 18 models, each with its special features of serviceability, convenience and economy. "Best of all breeds" for most tool users is No. 48 (illustrated), a higher-quality frame of unusual excellence in design, ruggedness, and value. Rigid, fine balance; polished and buffed finish; comfortable checked Lumarith unbreakable handle. Adjustable for 8 to 12 in. blades.



IDEAL companion for No. 48 is Tuf-Flex, the most efficient and economical general-purpose hand saw blade ever developed. Won't break, won't strip. Bites cleanly through tough rods or thin tubing. A good example of what we mean by "Millers Falls Quality."

STANDARD items of excellent reputation in the normal Millers Falls line are 52 sizes and styles of cold chisels and punches, hammer-forged of high grade steel selected for its extreme toughness. Superior heat treating—a Millers Falls specialty—makes these items uniformly the finest quality. Look for the Millers Falls name when you buy, you'll decide the results are worth extra care in selection.



## MILLERS FALLS TOOLS

MILLERS FALLS  
COMPANY

Greenfield, Mass.  
U.S.A.







# MEDICO FILTERED SMOKING

**SENSATIONAL PIPE FILTER  
ALSO IN CIGARETTE  
AND CIGAR HOLDERS**

No wonder millions have switched to this amazing and revolutionary filter invention—the greatest improvement ever known in pipes, cigarette and cigar holders.

Inside of cellophane exterior are 66 mesh screen "baffles" which whirlcool smoke—retain flakes and slugs, minimize juices, raw mouth, and tongue-bite. Improves taste and aroma of your favorite smoke.

This filter is the "heart" of Medico Filtered Smoking. When discolored, put a fresh one in your pipe or holder. Costs only ONE CENT. Do not miss the benefits of mild, sanitary, Filtered Smoking.

Something wonderful goes on inside

GENUINE  
FILTERS  
FOR MEDICO  
PACKED  
ONLY IN  
THIS RED AND  
BLACK BOX



X-RAY VIEW OF FILTER

**\$1.00**

## DRILL PRESS OWNERS!

**HERE'S 1 TOOL WITH 5 DISTINCT USES**



**THE BARRON MULTI-PURPOSE  
ROTARY WOOD PLANER**

PLANES & SURFACES • PANELS & BEADS • ROUTES & GROOVES • RABBETS • TENONS **\$7.50** COMPLETE

Converts ANY drill press into a time saving, low cost planer, paneler, bender, etc. Surface finishes all types of tough grained and knotty surfaces to agree smoothness. Safe! Guaranteed harmless to drill press. Thousands now in use. **SOLD ON MONEY BACK GUARANTEE.** Full refund on 3 day trial. Shipped prepaid on receipt of \$7.50—or C.O.D. YOU RISK NOTHING. Free literature.

**BARRON TOOL CO., INC.**  
370 Architects Bldg., Detroit 1, Mich.

**STEEL TOP AUXILIARY  
DRILL PRESS TABLE**

Has 500 sq. in. smooth working surface. Equipped for shaper and many other important workshop uses—a real buy at **\$5.95**




## H&R WARTIME LINE Available Now for Essential Use



**THE H&R REISING  
SEMI-AUTOMATIC RIFLE**

Caliber .45, bottom-fed from 12 or 20 cartridge clip; fires as fast as trigger is pulled; effective range 400 yards, weight with magazine 7 lbs. Excellent weapon for police, guard or military use.




**H&R STANDARD**

Single barrel shotgun, 12 gauge. Unique action design takes up its own wear



**H&R FLARE PISTOLS  
MARK IV; MARK VI**

For ball or parachute flares; 37 mm. and 1" bores.



**H&R DEFENDER .38**

Five shot, .38 caliber, rugged, precise, general purpose revolver



**H&R SPORTSMAN**

Nine shot, .22 caliber. World famous for crisp action and balance.

WRITE for your free copy of the Manual of the H&R Reising Sub-machine Gun. Also now in preparation—a more detailed catalog of the H&R wartime line covered briefly here; we'll reserve a copy for you at your request—will mail it as soon as it's off the press. Harrington & Richardson Arms Company, Worcester 2, Mass., U.S.A.



**H&R**  
FINE FIREARMS

*For Sportsmen, Police, and the Military*

Buy War Savings Bonds and Stamps regularly.





"Yankee" Fine Mechanics' Tools have contributed to the efficiency of American production for nearly half a century... are now working day and night to speed the output of war. Without proper care, however, no fine tools can withstand the punishment of all-out production—and "Yankee" Tools are no exception. Their ingenuity will save time and trouble on the job—if you take the time and trouble to "Treat 'em Right!"

**"YANKEE" TOOLS**  
 make good mechanics better  
 North Bros. Mfg. Co., Phila. 33, U.S.A.  
 Established 1880

Makers, also, of "Yankee-Handyman" Tools



Waiting orders for the dash  
 Our hero thought he'd take a splash  
 The land's best bet  
 Was the Sultan's pet  
 But the MP's took a flash.



You can't buy them as before  
 When it's over there'll be more

Buy War Savings Bonds and Stamps regularly.

**IT'S Free**  
**WARDS 1943**  
**PHOTOGRAPHIC CATALOG**

Most everything you'll need, you'll find in our big 1943 Catalog...and at Wards moderate prices...either cash or Time Payment Terms. Order now and pay later. Get what you want while our stocks are still complete. Act Now...Get this money-saving 36 Page Free Catalog.

**EQUIPMENT AND SUPPLIES**  
**EXHIBITION FILM ACCESSORIES**

*Montgomery Ward*  
 PHOTOGRAPHIC DEPT. PZ-1143A, CHICAGO, ILLINOIS

**DIE-LESS DUPLICATING**

Many small parts can be formed without dies to duplicated accuracy of .001" with DIACRO Precision Machines. — Benders, Brakes, Shears—saving Man Hours and Critical Materials. Requires priority of A-1-A or higher. Write on business letterhead for catalog, or state if employed in War production.

**O'NEIL-IRWIN MFG. COMPANY**  
 242 Elm Avenue S. Minneapolis 15, Minn.

**SHEAR BENDER**  
**FRAME**

**IT'S FUN TO MAKE THINGS OF WOOD**

**CONSTANTINE'S MANUAL TELLS HOW TO DO IT**  
 Wood work or expert work and many helpful hints and tips on everything woodwork, cabinet making, carpentry, etc. from care and selection over 100 different kinds of wood and how different items for you. **ALL AT MONEY SAVINGS \$2.95**. The new ideal learning manual and chart of 100 of the most woods in natural color. A source of help for anything a wood worker can do. Quantity of only 25 in stamps or run. The refund or credit on that order so Manual costs you nothing.

**ALBERT CONSTANTINE & SON, INC.**  
 793 P. O. Box 1111th St. New York N. Y.

**ARMSTRONG TOOL HOLDERS**

enabled American industry to change to war production over night. They are the permanent multi-purpose tools used by 95% of the machine shops and tool rooms on the planet and shapers—the tools used to make dies and to build production machines. They are the tools you will want for your own shop after the war—**ARMSTRONG TOOL HOLDERS** for industry. **ACE Tool Holders** for home work shops.

**ARMSTRONG BROS. TOOL CO.**  
 "The Tool Holder People"  
 579 N. Franklin Ave. Chicago, U. S. A.

**TURNING**  
**THREADING**  
**BORING**  
**CUTTING-OFF**

**LEPAGE'S GLUE**

**LEPAGE'S MODEL AEROPLANE GLUE**  
**LEPAGE'S LIQUID SOLDER**



# YOU CAN EASILY MAKE Telescopes—Magnifiers—Photographic Gadgets and HUNDREDS of EXPERIMENTS with

## LOW COST LENSES

Big 10 Page Project and Idea Booklet with all sets—describes successful developments—points the way to new experiments.

**ALL LENSES NEW**, finely ground and polished, edges very slightly chipped—**A SALVAGE BARGAIN!**

**Set No. 301-N "Our Advertising Special"** 15 Lenses for \$1.00 Postpaid. For making your own powerful telescopes strong magnifiers, photo cells rifle scope telephoto lens **DUMMY FOCUSING CAMERA**. Kodachrome viewer stereoscopic viewer ground glass and enlarging focusing aids. For experimental optics, portraits of babies and small pets copying, ultra close-up shots, and many many other uses.

**Set No. 302-N "The Gadgeteer's Delight"** 25 Lenses for \$5.00 Postpaid. Contains all the lenses in the above set plus twenty more expensive lenses increasing your field of experiment and gadget making. All our lenses are neatly packed and marked.

**Set No. 310-N "The Experimenter's Dream"** 75 Lenses for \$10.00 Postpaid. Contains all the lenses in the above sets plus 35 others that makes this a sensational buy. The variety of lenses in this set will enable you to conduct countless experiments and build a wide variety of optical equipment. Here is a real worthwhile investment in many hours of pleasure and benefit.

Shopmen! Servicemen! Amateur Photographers!  
Stamp Collectors! Experimenters Everywhere!

Get in on this Lens Salvage Bargain Now! Order Today!

**EDMUND SALVAGE CO.**

41 W. Clinton Ave., P.O. Audubon, N. J.



UP 1 1/2" LATHE CAPACITY TO 3/4" . . .  
AN INCREASE OF 50% WITH THE NEW


**SPEEDICHUK** and

**"PRECISION" BREN COLLET**

Revolutionary new invention fits Atlas, Logan, B" South Bend Lathes and others with 1 1/2" AN Thread Spindle Nose having a No. 3 Morse Taper on its de. Write for Catalog "Y" and name of nearest dealer.

**GENERAL DIE-STAMPING TOOL COMPANY**  
265 Canal Street • New York 13, N. Y.

## NEW Things CLAMPS



**GRAND  
QUICK  
LOCKET**

The Magic Clamp  
with Trigger Release

Unequaled for light fast work. Setting the pace in war production. Finger operated. Its long leverage, cam-action converts a press of the thumb into a firm, tight grip. Spring tension and trigger teeth hold firm ratchet grip on screw which releases instantly with trigger pressure by thumb or finger so that screw may be slipped to any desired position with a single motion—or, may be immediately reclamped to other work of the same thickness without further screw adjustment. Swing up, locking lever, and sent makes it absolutely "non-creeping" and assures firm grip on any parallel, slanting or rounded surface. Free acting swivel with fibre face that prevents marring or scarring. Made also with fibre jaws for aluminum and other softer metals. Ask about the complete **GRAND Line of Speed Clamps**.

Write for Circular

**GRAND SPECIALTIES COMPANY**

Est. 1921

Grand Avenue at Troy, CHICAGO 22, U. S. A.



"Much credit for the successful maintenance work on both our commercial and military planes is due to the dependability of Snap-on tools, with which the majority of our mechanics work."

*Thomas D. Brooks*

Superintendent of Maintenance  
CHICAGO AND SOUTHERN AIR LINES



## ANOTHER GREAT AIR LINE Endorses Snap-on Tools!

With its far-flung commercial routes supplying swift and dependable transport over the strategic heart of America . . . with giant hangers busily engaged in important modification work for the Army Air Forces . . . Chicago and Southern Air Lines know the importance of good tools in every phase of aviation. Says Thomas D. Brooks, Supt. of Maintenance:

"Chicago and Southern mechanics assigned to both commercial airline and military transport, as well as modification work, have found Snap-on tools adaptable to work where there is very little room available, where the fitting of a tool is of the utmost importance to a dependable job, and where the strength of the tool saves time and in many cases prevents injuries."

Snap-on tools are endorsed by leading air lines, foremost plane manufacturers and engine builders. Their accuracy, flexibility and ease of application meet today's urgent need for speed, and more speed. In victory-gear industry throughout America you'll find them in the hands of men who know tools . . . the choice of better mechanics!

**SNAP-ON TOOLS CORPORATION, Kenosha, Wis.**











# MOTORISTS *Wanted!*

TO MAKE THIS **UNIQUE TEST...**

## of **GAS SAVINGS**



**Car Owners:** You are invited to make a gas saving road test with the Vacu-matic on your own car, with the absolute understanding that unless it proves to you that it will save you up to 30% on gas and improve your car performance, the test will cost you nothing. Investigate this remarkable discovery that trims dollars off gasoline bills—gives you worthwhile gas savings—more power—quicker starting—more miles on less gas.

### Automatic Supercharge Principle

Vacu-matic is *entirely different!* It operates on the supercharge principle by automatically adding a charge of extra oxygen, drawn free from the outer air, into the heart of the gas mixture. It is entirely automatic and allows the motor to "breathe" at the correct time, opening and closing *automatically* to save dollars on gas costs.

### Proven By Test

In addition to establishing new mileage records on cars in all sections of the country, the Vacu-matic has proven itself on thousands of road tests and on dynamometer tests which duplicate road conditions and record accurate mileage and horse power increases.

### Fits All Cars—Easy to Install

Vacu-matic is constructed of six parts assembled and fused into one unit, adjusted and *sealed at the factory*. Nothing to regulate. Any motorist can install in ten minutes. The free offer coupon will bring all the facts. Mail it today!

**The Vacu-matic Co., Wauwatosa, Wis.**

### Sworn Proof of Gas Savings

This certifies that I have carefully read 300 original letters received from Vacu-matic users testifying to gas savings up to 30%, many reporting added power, smoother running, and quicker pick-up. These letters are just a small part of the larger file of enthusiastic user letters that I saw at the company offices.



Signed

*Thomas J. Kelly*  
Sales Representative

### AGENTS Get Yours FREE For Introducing

Vacu-matic offers a splendid opportunity for unusual sales and profits. Every car, truck, tractor, and motorcycle owner a prospect. Valuable territories now being assigned. If you help us introduce it to a friend, you can obtain your own free. Check and mail coupon today.

### SEND THIS *Free Offer* COUPON

THE VACU-MATIC COMPANY  
7617-844 W. State St., Wauwatosa, Wis.

Please send full particulars about VACU-MATIC, also how I may obtain one for my own car FREE. This does not obligate me in any way.

Name .....

Address .....

City..... State.....

☐ Check here if interested in Agency Proposition.





# Women

## ARE TAKING THIS WAR SERIOUSLY

★  
BUY U.S.  
WAR  
BONDS  
★

### SOUTH BEND LATHES

With grim determination thousands of American women are doing their best to fill men's shoes. Eagerly they bend their shoulders to wartime tasks—for no sacrifice is too great if it hastens the return of their men from the fighting fronts.

In hundreds of vital war plants, women are operating South Bend Lathes with surprising results. On all kinds of jobs, they have kept up production and maintained established standards of precision. In some factories whole batteries of South Bend Lathes are humming under the guidance of feminine hands.

Since World War I, women operators have preferred South Bend Lathes. The convenient controls are well suited to their sensitive touch. They



like the fully enclosed design. And, most of all, they appreciate the ease of operation that prevents fatigue and makes the workday seem shorter.

South Bend Engine Lathes and Toolroom Lathes are made in five sizes: 9" to 16" swings, with 3' to 12' bed lengths. The Turret Lathes are made with 9" and 10" swings. Write for Catalog 100C which describes all sizes and types of South Bend Lathes.

### SOUTH BEND LATHE WORKS

Lathe Builders for 37 Years  
SOUTH BEND, INDIANA

POPULAR SCIENCE

Buy War Savings Bonds and Stamps regularly.

This One



HQSH-X7L-KF1S



# The National Educational Alliance Brings a "Great University" into Your Home The Higher Education You Need for Success

Organized to Help Millions Broaden Their Knowledge and Increase Their Opportunity for Earnings, the ALLIANCE Now Offers Its 57 FAMOUS EASY-READING COURSES in Book Form

## at amazingly low cost!

OVER 400,000 PEOPLE HAVE SUBSCRIBED  
TO THESE COURSES!

for  
**1¢ A LESSON!**

57 Complete Courses—1,585 Lectures!  
Prepared by 61 Educators from 47 Great Universities, in  
**THE POPULAR EDUCATOR LIBRARY**

**Accountancy.** E. A. Saliers, B.S., M.A., Ph.D., Louisiana State University.

**Aeronautics.** Theodor Von Karman, M.E., Ph.D.; Frank J. Malina, Research Fellow, California Institute of Technology.

**American History.** Harry Elmer Barnes, M.A., Ph.D., New School for Social Research.

**Anthropology.** Clark Wissler, A.B., Ph.D., LL.D., Yale University.

**Art and Architecture.** Ernest Pickering, B.Sc., M.Arch., University of Cincinnati.

**Astronomy.** Clyde Fisher, Ph.D., LL.D., American Museum of Natural History.

**Biology.** John H. Gerould, Ph.D., Dartmouth College.

**Business English.** John Presley Fife, B.A., M.A., Stevens Institute of Technology.

**Chemistry.** L. A. Goldblatt, Ph.D., University of Pittsburgh.

(Continued on opp. page)

POPULAR  
EDUCATOR  
LIBRARY

POPULAR  
EDUCATOR  
LIBRARY

VOLUME 1  
PAGES 1-100

NATIONAL  
EDUCATIONAL  
ALLIANCE

10 BIG VOLUMES

5,120 PAGES! 2,437 ILLUSTRATIONS!

**THINK OF IT!** In your own home now you can receive and enjoy instruction by eminent educators especially chosen by The NATIONAL EDUCATIONAL ALLIANCE from such great universities as Harvard, Pittsburgh, Oregon, M.I.T., Minnesota, Notre Dame, Princeton, Pennsylvania, and dozens of others . . . at the miracle rate of about **1¢ A LESSON!**

For the first time all 57 Famous ALLIANCE Courses are available in 10 superb volumes—the Popular Educator Library! The higher education you have always wanted is now yours at amazingly low cost!

**Just As In College You Study Only the Courses You Want**

Think of Studying Courses of Immediate Practical Value . . . ACCOUNTANCY, PSYCHOLOGY, ENGLISH, etc., for only a few cents each!

No matter what your present position and ambitions may be, the ALLIANCE Courses will bring you help to fit your particular needs—practical, positive help to carry you on to the job ahead—to higher earnings and greater accomplishments.

No longer need you believe the old saying that "there is no royal road to knowledge," for the ALLIANCE has surveyed and paved the path for you—and has made a higher education available to all at extremely low cost.

Take, for example, a subject like PSYCHOLOGY. If you had to attend lectures on this subject in person at a college it would cost you hundreds of dollars—even a text book would cost you three or four dollars. Yet The NATIONAL EDUCATIONAL ALLIANCE brings you a complete survey of this science, in 38 lessons, by an eminent educator from Northwestern University—AT A TOTAL COST OF ABOUT 38 CENTS!

**57 Practical Courses for Everyone—Business Man, Mechanic, Office-Worker, Teacher, Parent, Student**

Courses in Mathematics, Languages, Chemistry, Psychology, Shorthand and Typing, Business English, Physics, History, Music, Drawing and Design, Radio, and dozens more presented in this great educational library.

## LAST CALL!

The present edition will very soon be exhausted. Future editions will be printed on less substantial paper and sold at a higher price. Buy now and act at once!

Copyright by the National Educational Alliance, Inc.  
**Examine THE POPULAR EDUCATOR LIBRARY Free!**



**ROAD  
CLOSED**

## by the Fighting Engineers

When there are tanks to be stopped—watch the Engineers! "Tank block—rush it!" is the order... and the photograph at the right (an actual training test) shows the result. Stopping tanks is only a *part* of the job of the fighting U. S. Engineers. And, like men in all the other services, you're apt to find that when an Engineer lights up a cigarette—it's a Camel.



# They've Got What it Takes!

CAMELS SURE  
STAND THE TEST OF  
STEADY SMOKING!  
THAT SWELL **FLAVOR**  
ALWAYS HOLDS UP...  
AND THEY'RE  
EXTRA  
**MILD!**



## First IN THE SERVICE

The favorite cigarette with men in the Army, the Navy, the Marines, and the Coast Guard is Camel. (Based on actual sales records.)

## The "T-Zone"

where cigarettes are judged

How long since you've smoked a Camel? Give them a try today. Compare them critically... for taste... for your throat... for your "T-ZONE." We believe you will like the extra flavor that Camel's costlier tobaccos give. We believe your throat will confirm the findings of other Camel smokers. So try Camels in your "T-ZONE."



# Camels

R. J. Reynolds Tobacco Company, Winston-Salem, N. C.



# WANTED AT ON

## ★ Mathematically Trained Ages 18 to 45 and Over—for Army Home Front AND Fighting Front

This war calls for mechanical ingenuity in America's factories and for scientific efficiency on the battlefield. And mathematics is *basic knowledge* for all mechanical and scientific work. Thousands of mathematically trained men are now needed for the war effort. To

serve your country, to qualify for a bigger responsibilities, bigger opportunities, in the army, navy or air force—mathematics! Now you can master mathematics in your spare time—easily and quickly—at

### THE NATIONAL EDUCATIONAL ALLIANCE, INC.

now brings you this up-to-date home-study lecture course in

## PRACTICAL MATHEMATICS

**in 120 days—at a cost of only 35c a subject!**  
**IN PERIODICAL FORM**

**Prepared by specialists from leading universities**

**NO LONGER** need you shrink from the "bugaboos" of mathematics! No longer need you stand aside while better qualified men get all the "breaks" in your shop. No longer need you be lost "in the ranks" while mathematically trained men are given special service ratings. You can now learn how to put mathematics to work for you—how to use it for more rapid promotion, for a chance to stand out from the crowd, for maximum service to your country! No previous training or elaborate schooling is required to master this brand-new simplified course in mathematics.

**Starts With a Review of Simple Arithmetic and  
Takes You by Easy, Clearly Illustrated Steps and  
Sample Problems to the Most Advanced Applications**

This series of lectures in PRACTICAL MATHEMATICS comes to you in 14 periodical pamphlets, three each month—just like any magazine—at no more than the cost of a magazine! Each issue contains a group of 20 to 30 lectures, with sample workaday problems, self-examinations and answers.

The series starts right from the beginning with "refresher" lessons in basic arithmetic, so that even if you have done nothing with mathematics since your school days, you will soon be at home in your studies. From here the Course takes you, one by one, into the 14 branches of applied mathematics. Each group contains 20 to 30 divisions of each subject, under the directions of specialists in the field. Every step is carefully explained, frequently reviewed, and clearly illustrated. No previous knowledge on your part is expected or taken for granted. Each installment includes a quiz-and-answer supplement especially designed for self-education, so that working by yourself—without a teacher—you master every important branch of mathematics in a period of 120 days or sooner.

### **You Get Training In Actual Mathematical War Problems!**

This is not a dry, abstract, school-room course, but a practical training in the vital applications of mathematics. You learn how to use mathematics in the design, production and operation of guns and projectiles. You learn how to use mathematics in aerial and sea navigation. You learn how to apply mathematics in chemistry, mechanics, electricity, radio. You discover how you can use mathematics for short-cuts in daily shop problems, in the laboratory, in all kinds of figuring. You discover that Algebra, Geometry, Trigonometry, simple Calculus and other mathematical subjects, far from being mysteries, are simply ingenious methods for solving

mysteries. By devoting an hour a day to study, you will soon find yourself absorbing the essentials of mathematics with an ease and enjoyment you never thought possible! The Course will make clear to you many problems that have often puzzled you. You will find it stepping-stone to the kind of a job where others will come to you for explanation and advice—the kind of a job that means a real future!

### **How Is the Low Cost Possible?**

Ordinarily a Course of this scope would cost hundreds of dollars and take years at college. But the need and demand for mathematical training is today widespread and urgent—so urgent that all precedents of high cost and lengthy study have had to be drastically revised. The National Educational Alliance, with its resources and experience in bringing education to the millions, is the one organization eminently qualified to make this great undertaking possible. It has gathered a faculty in mathematics from America's leading universities—each a specialist in his field (see list on other side of flap)—to prepare the lessons in this reading course. And it has organized this course so that it comes to you in convenient installments—like any magazine—at no more than the cost of a magazine! Think of it—a practical easy, short course in mathematics at the cost of a magazine subscription—the greatest bargain in the educational world! See order form on other side of flap. National Educational Alliance, Dept. 8012, 37 W. 47th St., New York 19, N.Y.

Copyright, 1943, by the National Educational Alliance, Inc.

**ONLY 25c TO START—STOP WHENEVER YOU LIKE!**







**THERE'S NOTHING LIKE  
A GOOD CIGARETTE**

**So let's wish them the Very Best**

**YES...THE CIGARETTE WITH THE RIGHT  
COMBINATION OF THE WORLD'S BEST TOBACCOS**

**STRIDES AHEAD** in Mildness, Better Taste and  
Cooler Smoking because Chesterfields are made  
of the world's best cigarette tobaccos...plus the  
Right Combination to satisfy smokers everywhere.

**Remember in a cigarette — the Blend...the  
Right Combination — that's the thing**



**AND HERE THEY ARE... again in the cheerful  
Chesterfield Christmas Red — the cigarette gift that SATISFIES  
with the best in Smoking Pleasure.**